



PB98-144603

FINAL REPORT

An Evaluation of the MICHIGAN URBAN DIAMOND INTERCHANGE with respect to the SINGLE-POINT URBAN INTERCHANGE

by

Paul B. W. Dorothy

and

Thomas L. Maleck, Ph.D., P.E.

December, 1997



COLLEGE OF ENGINEERING

MICHIGAN STATE UNIVERSITY

EAST LANSING, MICHIGAN 48824

MSU IS AN AFFIRMATIVE ACTION/EQUAL OPPORTUNITY INSTITUTION

REPRODUCED BY:
U.S. Department of Commerce **NTIS**
National Technical Information Service
Springfield, Virginia 22161

Technical Report Documentation Page

| | | | |
|--|-------------------------------------|---|-----------|
| 1. Report No. | 2. Government Accession No. | 3. Recipient's Catalog No. | |
| 4. Title and Subtitle An Evaluation of the Michigan Urban Diamond Interchange with Respect to the Single Point Urban Interchange. | | 5. Report Date December 1997 | |
| | | 6. Performing Organization Code | |
| | | 8. Performing Organization Report No. | |
| 7. Author(s) Dorothy, Paul & Maleck, Thomas L. | | 10. Work Unit No. | |
| 9. Performing Organization Name and Address Michigan State University Civil & Envir Engineering 3546 Engineering Building East Lansing, MI 48824 | | 11. Contract or Grant No. | |
| | | 13. Type of Report and Period Covered Final Report | |
| 12. Sponsoring Agency Name and Address Michigan Department of Transportation Traffic & Safety Division 425 West Ottawa Lansing, MI 48909 | | 14. Sponsoring Agency Code MDOT 94-1521A | |
| | | 15. Supplementary Notes | |
| 16. Abstract The Michigan Department of Transportation (MDOT) is considering the much needed rehabilitation and upgrading of many interchanges found in urban environments. Thus, MDOT and Michigan State University (MSU) undertook a joint effort to evaluate the appropriateness of an urban interchange geometric configuration, the Single Point Urban Interchange (SPUI), as an alternative design to those presently used by MDOT. In particular, the Michigan Urban Diamond Interchange (MUDI) and the traditional diamond were investigated. A field review was conducted to collect information about the geometric design, signal operation, pedestrian control and pavement markings of SPUIs, as none currently exist in Michigan. The field review showed that the design and operation of SPUIs vary greatly from state to state. Thus, the SPUI and MUDI designs were computer modeled to facilitate a comparison of their respective operational characteristics. A traditional diamond was also modeled to generate a frame of reference. The results showed that the SPUI operation is adversely affected with the addition of frontage roads. MUDI operation, in most situations, is superior to that of either a SPUI and diamond interchange configuration. Also, there was less migration of delay to downstream intersections with a MUDI configuration than with either a SPUI or diamond. Finally, MUDI operation, in most situations, is insensitive to the proximity of the closest downstream node, while the SPUI operation is sensitive. | | | |
| 17. Key Words interchange design geometric design simulation modeling | | 18. Distribution Statement | |
| 19. Security Classif. (of this report) | 20. Security Classif (of this page) | 21. No. of Pages 138 | 22. Price |



NOTICE

This document is disseminated under the sponsorship of the Michigan Department of Transportation and the United States Department of Transportation in the interest of information exchange. The sponsors assume no liability for its contents or use thereof.

The contents of this report reflect the views of the authors who are solely responsible for the facts and accuracy of the material presented. The contents do not necessarily reflect the official views of the sponsors.

The State of Michigan and the United States Government do not endorse products or manufacturers. Trademarks or manufacturers' names appear herein only because they are considered essential to the objectives of this document.

This report does not constitute a standard, specification or regulation.

TABLE OF CONTENTS

| | |
|--|-----|
| LIST OF TABLES | v |
| LIST OF FIGURES | vii |
| 1.0 INTRODUCTION | 1 |
| 2.0 OPERATION AND DESIGN OF THE MICHIGAN URBAN DIAMOND INTERCHANGE (MUDI) | 7 |
| 3.0 OPERATION AND DESIGN OF THE SINGLE POINT URBAN INTERCHANGE (SPUI) | 9 |
| 4.0 STATE OF THE PRACTICE | 10 |
| 4.1 Literature Review..... | 10 |
| 4.2 AASHTO E-mail Survey | 12 |
| 4.3 Telephone Survey | 13 |
| 5.0 FIELD REVIEW OF THE SPUI | 15 |
| 5.1 Geometric Design | 16 |
| 5.2 Signal Operation | 21 |
| 5.3 Pedestrian Control..... | 23 |
| 5.4 Pavement Markings | 24 |
| 5.5 Land Use/Landscaping..... | 26 |
| 5.6 Conclusions from the Field Review..... | 28 |
| 6.0 METHODOLOGY | 30 |
| 6.1 Selection of the Computer Model | 30 |
| 6.2 Network Configuration | 32 |
| 6.3 Signal Operation | 39 |
| 6.4 Variables and Measures of Effectiveness | 46 |
| 7.0 SIMULATION RESULTS | 50 |
| 7.1 Interchange Performance without Frontage Roads..... | 50 |
| 7.2 Migration of Delay without Frontage Roads | 55 |
| 7.3 Interchange Performance with Frontage Roads..... | 60 |
| 7.4 Migration of Delay with Frontage Roads | 70 |
| 7.5 Sensitivity to Proximity of Closest Downstream Node | 70 |
| 8.0 CONCLUSIONS | 81 |
| 9.0 REFERENCES | 82 |

APPENDICES

APPENDIX A: TABULAR PRESENTATION OF SIMULATION RESULTS 83

APPENDIX B: GRAPHICAL PRESENTATION OF SIMULATION RESULTS103

LIST OF TABLES

| | |
|--|----|
| Table A.1: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial | 83 |
| Table A.2: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial | 84 |
| Table A.3: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial | 85 |
| Table A.4: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial | 86 |
| Table A.5: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, without Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial | 87 |
| Table A.6: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, without Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial | 88 |
| Table A.7: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial | 89 |
| Table A.8: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial | 90 |
| Table A.9: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial | 91 |
| Table A.10: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial | 92 |
| Table A.11: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial | 93 |

| | |
|---|-----|
| Table A.12: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial | 94 |
| Table A.13: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.2 kilometers (3/4 mile), 5-lane Arterial | 95 |
| Table A.14: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.2 kilometers (3/4 mile), 7-lane Arterial | 96 |
| Table A.15: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.2 kilometers (3/4 mile), 5-lane Arterial | 97 |
| Table A.16: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.2 kilometers (3/4 mile), 7-lane Arterial | 98 |
| Table A.17: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 0.8 kilometers (1/2 mile), 5-lane Arterial | 99 |
| Table A.18: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 0.8 kilometers (1/2 mile), 7-lane Arterial | 100 |
| Table A.19: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 0.8 kilometers (1/2 mile), 5-lane Arterial | 101 |
| Table A.20: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 0.8 kilometers (1/2 mile), 7-lane Arterial | 102 |

LIST OF FIGURES

| | |
|---|----|
| Figure 1: Typical Single Point Urban Interchange (SPUI) Configuration without Frontage Roads | 2 |
| Figure 2: Typical Single Point Urban Interchange (SPUI) Configuration with Frontage Roads | 3 |
| Figure 3: Typical Michigan Urban Diamond Interchange (MUDI) Configuration with Frontage Roads | 4 |
| Figure 4: Typical Diamond Interchange Configuration with Frontage Roads | 5 |
| Figure 5: SPUI with cross-road going over the freeway with all signal heads located on a single overhead tubular beam. Minnesota | 17 |
| Figure 6: Confused driver (car with lights on) stopped in middle of a SPUI while traffic proceeds on either side | 18 |
| Figure 7: U-turn lane accommodates large trucks | 18 |
| Figure 8: Dual left-turning traffic on the off-ramp is backing up, blocking right-turning traffic | 21 |
| Figure 9: Pavement marking overlap creates driver confusion | 24 |
| Figure 10: "Runway" lighting to help illuminate the turning path. Note buildup of debris | 25 |
| Figure 11: Typical Landscaping of a SPUI in Phoenix, AZ | 27 |
| Figure 12: Typical Diamond Interchange Configuration with Frontage Roads | 33 |
| Figure 13: Link/Node Diagram for Diamond Configuration..... | 34 |
| Figure 14: Typical Michigan Urban Diamond Interchange (MUDI) Configuration with Frontage Roads..... | 35 |
| Figure 15: Link/Node Diagram for MUDI Configuration..... | 36 |
| Figure 16: Typical Single Point Urban Interchange (SPUI) Configuration with Frontage Roads | 37 |
| Figure 17: Link/Node Diagram for SPUI Configuration..... | 38 |
| Figure 18: Phasing Diagram for MUDI Configuration..... | 42 |

| | |
|---|----|
| Figure 19: Phasing Diagram for MUDI Cross-overs..... | 43 |
| Figure 20: Phasing Diagram for SPUI Configuration without Frontage Roads | 44 |
| Figure 21: Phasing Diagram for SPUI Configuration with Frontage Roads | 45 |
| Figure 22: Phasing Diagram for Diamond Configuration | 47 |
| Figure 23: Interchange Area Total Time for 70% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 51 |
| Figure 24: Interchange Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 53 |
| Figure 25: Interchange Area Total Time for 30% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 54 |
| Figure 26: Interchange Area Total Time for 70% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 56 |
| Figure 27: Interchange Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 57 |
| Figure 28: Interchange Area Total Time for 30% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 58 |
| Figure 29: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 59 |
| Figure 30: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 61 |
| Figure 31: Interchange Area Total Time for 70% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 62 |
| Figure 32: Interchange Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 64 |
| Figure 33: Interchange Area Total Time for 30% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 65 |
| Figure 34: Interchange Area Total Time for 70% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 67 |
| Figure 35: Interchange Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 68 |

| | |
|---|-----|
| Figure 36: Interchange Area Total Time for 30% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 69 |
| Figure 37: Downstream Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 71 |
| Figure 38: Downstream Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 72 |
| Figure 39: Interchange Area Total Time for 70% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 74 |
| Figure 40: Interchange Area Total Time for 50% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 75 |
| Figure 41: Interchange Area Total Time for 30% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 76 |
| Figure 42: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 79 |
| Figure 43: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios..... | 80 |
| Figure B.1: Interchange Area Total Time for 70% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 103 |
| Figure B.2: Interchange Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 104 |
| Figure B.3: Interchange Area Total Time for 30% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 105 |
| Figure B.4: Interchange Area Total Time for 70% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 106 |
| Figure B.5: Interchange Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 107 |
| Figure B.6: Interchange Area Total Time for 30% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 108 |
| Figure B.7: Downstream Area Total Time for 70% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 109 |

| | |
|--|-----|
| Figure B.8: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 110 |
| Figure B.9: Downstream Area Total Time for 30% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 111 |
| Figure B.10: Downstream Area Total Time for 70% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 112 |
| Figure B.11: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 113 |
| Figure B.12: Downstream Area Total Time for 30% Left Turns, without Frontage Roads, 1 mile, 1.6 kilometer (1 mile), 7-lane Arterial | 114 |
| Figure B.13: Interchange Area Total Time for 70% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 115 |
| Figure B.14: Interchange Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 116 |
| Figure B.15: Interchange Area Total Time for 30% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 117 |
| Figure B.16: Interchange Area Total Time for 70% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 118 |
| Figure B.17: Interchange Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 119 |
| Figure B.18: Interchange Area Total Time for 30% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 120 |
| Figure B.19: Downstream Area Total Time for 70% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 121 |
| Figure B.20: Downstream Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 122 |
| Figure B.21: Downstream Area Total Time for 30% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 5-lane Arterial | 123 |
| Figure B.22: Downstream Area Total Time for 70% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 124 |

| | |
|---|-----|
| Figure B.23: Downstream Area Total Time for 50% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 125 |
| Figure B.24: Downstream Area Total Time for 30% Left Turns, with Frontage Roads, 1.6 kilometer (1 mile), 7-lane Arterial | 126 |
| Figure B.25: Interchange Area Total Time for 70% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 127 |
| Figure B.26: Interchange Area Total Time for 50% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 128 |
| Figure B.27: Interchange Area Total Time for 30% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 129 |
| Figure B.28: Interchange Area Total Time for 70% Left Turns, without Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios..... | 130 |
| Figure B.29: Interchange Area Total Time for 50% Left Turns, without Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios..... | 131 |
| Figure B.30: Interchange Area Total Time for 30% Left Turns, without Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios..... | 132 |
| Figure B.31: Downstream Area Total Time for 70% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 133 |
| Figure B.32: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 134 |
| Figure B.33: Downstream Area Total Time for 30% Left Turns, without Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios..... | 135 |
| Figure B.34: Downstream Area Total Time for 70% Left Turns, without Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios..... | 136 |
| Figure B.35: Downstream Area Total Time for 50% Left Turns, without Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios..... | 137 |
| Figure B.36: Downstream Area Total Time for 30% Left Turns, without Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios..... | 138 |

1.0 INTRODUCTION

As Michigan marks its 100th year of auto manufacturing, it should also be noted that the freeways in the Detroit area have been in service since 1942. The first 11 kilometers (7 miles) were constructed in 1942 to get workers from Detroit to the World War II bomber plant at Willow Run. On Dec 19, 1960, Michigan claimed to have the longest freeway (322 kilometers or 200 miles) in the nation. Many of these early interchanges preceded the Interstate system and, thus, Interstate design standards. The Michigan Department of Transportation (MDOT) is considering the much needed rehabilitation and upgrading of many of these and other interchanges located in the urban environments. MDOT and Michigan State University (MSU) have undertaken a joint effort to evaluate the appropriateness of an urban interchange geometric configuration, the Single Point Urban Interchange (SPUI) (Figures 1 and 2), as an alternative design to those presently used by MDOT. In particular, the Michigan Urban Diamond Interchange (MUDI) (Figure 3) and the traditional diamond (Figure 4) were investigated.

Most of the pre-interstate freeway interchanges in the city of Detroit and its environs are directional, partial cloverleaf and diamond interchanges. Directional interchanges are normally used to allow a freeway to interchange with another freeway. Conversely, partial cloverleaf interchanges are often used when a freeway interchanges traffic with a major arterial, such as a state trunkline. The loop ramps of the partial cloverleaf accommodate the left-turning movements, thus reducing conflict on the major arterial. Finally, the simplest and perhaps most common interchange used is the urban diamond. Diamond interchanges




Figure 1: Typical Single Point Urban Interchange (SPUI) Configuration without Frontage Roads (Not to Scale)




Figure 2: Typical Single Point Urban Interchange (SPUI) Configuration with Frontage Roads (Not to Scale)




Figure 3: Typical Michigan Urban
Diamond Interchange (MUDI)
Configuration with Frontage Roads
(Not to Scale)




Figure 4: Typical Diamond Interchange Configuration with Frontage Roads
(Not to Scale)

are used to accommodate traffic from major city streets and for freeways with parallel frontage roads.

The configuration shown in Figure 4 is an example of an urban diamond interchange with a city street, freeway and parallel frontage roads. The frontage roads usually are one-way streets and run in the same direction as the juxtaposed freeway lanes. The at-grade intersections of the frontage roads with the crossroad usually have stop-and-go traffic signals. If the freeway is below grade and the crossroad is at grade, then traffic exiting the freeway is going uphill and traffic entering the freeway is going downhill which is beneficial for both movements. Also, the design of the diamond interchange allows traffic entering and exiting the freeway to do so at relatively high speeds. Moreover, if the freeway is depressed, the at-grade intersections have no sight restrictions typically created by freeway structures or differences in grades. Unfortunately, this configuration has relatively low capacity because all of the turning movements occur at the intersections and left-turning vehicles have to yield to on coming traffic. Thus, there are several areas where traffic spillback may exceed the storage space.

The Michigan Department of Transportation (MDOT), borrowing from its indirect left-turn strategy implemented for most at-grade urban boulevards, modified the traditional urban diamond in an effort to increase the design's capacity. This modified diamond interchange configuration will be referred to as the Michigan Urban Diamond Interchange (MUDI) (Figure 3). This configuration evolved during the design and construction of freeways in the early and mid 1960s.

There are no SPUIs in Michigan and most of the known SPUIs are located in southern states. As a result, the first step was to determine the state of the practice for SPUIs. Next, a field review was conducted in 6 states. In Michigan, three areas of concern were raised before the field reviews commenced. These areas are: a need to rely heavily on traffic lane markings, the ability to progress traffic on the cross-road, and, the impact of continuous frontage roads on the overall operation. The field review also concentrated on collecting information about the geometric design, signal operation, pedestrian control, pavement markings, and land use/landscaping of SPUIs. Finally, all three interchange configurations were computer modeled to examine their respective operational characteristics.

2.0 OPERATION AND DESIGN OF THE MICHIGAN URBAN DIAMOND INTERCHANGE (MUDI)

An example of a MUDI is shown in Figure 3. This configuration is an urban diamond with left-turning vehicles being routed through separate left-turn structures known as directional cross-overs. Thus, left-turning movements are prohibited at the intersection. As an example, a driver traveling from bottom to top along the arterial wanting to access the left entrance ramp to the freeway, which in the case of a standard diamond interchange, would make a direct left-turning maneuver. For the MUDI, the driver would turn right at the first frontage road, travel to the directional cross over, make a U-turn through the cross over, travel from right to left to the arterial, cross the arterial and access the entrance ramp, thus completing the desired left turn. Similarly, a driver desiring to access a business adjacent to

the service road in the opposite direction would use the cross-overs to change direction and gain access. Evident in these maneuvers is the associated increased travel distance to complete them.

The distance that the directional cross over structure is placed from the crossroad is a function of the cycle length of the traffic signals and the speed of the movement. Properly designed, if the left-turning maneuver described above began from the start of green, it should receive a green indication at both the cross over and the arterial. Thus, it does not have to stop and the total travel time for this indirect left turn would equal approximately one-half of the cycle length.

In urban areas, access to property abutting the freeway is often of such importance as to require parallel frontage roads. In addition, Intelligent Transportation System (ITS) strategies, such as ramp metering, function better with continuous frontage roads. However, the intersections of the frontage roads with the cross-road usually require the use of traffic signals. These closely spaced traffic signals may have a significant negative impact upon the operation and capacity of the cross-road. This impact may also be influenced by the cross-section (divided multilane vs. non-divided multilane) of the cross-road.

The addition of U-turn lanes to the cross over structures, as shown in Figure 3, is cost-effective when there is a major development or other large attractor of traffic located in the top left or bottom right quadrants of the interchange. For example, freeway traffic traveling from left to right destined for a development in the top left quadrant would exit normally at the ramp to the arterial but immediately use the U-turn structure to access the top frontage road

and, thus, the abutting property. This traffic never enters the intersection with the arterial and, consequently, this strategy can significantly increase the capacity of the intersection.

3.0 OPERATION AND DESIGN OF THE SINGLE POINT URBAN INTERCHANGE (SPUI)

An example of a SPUI without frontage roads is shown in Figure 1. Although this interchange design has been around for over 25 years, it has only recently become more prominent due to claims of its efficient operation. However, the benefits of the SPUI have been the subject of some debate. The first SPUI was completed in Clearwater, Florida on February 25, 1974 and was designed by Greiner Engineering. Since that time several other states have adopted the design and have SPUI interchanges in place.

The primary feature of the SPUI is that all through and left-turn maneuvers converge at one signalized intersection area as opposed to two separate, closely spaced signals as with the traditional diamond. In addition, opposing left-turn movements operate to the left of each other, contrary to the right-hand rule. This allows for a relatively simple phasing sequence to be used to control conflicting movements. This phasing sequence typically consists of three phases accommodating: both crossroad through movements, both off-ramp left-turn movements, and both crossroad left-turn movements. The right-turn movements are usually allowed to free-flow. However, if frontage roads are present (Figure 2), there is a need to add a fourth phase, resulting in a reduction in capacity of the other phases. In addition, because of the physical size of many of the SPUIs, a relatively long clearance interval is required between the phases.

A limitation in the SPUI design is that the close physical relationship of the bridge abutments, roadway cross-sections, and offset left-turn paths constrain the ability to easily upgrade the design in the future. In addition, these limitations make it difficult to utilize this design in an area where the crossroad and freeway intersect at a skew. Furthermore, the horizontal alignment of the left-turn paths can affect the amount of right-of-way needed.

4.0 STATE OF THE PRACTICE

To determine the state of the practice with respect to Single Point Urban Interchanges, a literature review, AASHTO e-mail survey and telephone survey were conducted.

4.1 Literature Review

Much of the published literature on the design and operation of single point interchanges was generated from research efforts by Bonneson, et. al., at the Texas Transportation Institute (TTI)(1). The objective of that study was to evaluate the design of a Single Point Urban Interchange (SPUI) with that of other interchange geometric configurations. The preliminary results indicated a concern for pedestrians and the lack of a protected pedestrian phase. Also, a concern that with the addition of continuous frontage roads the capacity of the interchange would be reduced was expressed. Moreover, it was found that SPUIs appear to have a relatively large number of rear-end accidents.

The final report from the TTI project endorsed the SPUI as a safe and efficient design alternative to a Tight Urban Diamond Interchange (TUDI) in restricted urban conditions. However, there was still a concern for pedestrian safety and it was determined

that SPUIs cost more than TUDIs. It was concluded that "motorist's driving skills at SPUIs are expected to improve with time" (2). It was also stated that "the tight urban interchange is a viable alternative to all other interchange forms...." (2). While, the capacity analyses determined that a simple SPUI is slightly more efficient than a TUDI, but the advantage diminishes as the size of the SPUI becomes larger. It was concluded that the SPUIs with a four-phase signal operation "clearly does not have as efficient lane capacities" (2).

Other authors have also stated a concern for pedestrian safety with SPUIs. In addition, a concern for vehicle traffic violations was expressed. Due to the SPUI's relatively unusual design, several authors have expressed a need for excellent sight lines and a heavy reliance on guide signs, pavement markings and lane use signing. A concern for the impacts resulting from a skewed intersection was also found in the literature. Fowler (3) concluded that as the directional split of the cross street through volumes increases, the performance of a TUDI improves with respect to that of a SPUI.

Leisch, et.al. (4), stated in two publications that a SPUI is an effective design. However, it was also stated that it has little potential for expansion and any possible advantage diminishes as the clearance intervals increase. No conclusive observation of safety differences between the two configurations was found and it was stated that the potential exists for higher accident rates with a SPUI. In addition, an accident analyses of the accident rate of three SPUIs was compared to the rate of three Compressed Diamond Interchanges (CDI) by the Utah DOT (5). UDOT found that the SPUI had an accident rate that was 1/3 to 1/2 that of a CDI. However, the sample size available is too small which could bias these results.

4.2 AASHTO E-Mail Survey

A survey was submitted by e-mail to each of the other 49 state departments of transportation. The survey requested fundamental information on the design and operation of Single Point Urban Interchanges (SPUI). Although the survey was as succinct as possible (i.e. only 11 questions), only 14 state DOTs responded. The responding states were: Arkansas, California, Indiana, Iowa, Missouri, New Mexico, New York, North Dakota, Oklahoma, Pennsylvania, Texas, Vermont, West Virginia and Wyoming. Of these, only California, Indiana, Missouri, and New Mexico have operating SPUIs. In addition, New York is presently designing their first SPUI. None of the responding states with existing SPUIs reported having frontage roads as part of the design. As expected, the state DOTs did not necessarily respond to each question.

Generally, the respondents reported that the major advantages of a SPUI configuration with respect to other geometric configurations are: that it requires the same or less Right-of-Way, has less delay and user costs, is adaptable to frontage roads, requires fewer signals, is easier to coordinate the traffic signals with the surrounding system, costs less, has fewer conflict points, allows for U-turn movements, and, has superior aesthetics. The responding states also stated that the major disadvantages of a SPUI configuration with respect to other interchange designs are: it is not an optimal solution if adequate Right-of-Way is available, it costs more, it has long or special bridge structures, signals are difficult to mount, it has long clearance intervals, it has unbalanced traffic flows from the off ramps, it is tough on pedestrians, it should not be considered where the Right-of-Way allows for the construction of a Partial-Cloverleaf interchange, it has less capacity than a Partial-

Cloverleaf, the downstream intersections may control the flow, left-turn storage capacity on the cross-road is critical, and, sight distance shall always be a concern.

The responses received from different states varied widely. With respect to delay, one state reported that delay decreased and another reported no noticeable increase in delay. Accident rates were reported to be similar to diamond interchanges or having no noticeable increase in accidents. One state reported that signing was more difficult and two other states reported that they used conventional signing. One state reported that they used conventional pavement markings, another state reported that pavement markings may be a problem, and a third state reported that there is a need for extensive pavement markings. A SPUI was reported to cost \$2 to 4 million more than a conventional diamond, \$8 to 12 million for converting an existing diamond, and, the same as a conventional diamond. Finally, the Right-of-Way requirements were reported to be similar to a tight diamond, to depend upon the use of retaining walls, and, to be less than a conventional diamond.

The limited number of responses to the survey restricted its usefulness for comparison to the conditions found in Michigan. While maintenance of a SPUI was not a problem for one state and was "little" problem for another state, snow plowing was not considered, as none of the responding states with SPUIs are considered to be in a climate where snow plowing would be anticipated to be a problem. In addition, Michigan tries to progress traffic on most of its cross-roads. However, only one state responded that they had a cross-road with good progression. The other states did not address this issue.

4.3 Telephone Survey

The review of the literature and the response to the e-mail survey, while helpful, had significant inconsistencies and lacked of information in key areas. A telephone survey was

subsequently conducted with some of the e-mail states and with several additional states' Departments of Transportation. The states called in the telephone survey were: Indiana, Illinois, Minnesota, Florida, Arizona, Missouri, and, Texas. The objective of the phone survey, in addition to collecting more information, was to locate the most appropriate sites for a field review. Specifically, it was desired to observe the operation of SPUIs with frontage roads, the progression of the cross-road, and, the operation of SPUIs under winter-time conditions.

The individuals having the greatest knowledge of the operations of the SPUIs were sought out. Thus, most of the phone conversations were with the district traffic engineers. Of the seven state DOTs telephoned, four gave strong favorable recommendations on the positive aspects of a SPUI. One state DOT could not recall its operation and had ambivalent feelings. The remaining two state DOTs had very unfavorable opinions.

Of the favorable comments, one engineer responded that their operation was "wonderful" and another responded that the SPUI was his preferred design. However, one of the state engineers responded that the SPUI did not have a single advantage with respect to the design and operation of a conventional tight diamond. Also on a negative note, another state traffic engineer responded that when their first SPUI was open to traffic it was like a "zoo" with the first six months of operation being "total chaos".

When attempting to narrow the search for appropriate field review sites, it was discovered that only two of the states had any experience operating a SPUI with frontage roads. Surprisingly, only two of the state traffic engineers reported that they progressed the traffic on the cross-road arterial. Most of the states reported that they rely solely on traffic actuated signalization. One state engineer reported that it is difficult to progress the cross-

road traffic because the SPUI requires too long of a cycle length. Another engineer responded that the older and smaller designs were much easier to operate.

The comments of the Minnesota DOT were of special interest since they have a similar climate. The district traffic engineer in Duluth believed that a SPUI was easier to operate than a conventional diamond interchange. In addition, he reported that pedestrians did not have a problem and he knew of no winter time difficulties.

5.0 FIELD REVIEW OF THE SPUI

Based on information gathered through the e-mail and telephone surveys, sites were selected in several states for inclusion in the field review. These sites were located in Indiana, Illinois, Minnesota, Florida, Missouri and Arizona. Without exception, the various state DOTs and county Road Commissions were very cooperative and their representatives a pleasure to meet with.

During a typical field review, the engineers and technicians responsible for the operation of the SPUI interchange being studied were interviewed. These interviews included a visit to the site where the actual operation of the SPUI was discussed. If possible, plan view drawings, signing plans, aerial photographs, signal timings, traffic volumes, in-house studies, and, economic data pertaining to the SPUI in question were collected. In the field, extensive photographs and video of the interchange were taken.

Based on the field review conducted between January 1996 through May 1996, subjective observations can be made about the design and operation of a SPUI. These observations can best be presented by grouping them into several topic areas including:

geometric design, signal operation, pedestrian control, pavement markings, and, land use/landscaping.

5.1 Geometric Design

The geometric features of the SPUIs varied greatly from state to state. The difference in designs was much greater than anticipated and this difference may explain some of the inconsistencies in the responses to the e-mail and phone surveys.

The most significant observed difference in design is between a SPUI with the cross-road going over the freeway and a SPUI with the freeway going over the cross-road. The SPUIs with the cross-road going over the freeway were found to be a preferred design (Figure 5). The resulting single-point intersection looks and operates more like a conventional signalized intersection. Because of this, driver confusion is greatly reduced. Conversely, significant driver confusion was observed at interchanges utilizing the cross-road under the freeway design. At times, vehicles became trapped in the intersection due to driver confusion, creating a dangerous situation (Figure 6). An engineer in one state that had recently opened a new SPUI of this design referred to "mass confusion when opened." In addition, routing the freeway over the cross-road exposes the freeway and major traffic volume to differential icing in cold weather climates.

Another significant difference in design is related to the physical size of the interchange. Some of the newer SPUI designs include the provision of a dedicated U-turn lane to permit a U-turn maneuver from the exit ramp back onto the entrance ramp (Figure 7). These dedicated structures were located under the tailspans requiring the tailspans to be much longer than normal. While the smaller designs can provide for most U-turns, this dedicated lane is necessary to accommodate large trucks and to increase the speed of the




Figure 5: SPUI with cross-road going over the freeway with all signal heads located on a single overhead tubular beam.



Figure 6: Confused driver (car with lights on) stopped in middle of a SPUI while traffic proceeds on either side




Figure 7: U-turn lane accommodates large trucks

maneuver. Even at interchanges where this maneuver was prohibited, it was still observed to occur regularly. However, the smaller designs were observed to function better than the larger designs. In addition, the Right-of-Way requirements are obviously much less with the smaller design.

The design of the structures varied from state to state. They are generally much longer than those of conventional diamond interchanges. For example, some of the spans measured were found to be greater than 146 meters (480 feet) in length. Often there are three spans of nearly equal lengths. Some of the structures were very noisy and the resulting booms could be heard for several kilometers. This noise was the source of almost constant residential complaints. Because of the large widths and lengths, the road under the structures were dark. Lighting was often provided under the structures during the day and visibility at locations that utilized light color bridge paints (e.g. sand or concrete) were noticeably better than those with dark color bridge paints. These undesirable characteristics were not evident when the cross-road went over the freeway.

The impact of continuous frontage roads on the overall operation of a SPUI was a key area of interest. It was explicitly desired to observe the operation of a SPUI with parallel frontage roads whose intersections with the cross-road are signalized and accommodate significant through traffic. Two of the states visited were anticipated to have these type of frontage roads based on responses from the e-mail and telephone surveys. However, these frontage roads did not satisfy Michigan's requirements. One of the state's frontage roads are what would be considered to be ramps with private driveways. The other state had a frontage road that was a two-way road which did not appear to generate the desired through traffic. Several of the district traffic engineers expressed strong opinions

that providing for continuous frontage roads with a SPUI is a poor design and counteracts the advantages of a SPUI.

The geometry of the exit ramps often flared from one lane to three at the ramp terminus. Of these three lanes, two were for left-turning traffic and one for right-turning traffic. The right- and left-turning lanes are separated by a large channelized island. The dual left-turning traffic on the off-ramp often backs up during peak periods. This blocks right-turning traffic from exiting and locks up the ramp (Figure 8). In the case where the freeway goes over the cross-road, sight distance is a concern.

The geometry of the on-ramps normally consisted of two left-turn lanes, under signal control, and a free-flow right-turn lane. These lanes merge down to one lane before entering the freeway. This geometry causes a "race track" effect on the on-ramp as vehicles vie for position to merge. This effect, along with the short distance allowed for the merge to occur, results in a sideswipe crash problem. However, in at least one state, the crash reporting system is structured in such a way that these sideswipe crashes are not referenced to the interchange. Thus, it is difficult to get a clear picture of the crash experience of the interchange.

Most of the SPUI designs, regardless of state, added several additional lanes to the cross-road basic laneage at the interchange. A typical design would have a 6 lane cross-road being widened to nine lanes at the interchange. The additional lanes are typically a right-turn bay and provision for dual left-turn lanes for the on-ramp. In addition to the auxiliary lanes, most of the cross-roads had raised, concrete medians ranging in width from 1.2 meters (4 feet) to 3.6 meters (12 feet).



Figure 8: Dual left-turning traffic is backing up, blocking right-turning traffic

5.2 Signal Operation

The operation and placement of traffic signals were of special interest. Each state's practice differed significantly. The cycle lengths varied from 80 seconds to 180 seconds. The SPUIs reviewed that had longer cycle lengths usually had fully actuated signal phases for all movements which was not what was expected.

Of special interest was the ability to progress traffic on the cross-road. Two of the SPUIs reviewed have a cross-road arterial which was part of a pre-timed progressed strategy. While the interchange was operating well below capacity, it was obvious that providing progression would not be a problem. These interchanges were the smaller designs which result in shorter clearance times and allows for a shorter cycle. However, the impact of the SPUI on intersections downstream must be considered. Comments were made to the

effect that the SPUI dumps traffic on the downstream nodes causing a migration of delay. This was hard to judge in the field as none of the SPUIs reviewed were operating near their capacity.

Most of the SPUIs reviewed had a 3 phase signal operation. The 3 phases were usually: left-turn entrance ramp movements, left-turn exit ramp movements, and, cross-road through movements. One state provided for a right-turn exit ramp green arrow during the left-turn entrance ramp phase. Usually the exiting right turn was accommodated via a free-flow, channelized merge with the cross-road traffic. However, a skewed intersection affects the operation of the signal phasing. At these locations, there are 4 signal phases: first exit ramp movement, opposing exit ramp movement, left-turn entrance ramp movements, and, cross-road through movements. In addition, the skew causes the clearance times to increase.

The placement of the traffic signal heads also varied greatly from state to state and by geometric design. In the case of a SPUI where the cross-road goes over the freeway, all of the signal heads are located on a single overhead tubular beam (Figure 5). Thus, the 3 phase operation was analogous to a traditional at-grade intersection with a 3-phase signal. This design typically took less Right-Of-Way. This SPUI design was observed to function very well, although the traffic volumes were not heavy. In the case of a SPUI where the freeway goes over the cross-road, the signal heads are mounted on the structure. However, some states have post-mounted signals located on traffic islands. In one interchange alone there were 24 signal heads. With this proliferation of signal heads, it was possible to see green, amber and red indicators at the same time depending on where one looked. In addition, the signal heads when post-mounted were vulnerable to damage from motorists running into them.

The physical size of the interchange also affected the signal operation. If the intersection area is very large, longer clearance times are required for traffic to clear the intersection prior to allowing the next phase. Additionally, the green signal arrow for left-turning traffic was often canted to give the motorist a sense of direction in these large intersection areas. Still, there was driver confusion resulting from the large distances needed to clear the intersection (Figure 6). There were three common mistakes observed. The first results when the lead car does not start on green because the driver is (presumably) confused on which signal indication is theirs. The second results when a motorist entering the intersection from the exit ramp on a green light has to drive through a red indication meant for the cross-road. Vehicles were observed stopping in the middle of the interchange and waiting for a green indication. The third results when a motorist starts into the intersection and simply gets lost due to the large size of the interchange.

5.3 Pedestrian Control

The ability to accommodate pedestrian movements varied greatly from site to site. Many of the locations simply had no pedestrian movements to accommodate. Where pedestrians were present, it was not difficult for them to move parallel to the cross-road and cross the ramp movements. However, with all movements going through the center of the interchange and a signal operation utilizing fully traffic actuated phases, there is always traffic moving through the intersection. This makes it hard for pedestrians to cross the cross-road. In addition, the width of the cross-road, often 6 to 8 lanes, makes it difficult for pedestrians to cross the cross-road. Often, pedestrians would become trapped on the concrete channelization of the cross-road when attempting to cross. Some sites actually prohibited pedestrians from crossing. However, this prohibition was often violated, as

typically the only other opportunity to cross was at the next intersection which was usually 400 meters (quarter of a mile) away.

5.4 Pavement Markings

With the potential for snow covering as in Michigan, the need to rely heavily on traffic lane markings was a concern that was focused on. For the most part the larger SPUIs have supplemental lane markings to assist the motorist with the left-turn movement. The need for these pavement markings is paramount. However, even in the best case scenario, these pavement markings overlap creating driver confusion (Figure 9). In a skewed configuration, this overlap is taken to the extreme and it can be confusing even to a driver familiar with the interchange. However, the need for supplemental lane lines for the turning movement was not evident for the locations where the cross-road when over the freeway or the interchange was small in size.



Figure 9: Pavement marking overlap creates driver confusion

One location had lights placed in the pavement to help illuminate the turning path. When left turning traffic was given a green light, these “runway” lights would light up green along the path to be taken by the motorist (Figure 10). However, the design of these lights is such that they are a maintenance problem as they fill with dirt which obscures the lens. The engineer responsible for maintaining the operation of this location expressed a concern that the lights may also raise several tort liability issues. For example, if the runway lights are not working at the time of an accident, can it be said that one of the traffic control devices (TCDs) was not working? Additionally, experience has shown that there is a problem with motorcycles executing turning maneuvers and hitting the slick surface of the lights when they are wet, causing an accident.



Figure 10: “Runway” lighting to help illuminate the turning path.
Note the buildup of debris.

Many of the SPUIs reviewed have channelized islands to help guide drivers as they negotiate through the single-point intersection. On the center island, typically there was also directional signing present. The location of this signing makes it extremely vulnerable to damage from motorists who stray onto the island. During the field review, it became obvious that motorists frequently strike these islands while negotiating the intersection. Channelized islands are not as popular in Michigan because of their interference with snow plowing.

5.5 Land Use/Landscaping

The land use surrounding the SPUIs reviewed and type of landscaping varied widely between states. In one case, the SPUI had no development in either direction along the cross-road and was located in an almost rural setting. For the remaining cases, the main difference in the type of land use surrounding the interchange was based on access control to the cross-road.

Some states did not control access to the cross-road or, in some cases, the interchange itself. This perpetuates a large number of driveway cuts in the median close to the interchange and the resulting increase in conflicts in the interchange area. In one state, driveway access was granted on the ramps themselves, greatly increasing the complexity of their operation. Other states had complete access control to the abutting properties. A narrow median was often used on the cross-road to limit access to properties except at specific locations. When allowed, access was typically accommodated at signalized intersections. This strategy reduced conflict areas and should also reduce the severity of accidents that do occur.

Landscaping was only present in two of the states reviewed and both of these states had southern climates. In one state, much of the original landscaping had been removed. The high cost of maintenance and problems with transients were cited as the reasons for the removal. In Arizona, however, great efforts had been taken to landscape the interchanges. The effect of this landscaping was spectacular, especially when the cross-road went over the freeway (Figure 11). The large island structures that result from the separation of the left- and right-turn ramp movements in the SPUI design provide an excellent space for landscaping. This landscaping varied from small flowers, shrubs and cactus to large palm trees and flowering bushes.




Figure 11: Typical Landscaping of a SPUI in Phoenix, AZ.

5.6 Conclusions from the Field Review

Based on this field review, subjective observations can be made about the design and operation of the SPUI. These observations were grouped into the areas of geometric design, signal operation, pedestrian control, pavement markings and land use/landscaping of SPUIs.

The most significant geometric design difference of the SPUIs reviewed is between a SPUI with the cross-road going over the freeway and a SPUI with the freeway going over the cross-road. The SPUI with the cross-road going over the freeway was found to be a preferred design. Another design difference was related to the physical size of the interchange. SPUIs without dedicated U-turn lanes appeared to accommodate U-turns as well as those with dedicated U-turn lanes. Thus, the smaller designs were observed to function better than the larger designs. In addition, the Right-of-Way requirements are less with the smaller designs. Moreover, the design of structures was observed to be very important. In some cases, the structures were very noisy causing residential complaints. Because of the large size of these structures, the roadway under the structure is dark. These undesirable structure characteristics are not evident when the cross-road goes over the freeway. In addition, several engineers expressed strong opinions that the use of continuous frontage roads with a SPUI counteracts the advantages of the design. Furthermore, in the case where the freeway goes over the cross-road, sight distance is a concern. Finally, the geometry of the typical on-ramps results in a sideswipe crash problem.

The signal operation strategy employed by each state differed significantly. Cycle lengths varied from 80 seconds to 180 seconds, with longer cycle lengths usually having fully actuated signal phases for all movements. The interchanges reviewed were operating

below capacity and, at this level, progression of the cross-road was not a problem. However, the impact of the SPUI on intersections downstream must be considered. If the interchange area was very large, the clearance times became quite long and there was significant driver confusion. Finally, the best placement of traffic signal heads occurred in designs where the cross-road went over the freeway, allowing the signal heads to be located on a single overhead tubular beam.

The ability to accommodate pedestrians varied greatly between designs. Typically, it was not difficult for pedestrians to move parallel to the cross-road and cross the ramp movements. However, due to the characteristics of the SPUI, there is always traffic moving through the intersection. This makes it extremely difficult for pedestrians to cross the cross-road.

The need for pavement marking in large SPUIs is paramount. However, these pavement markings can overlap and cause driver confusion. This resultant driver confusion is most pronounced when the cross-road is skewed. The use of “runway” lighting was not observed to be an effective solution to this problem. Additionally, the use of channelized islands to help guide drivers through the interchange was reviewed. This is also not an effective solution in Michigan, due to the snow removal requirements.

The major differences in land use between the different states can mostly be attributed to access control. Those states that did not control access near the interchange had a large number of conflict areas in the interchange area. Those states that did control access had a limited number of conflict areas. Where landscaping was provided, the aesthetics of the interchange were dramatically increased.

Based on the field review, the Single Point Urban Interchange (SPUI), properly situated, is a good design. However, some of the newer and enhanced designs with the resulting increase in size may be counterproductive.

6.0 METHODOLOGY

Sufficient traffic volumes could not be found at any of the locations visited during the field review to allow for a field determination of operation at capacity. Thus, it was determined that the best possible approach to determine the operational characteristics of the interchange configurations in question was to use computer modeling.

6.1 Selection of the Computer Model

The concept of traffic control is giving way to the broader philosophy of Transportation Systems Management (TSM), in which the purpose is not to move vehicles, but to optimize utilization of transportation resources in order to improve the movement of people and goods without impairing other community values (6). To better achieve this optimization, computer simulation techniques have been developed. These models predict a system's or network's operational performance based only on data inputs. This eliminates the need for an existing facility to be expanded or a proposed facility to be constructed to conduct the analysis.

The computer simulation approach is considered more practical for evaluation of network changes or operation than field experiments for the following reasons:

- It is less costly
- Results are obtained quickly

- The data generated by simulation includes many measures of effectiveness that cannot easily be obtained from field studies
- Disruption of traffic operations, which often accompany a field experiment, is completely avoided
- Many schemes require significant physical changes to the facility which are not acceptable for experimental purposes
- Evaluation of the operational impact of future traffic demand must be conducted using simulation or equivalent analytical tools (6).

TRAF-NETSIM is a stochastic, microscopic model which describes the operational performance of vehicles based on several measures of effectiveness (MOEs). The internal logic of this model describes the movements of individual vehicles responding to external stimuli including traffic control devices, the performance of other vehicles, pedestrian activity, and driver performance characteristics. NETSIM applies interval-based simulation to describe traffic operations. This means that every vehicle is a distinct object which is moved every second, and that every variable control device (traffic signals) and event are updated every second. Each time a vehicle is moved, its position (both lateral and longitudinal) on the links and its relationship to other vehicles nearby are recalculated. Its speed, acceleration and status are also recalculated. Vehicles are moved according to car following logic, response to traffic control devices and response to other demands (6). For these reasons, the TRAF-NETSIM model was selected for use in this study.

However, at the time this project was started, the TRAF-NETSIM model did not have the ability to simulate dual left-turning traffic. After a waiting period, a “patch” was developed for the program which allowed dual left-turns to be modeled. However, this “patch” limited the vehicle array size. It was discovered that even with the modest network size that was utilized in this project, this vehicle array was exceeded at low levels of network saturation. When the vehicle array is exceeded, the model stops simulation. This resulted in further delay until the beta version of CORSIM (the new package that TRAF-NETSIM is now a part) was available from the Federal Department of Transportation. CORSIM was able to handle both dual left-turning traffic and a large vehicle array.

6.2 Network Configuration

To compare the operation of a diamond interchange (Figures 12 and 13), a MUDI (Figures 14 and 15), and a SPUI (Figures 16 and 17), several assumptions had to be made about the network geometry to generate the necessary link/node diagrams. First, it was decided to model the arterial crossroad as both a five-lane and seven-lane pavement. The cross-section of the five-lane facility consists of four through lanes (two in each direction) and a continuous center left-turn lane (CCLTL), while the seven-lane facility consists of six through lanes (three in each direction) and a CCLTL.

Next, the size of the network had to be determined. A major concern with regard to interchange operation is the interchange’s effect on the downstream nodes of the arterial. Thus, it was decided to model both the interchange area and one arterial downstream node on either side of the interchange. These downstream nodes were modeled as the intersection of the arterial with a five-lane CCLTL. Since an arterial is said to have “perfect geometry” if the




Figure 12: Typical Diamond Interchange Configuration with Frontage Roads (Not to Scale)




Figure 13: Link/Node Diagram for Diamond Configuration
(Not to Scale)

Diamond




Figure 14: Typical Michigan Urban
Diamond Interchange (MUDI)
Configuration with Frontage Roads
(Not to Scale)




Figure 15: Link/Node Diagram for MUDI Configuration
(Not to Scale)






Figure 16: Typical Single Point Urban Interchange (SPUI) Configuration with Frontage Roads (Not to Scale)




Figure 17: Link/Node Diagram for SPUI Configuration
(Not to Scale)

SPUI

intersections are 0.8 kilometers (one-half mile) or 1.6 kilometers (one mile) apart, these downstream intersections were initially placed at 1.6 kilometers from the interchange. The perfect geometric spacing of these intersections allows for optimal signal progression, thus minimizing delay. The impact of minor crossroads and driveways was not modeled.

Once the spacing of these downstream intersections had been determined, their geometry had to be determined. For each approach to the downstream intersections, a 168 meter (550 foot) left and right turning bay was provided. In the interchange area, a 168 meter (550 foot) right turn bay was provided on the arterial approach for both the MUDI and diamond interchange. Additionally, a 168 meter (550 foot) right turn bay was provided on the frontage road for traffic wishing to make a right turn from the frontage road to the arterial for both configurations. In the SPUI interchange area, the length of the right turn bays was shortened to 84 meters (225 feet), as the right turn was operating in a free-flow condition.

6.3 Signal Operation

For the purposes of the computer model, a free flow speed of 72 kph (45 mph), or 20 meters per second (66 feet per second), was assumed for the arterial, minor crossroads and frontage roads. Based on this free flow speed and an intersection separation of 1.6 kilometers (one mile), the cycle length was determined to be a multiple of 40 seconds. Longer cycle lengths (over 60 seconds) will accommodate more vehicles per hour due to the lower frequency of starting delays and clearance intervals. Thus, a 80 second cycle was selected for the downstream nodes for all cases. An 80 second cycle was also selected for the operation of the MUDI, while a 160 second cycle (double cycle) was selected for both the SPUI and the diamond interchange due to the need for long phase changes and clearance intervals. Further,

given the freeflow speed of 72 kph (45 mph), the minimum phase change interval (yellow and overlapping red) for each phase was determined to be 5 seconds. This phase change interval ensures that approaching vehicles can either stop or clear the intersection without conflicts.

The modeled arterial was to be operated in a progressed-coordinated system, so a definite time relationship exists between the arterial start of green intervals and adjacent intersection signals. Thus, offsets had to be determined. Since both downstream intersections were placed with perfect geometric spacing from the interchange, the free flow speed was assumed to be 72 kph (45 mph), and a cycle length of either 80 or 160 seconds was used, an offset of 0 seconds was selected to best provide for progression of traffic along the arterial. When the spacing of the closest downstream intersection was changed to 0.8 kilometers (one-half mile), this offset was changed to one half a cycle or 40 seconds. Furthermore, when the spacing of the closest downstream intersection was changed to 1.2 kilometers (three-fourths mile), this offset was changed to 20 seconds for the closest node and 60 seconds for the node placed at 2.0 kilometers (one and one-quarter mile).

The number of phases used depends upon the geometry of the intersection (number of approaches, lanes) and the volumes and directional movements of traffic. The purpose of phasing is to minimize the potential conflicts at an intersection by separating conflicting traffic movements. However, as the number of phases increases, the total delay to vehicles is increased and the total carrying capacity of the intersection may be reduced. Thus, it is desirable to use the minimum number of phases that will accommodate the traffic demands.

The signal phasing diagram for the intersection of the minor five-lane CCLTL and the arterial was the same for both downstream nodes to be modeled. It was assumed that the

volume ratio between the arterial and the minor crossroads would be 70/30. Thus, the green split between the arterial and crossroad would also be 70/30.

The signal phasing diagram for the MUDI was determined (Figures 18 and 19) using a green split of 60/40. In addition, an offset had to be determined for the crossover signals of the MUDI design. At the free flow speed of 72 kph (45 mph), or 20 mps (66 fps), a vehicle requires 8.3 seconds to traverse the 168 meters (550 feet) from the intersection to the crossover. The desired offset for the crossover signal is one which reduces the delay to arterial traffic wishing to make an indirect left turn while not adversely affecting the progression of the arterial. If a vehicle left the stop bar of the crossroad intersection at the free-flow speed and there were no cars at the crossover signal, this offset would be 8.3 seconds. However, there is typically a queue of vehicles, mostly comprised of exiting freeway traffic wishing to make an indirect left turn onto the arterial, waiting at the crossover signal. For the best progression of the arterial traffic, this queue must begin to dissipate before indirect left turning traffic from the arterial reaches the crossover signal. This will result in an offset that is less than the 8.3 seconds of travel time. Thus, to determine the best crossover signal offset, the sensitivity of the offset setting was tested and a value of four seconds was chosen as optimal.

A signal phasing diagram was developed for the SPUI for the case where no frontage roads were present (Figure 20) and for the case where frontage roads were present (Figure 21). A concern with signaling the SPUI is the need for a long phase change interval to allow traffic to clear the intersection. Thus, the minimum phase change interval of 5 seconds was increased to 9 seconds for all movements which are affected by the SPUI geometry.




Figure 18: Phasing Diagram for MUDI Configuration




Figure 19: Phasing Diagram for MUDI Cross-overs




Figure 20: Phasing Diagram for SPUI Configuration without Frontage Roads




Figure 21: Phasing Diagram for SPUI Configuration
with Frontage Roads

Finally, the signal phasing diagram for the diamond (Figure 22) was determined. A concern with signalizing the diamond interchange is the need for a clearance interval to allow time for traffic which has turned left from the ramp and is stored on the structure to begin clearing before releasing arterial traffic. Thus, a 12 second clearance interval was provided.

6.4 Variables And Measures Of Effectiveness

There were four major variables of interest that needed to be addressed in this study: traffic volumes, turning percentages, frontage roads and distance to the closest downstream node.

The networks were loaded by considering the percent saturation of the entry links of the arterial. For the entry links of the arterial, it was assumed that each entry lane had a hourly capacity of 1800 vehicles. With this in mind, a simple incremental volume structure was identified for study based on arterial entry link saturation values of 0.3, 0.5, 0.7, 0.9, and 1.0. The minor downstream crossroad entry links were assumed to have a per lane hourly volume ratio of 30/70 when compared to the arterial entry links. Furthermore, the network was modeled with an imbalance in traffic flow for both the frontage roads and exit ramps. It was assumed that there was a 70/30 imbalance in flow between traffic approaching from the left and traffic approaching from the right (Figures 12, 14, and 16). The maximum frontage road volume was assumed to be 600 vehicles per hour.

The second variable addressed was turning percentages. First, turns from the minor crossroad to the arterial were fixed at 20 percent toward the interchange and 10 percent away from the interchange. Turns from the arterial to the minor crossroad were fixed at 10 percent




Figure 22: Phasing Diagram for Diamond Configuration

left and 10 percent right. Second, for arterial traffic approaching the interchange, it was assumed that 25 percent wanted to turn left to access the on-ramp, 25 percent wanted to turn right to access the other on-ramp, and 50 percent wanted to continue on the arterial. Third, turning traffic exiting the freeway was varied to test the sensitivity of the designs to the volume of left turning traffic. Thus, values of 30, 50, and 70 percent left turns from the exit ramps were modeled. Finally, it was assumed that the volume of traffic entering on a particular frontage road would also exit on that frontage road.

The third variable addressed was the existence of frontage roads. In Michigan, depressed freeway segments typically are built with frontage roads to access the adjacent properties. Thus, the operation of a particular interchange configuration with and without frontage roads was determined to be of interest.

The final variable addressed was the distance to the closest downstream node. Early in the project, a concern was raised about the affect that an interchange would have on a closely spaced intersection. In addition, it was desired to determine how an interchange configuration would function in an arterial that did not have perfect geometry. Thus, the distance to the closest downstream node was varied. To keep the size of the network constant, as a downstream node was moved closer to the interchange area, its counterpart on the other side of the interchange was moved an equal distance away from the interchange. The first value modeled was a spacing of 1.6 kilometers (one mile) to either side of the interchange area allowing for perfect progression on the arterial while keeping separation. The second value modeled was a spacing of 0.8 kilometers (one-half mile) on one side and 2.4 kilometers (one and one-half mile) on the other side. This spacing still allows for perfect progression of the

arterial. However, the proximity of one of the downstream nodes to the interchange may be a factor. Finally, a spacing of 1.2 kilometers (three-fourths mile) to one side and 2.0 kilometers (one and one-quarter mile) to the other side of the interchange was modeled. This configuration does not allow for perfect progression along the arterial, but does keep separation between the closest intersection and the interchange.

A TRAF-NETSIM simulation run produces an output that summarizes the traffic movements and various measures of effectiveness (MOEs) for both the network as a whole and for individual links. The MOEs that were selected for this study were: interchange area total time and downstream area total time.

An effort was made to delineate an interchange area and a downstream area in the computer model. The physical size of these areas was the same for all models. However, inside the area, the size of the interchange may vary. The nodes numbered 7 and 8 were coded as dummy nodes (i.e. no change in the traffic stream occurs at them) to allow MOEs to be gathered for both the interchange area (the area bounded by on the top by node 7 and on the bottom by node 8) and the downstream area (the area above node 7 plus the area below node 8).

A criticism of the indirect left-turn strategy used by the MUDI configuration is that while conflict from left turning vehicles has been removed from the intersection, these drivers are penalized by being forced to travel a greater distance to use the cross over. Thus, delay cannot be used as a MOE, as it would be unclear if the delay savings at an intersection were being offset by the extra travel time imposed on left-turning traffic. Therefore, total time,

which represents the amount of time all vehicles spent in the network as a combination of travel time and delay time, was selected as a MOE.

7.0 SIMULATION RESULTS

Based on the variables selected for study, an hour of operation for 300 individual models was simulated. However, there were too many exhibits for the limits of this publication. Thus, representative examples of the findings are presented here, while all findings are presented in both tabular and graphical format in the appendix.

7.1 Interchange Performance without Frontage Roads

Figure 23 illustrates the performance of the interchange configurations without the presence of frontage roads and with a five-lane arterial cross-section. Additionally, the situation modeled in this scenario is for the extreme case of 70 percent of the vehicles exiting the freeway and desiring to turn left onto the arterial. At 30 percent saturation, all three interchange configurations performed approximately the same. However, at 50 percent saturation, the total time for the MUDI and SPUI configurations was reduced by 60 percent with respect to the total time of the traditional diamond. Additionally, at 70 percent saturation, the total time for the MUDI configuration was reduced by 25 percent with respect to the SPUI and 36 percent with respect to the traditional diamond. Finally, at 90 percent saturation, the total time for the MUDI configuration was reduced by 16 percent with respect to the SPUI and 20 percent with respect to the traditional diamond.

Figure 23: Interchange Area Total Time For 70% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure 24 also illustrates interchange configurations without the presence of frontage roads and a five-lane arterial cross-section. However, the percent left turns is reduced to 50 percent. Although the operational advantage of the MUDI is less, it is still meaningful and follows the same pattern as the 70 percent left case outlined above. At 30 percent saturation, all three interchange configurations still performed approximately the same. At 50 percent saturation, the total time for the MUDI and SPUI configurations was reduced by 50 percent with respect to the traditional diamond. Moreover, at 70 percent saturation, the total time for the MUDI configuration was reduced by 18 percent with respect to the SPUI and 38 percent with respect to the traditional diamond. Finally, at 90 percent saturation, the total time for the MUDI configuration was reduced by approximately 23 percent with respect to the SPUI and 32 percent with respect to the traditional diamond.

As the percentage of left turns is decreased to 30 percent (Figure 25), the operational characteristics of both the MUDI and the SPUI configuration change at higher levels of saturation, as anticipated. At 30 percent saturation, all three interchange configurations are again approximately equal. In addition, at 50 percent saturation, the total time for the MUDI and SPUI configuration was again reduced by 50 percent with respect to the traditional diamond. However, at 70 percent saturation, the total time for the MUDI is reduced by 28 percent with respect to both the SPUI and traditional diamond, which perform approximately the same. Finally, at 90 percent saturation, the total time for the MUDI is reduced by 23 percent with respect to the SPUI and 10 percent with respect to the traditional diamond. Thus, at 90 percent saturation, the traditional diamond is operationally superior to the SPUI.

**Figure 24: Interchange Area Total Time For 50% Left Turns, w/out Frontage Roads,
1.6 kilometers (1 mile), 5-lane Arterial**





Figure 25: Interchange Area Total Time For 30% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial



Much the same pattern is shown when the arterial cross-section is changed from a five-lane cross-section to a seven-lane cross-section (Figures 26-28). The major differences are that at 30 percent saturation, the total time for both the MUDI and SPUI was reduced by 35 to 40 percent with respect to the traditional diamond for all turning percentages. In addition, the MUDI with a seven-lane arterial begins to operationally outperform the SPUI at 50 percent saturation as opposed to at 70 percent saturation with a five-lane arterial.


In all cases, the MUDI configuration either equals the operational performance of the SPUI and traditional diamond configuration or exceeds it. These operational advantages are most pronounced when the percentage of left-turning traffic is high and the level of saturation is high. In addition, the operational advantages of the SPUI are greatly reduced as the percentage of left-turning traffic is reduced, with the traditional diamond outperforming the SPUI at high levels of saturation and low levels of left-turning traffic.

7.2 Migration of Delay without Frontage Roads

In this research effort, there is concern that greatly enhanced urban interchange configurations may demonstrate an improved operation at the freeway, but may merely move the delay to the first signalized intersection up or downstream. Thus, their advantages (if any) may be exaggerated. Therefore, this analysis also evaluated the operation of the downstream nodes.

As illustrated in Figure 29, which is a specific case with 50 percent left turns, five-lane arterial cross-section and no frontage roads, there was no evidence that either the MUDI or SPUI configuration resulted in “dumping” traffic and moving delay to the downstream nodes.

Figure 26: Interchange Area Total Time For 70% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial



**Figure 27: Interchange Area Total Time For 50% Left Turns, w/out Frontage Roads,
1.6 kilometers (1 mile), 7-lane Arterial**




Figure 28: Interchange Area Total Time For 30% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial





Figure 29: Downstream Area Total Time For 50% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial



However, the total time for the downstream area when fed by traffic from the traditional diamond interchange is greater for all but the 30 percent saturation level, suggesting a dumping effect. In addition, when the specific case with 50 percent left turns, seven-lane arterial cross-section and no frontage roads (Figure 30) is examined, this dumping trend continues for the traditional diamond. Moreover, at 70 percent saturation, the modeling of the SPUI also shows a dumping effect.

7.3 Interchange Performance with Frontage Roads

Many, if not most of, the MUDIs in Michigan are located where frontage roads are provided. Usually these frontage roads parallel the urban freeway for a considerable distance and provide access to abutting property. The need for local access in a major urban area was a primary consideration in the evolution of the MUDI design since frontage roads would need to be provided.

Figure 31 illustrates the performance of the interchange configurations with the presence of frontage roads, a left-turning percentage of 70 percent and a five-lane cross-section. At 30 percent saturation, all three interchange configurations performed approximately the same, which is consistent with the results from simulations without the presence of frontage roads. However, at 50 percent saturation, the total time for the MUDI configuration was reduced by 21 percent with respect to the SPUI and 59 percent with respect to the traditional diamond. This represents a divergence from the results of simulations without the presence of frontage roads, in which the MUDI and SPUI performed the same at 50 percent saturation. At 70 percent saturation, the total time for the MUDI configuration was reduced by 18 percent with respect to the SPUI and 29 percent with respect to the traditional

Figure 30: Downstream Area Total Time For 50% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial





Figure 31: Interchange Area Total Time For 70% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




diamond. Finally, at 90 percent saturation, the total time for the MUDI configuration was reduced by 13 percent with respect to the SPUI and 33 percent with respect to the traditional diamond.


Figure 32 further illustrates the performance of the interchange configurations with both frontage roads and five-lane arterial cross-sections. However, the percentage of left-turning traffic has been reduced to 50 percent in this case. At 30 percent saturation, all three interchange configurations continue to perform approximately the same. At 50 percent saturation, the total time for the MUDI configuration was reduced by 12 percent with respect to the SPUI and 59 percent with respect to the traditional diamond. These results are consistent with the scenario involving 70 percent left-turns outlined above. However, the results diverge from the results of the scenario involving no frontage roads, in which the MUDI and SPUI performed similarly at this level of saturation. At 70 percent saturation, the total time for the MUDI configuration was reduced by 21 percent with respect to the SPUI and 38 percent with respect to the traditional diamond. Finally, at 90 percent saturation, the total time for the MUDI configuration was reduced by 23 percent with respect to the SPUI and 25 percent with respect to the traditional diamond.

Figure 33 illustrates the performance of the interchange configurations with the presence of frontage roads, 30 percent left-turning traffic and a five-lane arterial cross-section. At the lowest level of saturation, all three interchanges continue to perform approximately the same. However, at 50 percent saturation, the total time for the MUDI configuration was reduced by 25 percent with respect to the SPUI and 46 percent with respect to the traditional diamond. This continues the trend of the SPUI operating at a lesser level than the MUDI (at

Figure 32: Interchange Area Total Time For 50% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial



**Figure 33: Interchange Area Total Time For 30% Left Turns, with Frontage Roads,
1.6 kilometers (1 mile), 5-lane Arterial**



50 percent saturation) as was the case for the scenarios without frontage roads. At 70 percent saturation, the total time for the MUDI configuration was reduced by 21 percent with respect to the SPUI and 18 percent with respect to the traditional diamond. Finally, at 90 percent saturation, the SPUI and traditional diamond continued to perform approximately the same. The total time for the MUDI configuration was reduced by 28 percent with respect to the SPUI and 27 percent with respect to the traditional diamond.

Much the same pattern is shown when the arterial cross-section is changed from a five-lane to a seven-lane cross-section (Figures 34-36). As with the scenarios having no frontage roads, one major difference was that at 30 percent saturation, the total time for both the MUDI and SPUI was reduced by 35 to 40 percent with respect to a traditional diamond for all turning percentages. Additionally, for all left turning percentages, at 90 percent saturation, the traditional diamond operationally outperforms the SPUI. Moreover, for left turning percentages of 50 and 30 percent, the SPUI performed similar to the traditional diamond at saturation levels of 50 and 70 percent. However, in the scenario where left turning percentage was set at 70 percent, the results of the MUDI simulations are not valid past the 70 percent saturation mark. This is due to a spillback of traffic on one of the model's entry links, which resulted in delay occurring outside the environment of the analysis.

As with the scenarios involving the performance of the interchange configurations without frontage roads, the MUDI configuration with frontage roads either operationally equaled or outperformed both the SPUI and the traditional diamond.

Figure 34: Interchange Area Total Time For 70% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure 35: Interchange Area Total Time For 50% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial





Figure 36: Interchange Area Total Time For 30% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial



7.4 Migration of Delay with Frontage Roads


When the operation of the downstream nodes was examined for evidence of the migration of delay, a trend was evident. For example, in the scenario representing 50 percent left-turning traffic, frontage roads and a five-lane arterial cross-section (Figure 37), there is evidence of a “dumping” effect from both the SPUI and traditional diamond interchange configurations. This trend is also exhibited when the arterial cross-section is widened to seven-lanes (Figure 38). Thus, for all cases involving frontage roads, the MUDI was operationally superior in having less migration of delay to the downstream intersections.

7.5 Sensitivity to Proximity of Closest Downstream Node


The affect that the proximity of the closest downstream node has on either the MUDI or SPUI interchange operation was also studied. Three spacing scenarios were considered:

- 1.6 kilometers (one mile) which allows for perfect progression along the arterial while maintaining separation between the intersection and interchange area;
- 1.2 kilometers (three-quarter mile) which does not allow perfect progression along the arterial, but still maintains separation between the intersection and interchange area;
- 0.8 kilometers (one-half mile) which also allows for perfect progression along the arterial, but the proximity of the intersection to the interchange area may affect operation.

Figure 37: Downstream Area Total Time For 50% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial



**Figure 38: Downstream Area Total Time For 50% Left Turns, with Frontage Roads,
1.6 kilometers (1 mile), 7-lane Arterial**



In addition, all the scenarios involving sensitivity testing of the proximity of the downstream node were modeled without the presence of frontage roads.

When modeled with a five-lane arterial cross-section, 70 percent left-turns and 30 to 50 percent saturation, the MUDI configuration (Figure 39) performed approximately the same for all three spacing scenarios. In addition, the MUDI configurations with the closest downstream node placed at 1.6 kilometers (one-mile) and 1.2 kilometers (three-quarter mile) from the interchange continued to perform approximately the same for all levels of saturation. However, at 70 percent saturation and greater, the MUDI configuration with the closest downstream node placed at 0.8 kilometers (one-half mile) from the interchange exhibited greater total time than the other two MUDI spacing scenarios. At 70 percent saturation, the MUDI 0.8 kilometer spacing scenario had approximately 40 percent more total time than the other MUDI spacing scenarios, while at 90 percent saturation, the total time was 35 percent more.

When the percent left-turns was reduced to 50 percent (Figure 40), the simulation results for the MUDI configuration were similar to that of the 70 percent left-turning scenario described above. However, when the percent left-turns was reduced to 30 percent (Figure 41), the MUDI configuration performed approximately the same for all three spacing scenarios and all levels of saturation. In addition, when the arterial cross-section was changed to seven lanes, the MUDI configuration performed approximately the same for all three spacing scenarios and all levels of saturation.

Thus, the only conditions where the MUDI configuration was affected by the spacing of the closest downstream node were the scenarios using 70 percent left turning traffic, an

Figure 39: Interchange Area Total Time for 70% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios




Figure 40: Interchange Area Total Time for 50% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios





Figure 41: Interchange Area Total Time for 30% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios



arterial cross-section of five lanes, saturation levels of 70 percent or greater and a proximity of 0.8 kilometers (one-half mile). However, the models had been designed with an imbalance in traffic flow of 70/30 between traffic approaching from the left and traffic approaching from the right (Figure 14). In addition, this increase in total time only appeared with a left-turning percentage of 70 percent, an arterial cross-section of five lanes and when the model was operating at near capacity. Thus, the most likely cause of this increase in total time is a spillback from the limited storage available between the downstream intersection and the interchange.

When modeled with a five-lane arterial cross-section, 70 percent left turns and 30 percent saturation, the SPUI configuration (Figure 39) performed approximately the same for all three spacing scenarios. However, at 50 percent saturation, the total time for the SPUI configurations with 1.2 kilometer (three-quarter mile) and 0.8 kilometer (one-half mile) separation was approximately 35 percent greater when compared to the 1.6 kilometer (one mile) spacing scenario. At saturation levels of 70 percent or greater, the SPUI configuration with 1.6 kilometer (one mile) separation performed approximately the same as the SPUI configuration with a 1.2 kilometer (three-quarter mile) separation. However, at 70 and 90 percent saturation, the total time for the SPUI configuration with 0.8 kilometer (one-half mile) separation was approximately 15 percent and 20 percent greater, respectively, when compared to the other SPUI spacing scenarios. These results are also reflected in the performance of the SPUI configuration with a seven-lane arterial cross-section.

When the percent left-turns was reduced to 50 percent (Figure 40), the simulation results were similar to that of the 70 percent left-turn scenario for saturation levels of 30, 50,

and 90 percent. However, at 70 percent saturation, the SPUI configuration performed approximately the same for all spacing scenarios. When the percent left-turns was reduced to 30 percent (Figure 41), the simulation results were also similar to the 70 percent left-turn scenario for all saturation levels. At both 50 and 30 percent left-turning traffic, the scenarios modeled with a seven-lane arterial cross-section reflected similar results.

Unlike the MUDI configuration, the total time for the SPUI configuration was adversely affected for all percent left-turning scenarios when the spacing to the closest downstream node was reduced to 0.8 kilometers (one-half mile). In addition, at 50 percent saturation, the scenarios modeling a separation of 1.2 kilometers (three-quarter mile) resulted in greater total time than the comparable models with a separation of 1.6 kilometers (one mile).

In all cases, the performance of the MUDI configuration with a separation of 1.6 kilometers (one mile) or 1.2 kilometers (three-quarter mile) either equals or exceeds the operational performance of the SPUI. In addition, for levels of saturation of 50 percent or less, the MUDI configuration with a separation of 0.8 kilometers (one-half mile) also either equals or exceeds the operational performance of the SPUI. Furthermore, at higher saturation levels, the operational performance of the SPUI configuration was adversely affected by a separation of 0.8 kilometers (one-half mile). Thus, in most cases, the MUDI configuration appears to be insensitive to the proximity of the closest downstream node, while the SPUI configuration is sensitive.

For both arterial cross-sections and all three spacing scenarios of the downstream node, the MUDI configuration (Figures 42 and 43) showed no evidence of migration of delay.

Figure 42: Downstream Area Total Time for 50% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios





Figure 43: Downstream Area Total Time for 50% Left Turns, w/out Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios



In addition, the SPUI configuration with a five-lane cross-section and 1.6 kilometer (one mile) spacing also showed no evidence of migration of delay to the downstream nodes. However, for levels of saturation of 50 percent or greater, all other SPUI configuration scenarios resulted in higher total times, suggesting a “dumping” effect.

8.0 CONCLUSIONS

- Design and operation of SPUIs vary greatly from state to state.
- SPUI with the cross-road going over the freeway is the preferred design.
- SPUI operation is sensitive to geometric size.
- SPUI operation is adversely affected if the interchange is skewed.
- The need for pavement markings is paramount with a SPUI.
- SPUI operation is adversely affected with the addition of frontage roads.
- MUDI operation, in most situations, is superior to that of a SPUI and traditional diamond interchange configurations.
- At levels of traffic near capacity, the traditional diamond interchange is often operationally equal to, or superior to, a SPUI.
- There was less migration of delay to downstream intersections with a MUDI configuration than with either a SPUI or traditional diamond configuration.
- MUDI operation, in most situations, is insensitive to the proximity of the closest downstream node, while the SPUI operation is sensitive.

9.0 REFERENCES

1. Bonneson, James A., and Carroll J. Messer. A National Survey of Single-Point Urban Interchanges, Texas Transportation Institute, College Station, Texas, 1989.
2. Messer, Carroll, J., and James A. Bonneson. Single Point Urban Interchange Design and Operations Analysis, National Cooperative Highway Research Program Report 345, TRB, National Research Council, Washington, D.C., 1989.
3. Fowler, Brian C. An Operational Comparison of the Single-Point Urban and Tight-Diamond Interchanges. ITE Journal, April, 1993.
4. Leisch, J. P., T. Urbanik and J. P. Oxley. A Comparison of Two Diamond Interchange Forms in Urban Areas, ITE Journal, May, 1989.
5. Abbey, Lester and Glen S. Thurgood. Design and Operational Features of the Single Point Urban Interchange, Utah Department of Transportation, Salt Lake City, Utah, June 1991.
6. TRAF User Reference Guide, U.S. Department of Transportation, FHWA, April 1993.

APPENDICES

APPENDIX A

| MUDI w/out Frontage Roads | | | | | | | | | | | |
|---|---------------|------------------|--------|-------------------|----------|--------|---------|-------------|-------------------------|------------|-------------------------|
| Major Crossroad = 5-lane | | | | | | | | | | | |
| Distance to Closest Intersection = 1 mile | | | | | | | | | | | |
| Interchange Area | | Major Entry Link | | Minor | | Ramp | | Interchange | | Downstream | |
| % Left Turns | % Right Turns | % Sat | Volume | Entry Link Volume | Volume | Volume | 70%/30% | Area | Total Time (veh. hours) | Area | Total Time (veh. hours) |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 81 | 139 | | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 152 | 264 | | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 302 | 530 | | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 381 | 645 | | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 417 | 1030 | | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 80 | 139 | | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 149 | 247 | | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 277 | 423 | | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 327 | 742 | | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 368 | 899 | | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 79 | 139 | | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 146 | 263 | | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 243 | 507 | | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 344 | 662 | | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 331 | 912 | | | | |

Table A.1: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial.

| MUDI w/out Frontage Roads | | | | | | | | | |
|---|---------------|-------------------|--------|-------------------|----------|-------------|------|------------------|----------------------------|
| Major Crossroad = 7-lane | | | | | | | | | |
| Distance to Closest Intersection = 1 mile | | | | | | | | | |
| Interchange Area | | Major Entry Links | | Minor Entry Links | | Ramp Volume | | Interchange Area | |
| % Left Turns | % Right Turns | % Sat | Volume | Volume | Volume | 70%/30% | Area | Total Time | Downstream Area Total Time |
| | | | | | | | | (veh. hours) | |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 102 | 180 | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 195 | 373 | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 382 | 599 | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 463 | 780 | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 478 | 940 | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 102 | 181 | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 189 | 368 | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 342 | 669 | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 391 | 784 | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 415 | 955 | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 100 | 180 | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 185 | 390 | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 379 | 686 | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 416 | 754 | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 464 | 957 | | |

Table A.2: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial.

| SPUI w/out Frontage Roads Major Crossroad = 5-lane Distance to Closest Intersection = 1 mile | | | | | | | | | | | |
|--|------------------|----------------------------|------|--------------------------------|----------|----------------|---------|--|--|---|--|
| Interchange Area Major Flow | | Major Entry Links % Sat | | Minor Entry Links Volume | | Ramp Volume | | Interchange Area Total Time (veh. hours) | | Downstream Area Total Time (veh. hours) | |
| % Left Turns | % Right Turns | | | | | | 70%/30% | | | | |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 81 | 113 | | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 148 | 226 | | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 402 | 578 | | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 451 | 839 | | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 459 | 968 | | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 79 | 114 | | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 144 | 232 | | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 336 | 545 | | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 423 | 842 | | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 445 | 995 | | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 76 | 114 | | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 140 | 234 | | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 336 | 582 | | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 449 | 854 | | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 458 | 932 | | | | |

Table A.3: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial.

| SPUI w/out Frontage Roads Major Crossroad = 7-lane Distance to Closest Intersection = 1 mile | | | | | | | | | | | |
|--|------------------|----------------------------|------|--------------------------------|----------|----------------|------|--|--|---|--|
| Interchange Area Major Flow | | Major Entry Links % Sat | | Minor Entry Links Volume | | Ramp Volume | | Interchange Area Total Time (veh. hours) | | Downstream Area Total Time (veh. hours) | |
| % Left Turns | % Right Turns | | | | | 70%/30% | | | | | |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 105 | 184 | | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 285 | 370 | | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 498 | 998 | | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 625 | 1122 | | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 646 | 1394 | | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 104 | 183 | | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 287 | 369 | | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 447 | 987 | | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 532 | 1036 | | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 609 | 1409 | | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 101 | 149 | | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 282 | 379 | | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 443 | 1146 | | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 524 | 1149 | | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 599 | 1148 | | | | |

Table A.4: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial.

| DIAMOND w/out Frontage Roads | | | | | | | | | |
|---|---------------|-------------------|--------|-------------|----------|--------|---------|-------------|-------------------------|
| Major Crossroad = 5-lane | | | | | | | | | |
| Distance to Closest Intersection = 1 mile | | | | | | | | | |
| Interchange Area | | Major Entry Links | | Minor | | Ramp | | Interchange | |
| % Left Turns | % Right Turns | % Sat | Volume | Entry Links | Volume | Volume | 70%/30% | Area | Total Time (veh. hours) |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 87 | 143 | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 382 | 393 | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 469 | 895 | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 478 | 1015 | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 531 | 1245 | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 84 | 142 | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 296 | 399 | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 447 | 881 | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 481 | 1117 | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 484 | 1115 | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 79 | 143 | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 289 | 422 | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 336 | 887 | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 383 | 1147 | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 456 | 1219 | | |

Table A.5: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, without Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial.

| DIAMOND w/out Frontage Roads | | | | | | | | | |
|---|-----------------|------------------|-------------------|--------|--------------------------------|----------------|--|---|--|
| Major Crossroad = 7-lane | | | | | | | | | |
| Distance to Closest Intersection = 1 mile | | | | | | | | | |
| Interchange Area Major Flow | % Left Turns | % Right Turns | Major Entry Links | | Minor Entry Links Volume | Ramp Volume | Interchange Area Total Time (veh. hours) | Downstream Area Total Time (veh. hours) | |
| | | | % Sat | Volume | | | | | |
| 70 | 30 | 30 | 0.3 | 1080 | 463 | 540/231 | 163 | 182 | |
| 70 | 30 | 30 | 0.5 | 1800 | 771 | 900/386 | 365 | 621 | |
| 70 | 30 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 555 | 1117 | |
| 70 | 30 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 647 | 1368 | |
| 70 | 30 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 680 | 1420 | |
| 50 | 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 159 | 182 | |
| 50 | 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 375 | 688 | |
| 50 | 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 430 | 1080 | |
| 50 | 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 593 | 1448 | |
| 50 | 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 579 | 1411 | |
| 30 | 70 | 70 | 0.3 | 1080 | 463 | 540/231 | 157 | 182 | |
| 30 | 70 | 70 | 0.5 | 1800 | 771 | 900/386 | 363 | 663 | |
| 30 | 70 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 408 | 1071 | |
| 30 | 70 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 457 | 1383 | |
| 30 | 70 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 464 | 1393 | |

Table A.6: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, without Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial.

| MUDI w/ Frontage Roads Major Crossroad = 5-lane Distance to Closest Intersection = 1 mile | | | | | | | | | | | | | |
|---|------------------|-------------------------|-----|----------------------------|------|--------------------------------|-----|----------------|--|--------------------------------------|--|-------------------------------------|--|
| Interchange Area Major Flow | | Service Drive Volume | | Major Entry Links % Sat | | Minor Entry Links Volume | | Ramp Volume | | Interchange Area Total Time | | Downstream Area Total Time | |
| % Left Turns | % Right Turns | 70%/30% | | | | | | 70%/30% | | (veh. hours) | | (veh. hours) | |
| 70 | 30 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 90 | 84 | | | | | |
| 70 | 30 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 182 | 162 | | | | | |
| 70 | 30 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 377 | 338 | | | | | |
| 70 | 30 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 438 | 433 | | | | | |
| 70 | 30 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 553 | 486 | | | | | |
| 50 | 50 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 89 | 86 | | | | | |
| 50 | 50 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 164 | 164 | | | | | |
| 50 | 50 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 313 | 347 | | | | | |
| 50 | 50 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 403 | 422 | | | | | |
| 50 | 50 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 386 | 533 | | | | | |
| 30 | 70 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 88 | 87 | | | | | |
| 30 | 70 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 161 | 168 | | | | | |
| 30 | 70 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 302 | 375 | | | | | |
| 30 | 70 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 373 | 379 | | | | | |
| 30 | 70 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 405 | 908 | | | | | |

Table A.7: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial.

| MUDI w/ Frontage Roads Major Crossroad = 7-lane Distance to Closest Intersection = 1 mile | | | | | | | | | | | | | | |
|---|------------------|-------------------------|---------|-----------------------------|------|--------------------------------|----------|----------------|---------|--------------------------------------|--------------|-------------------------------------|--------------|--|
| Interchange Area Major Flow | | Service Drive Volume | | Major Entry Links Volume | | Minor Entry Links Volume | | Ramp Volume | | Interchange Area Total Time | | Downstream Area Total Time | | |
| % Left Turns | % Right Turns | 70%/30% | | % Sat | | | | | 70%/30% | | (veh. hours) | | (veh. hours) | |
| 70 | 30 | 180/77 | 300/129 | 0.3 | 1080 | 463 | 540/231 | 111 | 109 | | | | | |
| 70 | 30 | 300/129 | 420/180 | 0.5 | 1800 | 771 | 900/386 | 280 | 243 | | | | | |
| 70 | 30 | 420/180 | 540/231 | 0.7 | 2520 | 1080 | 1260/540 | 545 | 364 | | | | | |
| 70 | 30 | 540/231 | 600/257 | 0.9 | 3240 | 1388 | 1620/694 | 342 | 271 | | | | | |
| 70 | 30 | 600/257 | 180/77 | 1.0 | 3600 | 1543 | 1800/771 | 259 | 200 | | | | | |
| 50 | 50 | 180/77 | 300/129 | 0.3 | 1080 | 463 | 540/231 | 109 | 110 | | | | | |
| 50 | 50 | 300/129 | 420/180 | 0.5 | 1800 | 771 | 900/386 | 204 | 255 | | | | | |
| 50 | 50 | 420/180 | 540/231 | 0.7 | 2520 | 1080 | 1260/540 | 411 | 404 | | | | | |
| 50 | 50 | 540/231 | 600/257 | 0.9 | 3240 | 1388 | 1620/694 | 541 | 492 | | | | | |
| 50 | 50 | 600/257 | 180/77 | 1.0 | 3600 | 1543 | 1800/771 | 527 | 978 | | | | | |
| 30 | 70 | 180/77 | 300/129 | 0.3 | 1080 | 463 | 540/231 | 107 | 113 | | | | | |
| 30 | 70 | 300/129 | 420/180 | 0.5 | 1800 | 771 | 900/386 | 198 | 266 | | | | | |
| 30 | 70 | 420/180 | 540/231 | 0.7 | 2520 | 1080 | 1260/540 | 371 | 404 | | | | | |
| 30 | 70 | 540/231 | 600/257 | 0.9 | 3240 | 1388 | 1620/694 | 487 | 435 | | | | | |
| 30 | 70 | 600/257 | 180/77 | 1.0 | 3600 | 1543 | 1800/771 | 506 | 575 | | | | | |

Table A.8: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial.

| SPUI w/ Frontage Roads Major Crossroad = 5-lane Distance to Closest Intersection = 1 mile | | | | | | | | | | |
|---|------------------|----------------------------|----------------------------|--------------------------------|----------------|--------------------------------------|-------------------------------------|--|--|--|
| Interchange Area Major Flow | | Service Drive Volume | Major Entry Links % Sat | Minor Entry Links Volume | Ramp Volume | Interchange Area Total Time | Downstream Area Total Time | | | |
| % Left Turns | % Right Turns | 70%/30% | | | 70%/30% | (veh. hours) | (veh. hours) | | | |
| 70 | 30 | 180/77 | 0.3 | 1080 | 540/231 | 96 | 147 | | | |
| 70 | 30 | 300/129 | 0.5 | 1800 | 900/386 | 230 | 283 | | | |
| 70 | 30 | 420/180 | 0.7 | 2520 | 1260/540 | 458 | 774 | | | |
| 70 | 30 | 540/231 | 0.9 | 3240 | 1620/694 | 503 | 1097 | | | |
| 70 | 30 | 600/257 | 1.0 | 3600 | 1800/771 | 516 | 1387 | | | |
| 50 | 50 | 180/77 | 0.3 | 1080 | 540/231 | 93 | 147 | | | |
| 50 | 50 | 300/129 | 0.5 | 1800 | 900/386 | 186 | 288 | | | |
| 50 | 50 | 420/180 | 0.7 | 2520 | 1260/540 | 398 | 803 | | | |
| 50 | 50 | 540/231 | 0.9 | 3240 | 1620/694 | 526 | 1132 | | | |
| 50 | 50 | 600/257 | 1.0 | 3600 | 1800/771 | 555 | 1347 | | | |
| 30 | 70 | 180/77 | 0.3 | 1080 | 540/231 | 89 | 141 | | | |
| 30 | 70 | 300/129 | 0.5 | 1800 | 900/386 | 214 | 275 | | | |
| 30 | 70 | 420/180 | 0.7 | 2520 | 1260/540 | 383 | 759 | | | |
| 30 | 70 | 540/231 | 0.9 | 3240 | 1620/694 | 516 | 1043 | | | |
| 30 | 70 | 600/257 | 1.0 | 3600 | 1800/771 | 538 | 1243 | | | |

Table A.9: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial.

| SPUI w/ Frontage Roads Major Crossroad = 7-lane Distance to Closest Intersection = 1 mile | | | | | | | | | |
|---|-------------------------|----------------------------|--------------------------------|----------------|--------------------------------------|-------------------------------------|--|--|--|
| Interchange Area Major Flow | Service Drive Volume | Major Entry Links % Sat | Minor Entry Links Volume | Ramp Volume | Interchange Area Total Time | Downstream Area Total Time | | | |
| % Left Turns | 70%/30% | | | 70%/30% | (veh. hours) | (veh. hours) | | | |
| 70 | 180/77 | 0.3 | 463 | 540/231 | 120 | 188 | | | |
| 70 | 300/129 | 0.5 | 771 | 900/386 | 370 | 419 | | | |
| 70 | 420/180 | 0.7 | 1080 | 1260/540 | 605 | 1017 | | | |
| 70 | 540/231 | 0.9 | 1388 | 1620/694 | 668 | 1389 | | | |
| 70 | 600/257 | 1.0 | 1543 | 1800/771 | 691 | 1324 | | | |
| 50 | 180/77 | 0.3 | 463 | 540/231 | 118 | 189 | | | |
| 50 | 300/129 | 0.5 | 771 | 900/386 | 353 | 419 | | | |
| 50 | 420/180 | 0.7 | 1080 | 1260/540 | 498 | 1070 | | | |
| 50 | 540/231 | 0.9 | 1388 | 1620/694 | 695 | 1428 | | | |
| 50 | 600/257 | 1.0 | 1543 | 1800/771 | 730 | 1317 | | | |
| 30 | 180/77 | 0.3 | 463 | 540/231 | 114 | 188 | | | |
| 30 | 300/129 | 0.5 | 771 | 900/386 | 324 | 398 | | | |
| 30 | 420/180 | 0.7 | 1080 | 1260/540 | 478 | 975 | | | |
| 30 | 540/231 | 0.9 | 1388 | 1620/694 | 673 | 1292 | | | |
| 30 | 600/257 | 1.0 | 1543 | 1800/771 | 696 | 1397 | | | |

Table A.10: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial.

| DIAMOND w/ Frontage Roads Major Crossroad = 5-lane Distance to Closest Intersection = 1 mile | | | | | | | | | | |
|--|-----------------|------------------|----------------------------|---------|----------------------------|-----------------------------|--------------------------------|----------------|--|---|
| Interchange Area Major Flow | % Left Turns | % Right Turns | Service Drive Volume | 70%/30% | Major Entry Links % Sat | Major Entry Links Volume | Minor Entry Links Volume | Ramp Volume | Interchange Area Total Time (veh. hours) | Downstream Area Total Time (veh. hours) |
| | | | | | | | | | | |
| 70 | 30 | 30 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 109 | 149 | |
| 70 | 30 | 30 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 440 | 401 | |
| 70 | 30 | 30 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 528 | 879 | |
| 70 | 30 | 30 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 654 | 1129 | |
| 70 | 30 | 30 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 715 | 1223 | |
| 50 | 50 | 50 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 91 | 148 | |
| 50 | 50 | 50 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 400 | 429 | |
| 50 | 50 | 50 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 508 | 895 | |
| 50 | 50 | 50 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 539 | 1147 | |
| 50 | 50 | 50 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 569 | 1197 | |
| 30 | 70 | 70 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 85 | 148 | |
| 30 | 70 | 70 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 298 | 428 | |
| 30 | 70 | 70 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 370 | 911 | |
| 30 | 70 | 70 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 511 | 1201 | |
| 30 | 70 | 70 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 520 | 1254 | |

Table A.11: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial.

| DIAMOND w/ Frontage Roads | | | | | | | | | | |
|---|---------------|----------------------|-------------------------|--------------------------|--------------------------|-------------|-----------------------------|----------------------------|--|--|
| Major Crossroad = 7-lane | | | | | | | | | | |
| Distance to Closest Intersection = 1 mile | | | | | | | | | | |
| Interchange Area | Major Flow | Service Drive Volume | Major Entry Links % Sat | Major Entry Links Volume | Minor Entry Links Volume | Ramp Volume | Interchange Area Total Time | Downstream Area Total Time | | |
| % Left Turns | % Right Turns | 70%/30% | | | | 70%/30% | (veh. hours) | (veh. hours) | | |
| 70 | 30 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 173 | 173 | | |
| 70 | 30 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 484 | 616 | | |
| 70 | 30 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 574 | 1154 | | |
| 70 | 30 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 673 | 1330 | | |
| 70 | 30 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 736 | 1321 | | |
| 50 | 50 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 168 | 188 | | |
| 50 | 50 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 361 | 602 | | |
| 50 | 50 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 556 | 1145 | | |
| 50 | 50 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 672 | 1349 | | |
| 50 | 50 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 669 | 1399 | | |
| 30 | 70 | 180/77 | 0.3 | 1080 | 463 | 540/231 | 159 | 188 | | |
| 30 | 70 | 300/129 | 0.5 | 1800 | 771 | 900/386 | 362 | 619 | | |
| 30 | 70 | 420/180 | 0.7 | 2520 | 1080 | 1260/540 | 438 | 1129 | | |
| 30 | 70 | 540/231 | 0.9 | 3240 | 1388 | 1620/694 | 505 | 1293 | | |
| 30 | 70 | 600/257 | 1.0 | 3600 | 1543 | 1800/771 | 538 | 1241 | | |

Table A.12: Simulation Results for Modeling Scenarios Involving the Traditional Diamond Interchange, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial.

| MUDI w/out Frontage Roads | | | | | | | | | | | |
|---|---------------|-------------------|--------|-------------|----------|--------|---------|--------------|--------------|------------|--------------|
| Major Crossroad = 5-lane | | | | | | | | | | | |
| Distance to Closest Intersection = 3/4 mile | | | | | | | | | | | |
| Interchange Area | | Major Entry Links | | Minor | | Ramp | | Interchange | | Downstream | |
| % Left Turns | % Right Turns | % Sat | Volume | Entry Links | Volume | Volume | 70%/30% | Area | Total Time | Area | Total Time |
| | | | | | | | | (veh. hours) | (veh. hours) | | (veh. hours) |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 85 | 133 | | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 150 | 256 | | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 280 | 492 | | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 374 | 667 | | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 505 | 980 | | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 83 | 134 | | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 147 | 253 | | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 271 | 494 | | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 331 | 707 | | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 366 | 921 | | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 82 | 137 | | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 144 | 262 | | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 263 | 614 | | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 320 | 698 | | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 364 | 947 | | | | |

Table A.13: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.2 kilometers (3/4 mile), 5-lane Arterial.

| MUDI w/out Frontage Roads | | | | | | | | | |
|---|-----------------|------------------|-------------------|--------|--------------------------------|----------------|--|---|--|
| Major Crossroad = 7-lane | | | | | | | | | |
| Distance to Closest Intersection = 3/4 mile | | | | | | | | | |
| Interchange Area Major Flow | % Left Turns | % Right Turns | Major Entry Links | | Minor Entry Links Volume | Ramp Volume | Interchange Area Total Time (veh. hours) | Downstream Area Total Time (veh. hours) | |
| | | | % Sat | Volume | | | | | |
| 70 | 30 | 30 | 0.3 | 1080 | 463 | 540/231 | 107 | 170 | |
| 70 | 30 | 30 | 0.5 | 1800 | 771 | 900/386 | 201 | 377 | |
| 70 | 30 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 372 | 563 | |
| 70 | 30 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 442 | 774 | |
| 70 | 30 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 486 | 941 | |
| 50 | 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 105 | 172 | |
| 50 | 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 189 | 388 | |
| 50 | 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 338 | 696 | |
| 50 | 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 399 | 739 | |
| 50 | 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 408 | 927 | |
| 30 | 70 | 70 | 0.3 | 1080 | 463 | 540/231 | 104 | 175 | |
| 30 | 70 | 70 | 0.5 | 1800 | 771 | 900/386 | 187 | 362 | |
| 30 | 70 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 359 | 725 | |
| 30 | 70 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 414 | 773 | |
| 30 | 70 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 416 | 934 | |

Table A.14: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 1.2 kilometers (3/4 mile), 7-lane Arterial.

| SPUI w/out Frontage Roads | | | | | | | | | | | |
|---|---------|-------------------|-------|-------------|--------|--------|----------|--------------|--------------|--------------|--------------|
| Major Crossroad = 5-lane | | | | | | | | | | | |
| Distance to Closest Intersection = 3/4 mile | | | | | | | | | | | |
| Interchange Area | | Major Entry Links | | Minor | | Ramp | | Interchange | | Downstream | |
| Major Flow | | Volume | | Entry Links | | Volume | | Area | | Area | |
| % Left | % Right | % Sat | Turns | Volume | Volume | Volume | 70%/30% | Total | Total | Total | Total |
| Turns | Turns | | | | | | | Time | Time | Time | Time |
| | | | | | | | | (veh. hours) | (veh. hours) | (veh. hours) | (veh. hours) |
| 70 | 30 | 0.3 | | 1080 | 463 | | 540/231 | 84 | | 143 | |
| 70 | 30 | 0.5 | | 1800 | 771 | | 900/386 | 236 | | 292 | |
| 70 | 30 | 0.7 | | 2520 | 1080 | | 1260/540 | 422 | | 806 | |
| 70 | 30 | 0.9 | | 3240 | 1388 | | 1620/694 | 448 | | 1101 | |
| 70 | 30 | 1.0 | | 3600 | 1543 | | 1800/771 | 460 | | 1242 | |
| 50 | 50 | 0.3 | | 1080 | 463 | | 540/231 | 82 | | 143 | |
| 50 | 50 | 0.5 | | 1800 | 771 | | 900/386 | 228 | | 292 | |
| 50 | 50 | 0.7 | | 2520 | 1080 | | 1260/540 | 354 | | 799 | |
| 50 | 50 | 0.9 | | 3240 | 1388 | | 1620/694 | 419 | | 1173 | |
| 50 | 50 | 1.0 | | 3600 | 1543 | | 1800/771 | 439 | | 1270 | |
| 30 | 70 | 0.3 | | 1080 | 463 | | 540/231 | 80 | | 145 | |
| 30 | 70 | 0.5 | | 1800 | 771 | | 900/386 | 177 | | 270 | |
| 30 | 70 | 0.7 | | 2520 | 1080 | | 1260/540 | 355 | | 838 | |
| 30 | 70 | 0.9 | | 3240 | 1388 | | 1620/694 | 446 | | 1128 | |
| 30 | 70 | 1.0 | | 3600 | 1543 | | 1800/771 | 463 | | 1283 | |

Table A.15: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.2 kilometers (3/4 mile), 5-lane Arterial.

| SPUI w/out Frontage Roads | | | | | | | | | | | |
|---|---------------|-------------------|--------|-------------|----------|--------|---------|--------------|------------|--------------|------------|
| Major Crossroad = 7-lane | | | | | | | | | | | |
| Distance to Closest Intersection = 3/4 mile | | | | | | | | | | | |
| Interchange Area | | Major Entry Links | | Minor | | Ramp | | Interchange | | Downstream | |
| % Left Turns | % Right Turns | % Sat | Volume | Entry Links | Volume | Volume | 70%/30% | Area | Total Time | Area | Total Time |
| | | | | | | | | (veh. hours) | | (veh. hours) | |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 112 | 187 | | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 382 | 451 | | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 539 | 1225 | | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 653 | 1576 | | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 665 | 1703 | | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 105 | 183 | | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 386 | 473 | | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 488 | 1277 | | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 554 | 1389 | | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 627 | 1432 | | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 106 | 185 | | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 372 | 487 | | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 476 | 1171 | | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 585 | 1286 | | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 649 | 1385 | | | | |

Table A.16: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 1.2 kilometers (3/4 mile), 7-lane Arterial.

| MUDI w/out Frontage Roads Major Crossroad = 5-lane Distance to Closest Intersection = 1/2 mile | | | | | | | | | | | |
|--|------------------|----------------------------|------|--------------------------------|----------|---------------------------|--------|--|------|---|------|
| Interchange Area Major Flow | | Major Entry Links % Sat | | Minor Entry Links Volume | | Ramp Volume 70%/30% | | Interchange Area Total Time (veh. hours) | | Downstream Area Total Time (veh. hours) | |
| % Left Turns | % Right Turns | | | | Volume | Volume | Volume | Area | Time | Area | Time |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 82 | 131 | | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 152 | 256 | | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 489 | 554 | | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 585 | 652 | | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 369 | 904 | | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 81 | 135 | | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 146 | 262 | | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 414 | 535 | | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 579 | 820 | | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 537 | 977 | | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 79 | 139 | | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 143 | 271 | | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 270 | 534 | | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 294 | 746 | | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 409 | 1011 | | | | |

Table A.17: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 0.8 kilometers (1/2 mile), 5-lane Arterial.

| MUDI w/out Frontage Roads | | | | | | | | | |
|---|-----------------|------------------|-------------------|--------|--------------------------------|----------------|--|---|--|
| Major Crossroad = 7-lane | | | | | | | | | |
| Distance to Closest Intersection = 1/2 mile | | | | | | | | | |
| Interchange Area Major Flow | % Left Turns | % Right Turns | Major Entry Links | | Minor Entry Links Volume | Ramp Volume | Interchange Area Total Time (veh. hours) | Downstream Area Total Time (veh. hours) | |
| | | | % Sat | Volume | | | | | |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 103 | 171 | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 193 | 466 | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 422 | 548 | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 478 | 810 | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 483 | 877 | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 101 | 174 | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 186 | 382 | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 507 | 664 | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 416 | 802 | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 433 | 938 | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 100 | 180 | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 184 | 365 | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 350 | 645 | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 538 | 888 | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 412 | 959 | | |

Table A.18: Simulation Results for Modeling Scenarios Involving the Michigan Urban Diamond Interchange (MUDI), without Frontage Roads, 0.8 kilometers (1/2 mile), 7-lane Arterial.

| SPUI w/out Frontage Roads Major Crossroad = 5-lane Distance to Closest Intersection = 1/2 mile | | | | | | | | | | | |
|--|------------------|----------------------------|------|--------------------------------|----------|----------------|------|--|--|---|--|
| Interchange Area Major Flow | | Major Entry Links % Sat | | Minor Entry Links Volume | | Ramp Volume | | Interchange Area Total Time (veh. hours) | | Downstream Area Total Time (veh. hours) | |
| % Left Turns | % Right Turns | | | | | 70%/30% | | | | | |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 82 | 143 | | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | 222 | 282 | | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | 471 | 796 | | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | 551 | 1107 | | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | 516 | 1243 | | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | 81 | 150 | | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | 223 | 291 | | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | 357 | 683 | | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | 512 | 1137 | | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | 540 | 1221 | | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | 79 | 146 | | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | 185 | 274 | | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | 426 | 800 | | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | 540 | 1115 | | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | 509 | 1372 | | | | |

Table A.19: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 0.8 kilometers (1/2 mile), 5-lane Arterial.

| SPUI w/out Frontage Roads Major Crossroad = 7-lane Distance to Closest Intersection = 1/2 mile | | | | | | | | | | | |
|--|------------------|-------------------|--------|-----------------------|----------|---------|--------|---------------------------------------|---------------------------------------|---------------------------------------|---------------------------------------|
| Interchange Area Major Flow | | Major Entry Links | | Minor | | Ramp | | Interchange | | Downstream | |
| % Left Turns | % Right Turns | % Sat | Volume | Entry Links Volume | Volume | Volume | Volume | Area Total Time (veh. hours) | Area Total Time (veh. hours) | Area Total Time (veh. hours) | Area Total Time (veh. hours) |
| 70 | 30 | 0.3 | 1080 | 463 | 540/231 | 70%/30% | 110 | 182 | | | |
| 70 | 30 | 0.5 | 1800 | 771 | 900/386 | | 364 | 417 | | | |
| 70 | 30 | 0.7 | 2520 | 1080 | 1260/540 | | 580 | 1050 | | | |
| 70 | 30 | 0.9 | 3240 | 1388 | 1620/694 | | 518 | 1099 | | | |
| 70 | 30 | 1.0 | 3600 | 1543 | 1800/771 | | 741 | 1328 | | | |
| 50 | 50 | 0.3 | 1080 | 463 | 540/231 | | 107 | 186 | | | |
| 50 | 50 | 0.5 | 1800 | 771 | 900/386 | | 395 | 476 | | | |
| 50 | 50 | 0.7 | 2520 | 1080 | 1260/540 | | 452 | 1066 | | | |
| 50 | 50 | 0.9 | 3240 | 1388 | 1620/694 | | 684 | 1221 | | | |
| 50 | 50 | 1.0 | 3600 | 1543 | 1800/771 | | 650 | 1210 | | | |
| 30 | 70 | 0.3 | 1080 | 463 | 540/231 | | 105 | 185 | | | |
| 30 | 70 | 0.5 | 1800 | 771 | 900/386 | | 371 | 454 | | | |
| 30 | 70 | 0.7 | 2520 | 1080 | 1260/540 | | 476 | 1234 | | | |
| 30 | 70 | 0.9 | 3240 | 1388 | 1620/694 | | 505 | 1038 | | | |
| 30 | 70 | 1.0 | 3600 | 1543 | 1800/771 | | 573 | 1107 | | | |

Table A.20: Simulation Results for Modeling Scenarios Involving the Single Point Urban Interchange (SPUI), without Frontage Roads, 0.8 kilometers (1/2 mile), 7-lane Arterial.

APPENDIX B

Figure B.1: Interchange Area Total Time For 70% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial





Figure B.2: Interchange Area Total Time For 50% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial



**Figure B.3: Interchange Area Total Time For 30% Left Turns, w/out Frontage Roads,
1.6 kilometers (1 mile), 5-lane Arterial**




Figure B.4: Interchange Area Total Time For 70% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.5: Interchange Area Total Time For 50% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial





Figure B.6: Interchange Area Total Time For 30% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial



**Figure B.7: Downstream Area Total Time For 70% Left Turns, w/out Frontage Roads,
1.6 kilometers (1 mile), 5-lane Arterial**




Figure B.8: Downstream Area Total Time For 50% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.9: Downstream Area Total Time For 30% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.10: Downstream Area Total Time For 70% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.11: Downstream Area Total Time For 50% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.12: Downstream Area Total Time For 30% Left Turns, w/out Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.13: Interchange Area Total Time For 70% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.14: Interchange Area Total Time For 50% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.15: Interchange Area Total Time For 30% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.16: Interchange Area Total Time For 70% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.17: Interchange Area Total Time For 50% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.18: Interchange Area Total Time For 30% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.19: Downstream Area Total Time For 70% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.20: Downstream Area Total Time For 50% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.21: Downstream Area Total Time For 30% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 5-lane Arterial




Figure B.22: Downstream Area Total Time For 70% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.23: Downstream Area Total Time For 50% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.24: Downstream Area Total Time For 30% Left Turns, with Frontage Roads, 1.6 kilometers (1 mile), 7-lane Arterial




Figure B.25: Interchange Area Total Time for 70% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios




Figure B.26: Interchange Area Total Time for 50% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios




Figure B.27: Interchange Area Total Time for 30% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios




Figure B.28: Interchange Area Total Time for 70% Left Turns, w/out Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios




Figure B.29: Interchange Area Total Time for 50% Left Turns, w/out Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios




Figure B.30: Interchange Area Total Time for 30% Left Turns, w/out Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios




Figure B.31: Downstream Area Total Time for 70% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios




Figure B.32: Downstream Area Total Time for 50% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios




Figure B.33: Downstream Area Total Time for 30% Left Turns, w/out Frontage Roads, 5-lane Arterial, Varying Spacing Scenarios




Figure B.34: Downstream Area Total Time for 70% Left Turns, w/out Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios




Figure B.35: Downstream Area Total Time for 50% Left Turns, w/out Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios




Figure B.36: Downstream Area Total Time for 30% Left Turns, w/out Frontage Roads, 7-lane Arterial, Varying Spacing Scenarios

