

REVISIONS

DESCRIPTION	DATE
[CD-G PS-200, Revision C, Initial Release IRN-200C-001	10 October 1S93 13 October 1995

Distribution authorized to U.S. Government agencies and their contractors for administrative and operational use. Other requests for this document shall be referred to SMC/CZ (AFMC).
DESTRUCTION NOTICE - For classified documents, follow the procedures in DoD 5220.22-M, Industrial Security Manual, Section II-19 or DoD 5200.1-R, Information Security Program Regulation, Chapter IX. For unclassified, Limited Documents, destroy by any method that will prevent disclosure of contents or reconstruction of the document.

APPROVALS

AUTHORIZED SIGNATURES	REPRESENTING	DATE
<i>Carl Wotef</i>	GPS NAVSTAR JPO SMC/CZ (AFMC)	Dec 15 94
<i>JL Cooper</i>	ROCKWELL INTERNATIONAL SPACE SYSTEMS DIVISION	Nov 16, 93
<i>Conroy G. Okey</i>	ROCKWELL INTERNATIONAL COLLINS AVIONICS & COMMUNICATIONS DIVISION	11" 15 - 93
<i>M. B. Kelly</i>	INTERNATIONAL BUSINESS MACHINES (IBM) FEDERAL SYSTEMS COMPANY	12/1/93
<i>David R. Brown *</i>	MARTIN-MARIETTA ASTROSPACE DIVISION	5 August 1994

* An asterisk affixed to the approval signature indicates that the approval is subject to 10 exceptions taken in the "Letter of Exception" contained in Appendix I of this document.

INTERFACE CONTROL DOCUMENT

10 Oct 1993

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN INCHES. TOLERANCES ON: DECIMALS ANGLES XX = ±0.03 ±0° 30' XXX = ±0.01	DR 3Y			ARINC RESEARCH CORPORATION 11770 Warner Ave, Suite 210 Fountain Valley, CA 92708
	CHK 3Y			
THIS DOCUMENT SPECIFIES TECHNICAL REQUIREMENTS AND NOTHING HEREIN CONTAINED SHALL BE DEEMED TO ALTER THE TERMS OF ANY CONTRACT OR PURCHASE ORDER BETWEEN ALL PARTIES AFFECTED.	APPROVALS			ICD TITLE Navstar GPS Space Segment / Navigation User Interfaces
	SIZE A	CODE IDENT No. 6Z691	DRAWING NO. ICD-GPS-200	
	SCALE: N/A	REV: C	SHEET I	

(This page intentionally left blank.)

ICD-GPS-200C
10 OCT 1993

(This page intentionally left blank.)

ICD-GPS-200C
10 OCT 1993

Page Revision Record

<u>Pages</u>	<u>Revision</u>	<u>Pages</u>	<u>Revision</u>
1-II	IRN-200C-001		
iii-iv	Original		
v-vi	IRN-200C-001		
vii-xiv	Original		
1-14	Original		
15-16	IRN-200C-001		
17-50	Original		
51-64b	IRN-200C-001		
65-120	Origins]		
121-122	IRN-200C-001		
123-12s	Original		
129-130	IRN-200C-001		
131-132	Original		
133-134	IRN-200C-001		
135-138	Original		

--

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

(This page intentionally left blank.)

ICD-GPS-200C
10 OCT 1993

TABLE OF CONTENTS

1	SCOPE.....	1
1.1	Scope	1
1.2	Key Dates	1
1.3	ICD Approval and Changes	1
2	APPLICABLE DOCUMENTS	3
2.1	Government Documents	3
2.2	Non. Government Documents	4
3	REQUIREMENTS	5
3.1	Interface Definition	5
3.2	Interface Identification	5
3.2.1	Ranging Codes	5
3.2.1.1	P-Code.....	7
3.2.1.2	Y-Code	7
3.2.1.3	CIA-Code	7
3.2.1.4	Non-Standard Codes	7
3.2.-2	NAV Data	10
3.2.3	L-Band Signal Structure	10
3.3	Interface Criteria	10
3.3.1	Composite Signal	10
3.3.1.1	Frequency Plan	11
3.3.1.2	Correlation Loss	11
3.3.1.3	Carrier Phase Noise	11
3.3.1.4	Spurious Transmissions	12
3.3.1.5	Phase Quadrature	12
3.3.1.6	User-Received Signal Levels	12
3.3.1.7	Equipment Group Delay	14
3.3.1.7.1	Group Delay Uncertainty	14
3.3.1.7.2	Group Delay Differential	14
3.3.1.8	Signal Coherence	14

ICD-GPS-200C
10 OCT 1993

3.3.1.9 Signal Polarization	15
3.3.2 PRN Code Characteristics	15
3.3.2.1 Code Structure	17
3.3.2.2 P-Code Generation	17
3.3.2.3 C/A Code Generation	28
3.3.3 Navigation Data	33
3.3.4 GPS Time and SV Z-Count	33
4 NOT APPLICABLE	37
5 NOT APPLICABLE	39
6 NOTES	41
6.1 Acronyms	41
6.2 Definitions	43
6.2.1 User Range Accuracy	43
6.2.2 SV Block Definitions	43
6.2.2.1 Developmental SVs	43
6.2.2.2 Operational SVs	43
6.2.2.2.1 Block II SVs	44
6.2.2.2.2 Block IIA SVs	44
6.2.2.2.3 Block IIR SVs	44
6.2.3 Operational Interval Definitions	44
6.2.3.1 Normal Operations	44
6.2.3.2 Short-term Extended Operations	44
6.2.3.3 Long-term Extended Operations	45
6.3 Supporting Material	45
6.3.1 Received Signals	45
6.3.2 Extended Navigation Mode (Block II/IIA)	47
6.3.3 Block 11A Mode (Block IIR)	48
6.3.4 Autonomous Navigation Mode (Block IIR)	48
10 APPENDIX I: LETTERS OF EXCEPTION	49
10.1 Scope	49
10.2 Applicable Documents	49

10.3 Letters of Exception]	49
20 APPENDIX II: GPS NAVIGATION DATA STRUCTURE FOR DATA ID NO. 2	65
20.1 Scope	65
20.2 Applicable Documents	65
20.2.1 Government Documents	65
20.2.2 Non-Government Documents	65
20.3 Requirements	66
20.3.1 Data Characteristics	66
20.3.2 Message Structure	66
20.3.3 Message Content	79
20.3.3.1 Telemetry Word (TLM)	79
20.3.3.2 Handover Word (HOW)	79
20.3.3.3 Sub frame 1	82
20.3.3.3.1 Subframe 1 Content	82
20.3.3.3.1.1 Week Number	82
20.3.3.3.1.2 Code(s) on L2 Channel	83
20.3.3.3.1.3 SV Accuracy	83
20.3.3.3.1.4 SV Health	84
20.3.3.3.1.5 Issue of Data, Clock (1 ODC)	85
20.3.3.3.1.6 Data Flag for L2P, Code	85
20.3.3.3.1.7 (Reserved)	85
20.3.3.3.1.8 Estimated Group Delay Differential	85
20.3.3.3.1.9 SV Clock Correction	86
20.3.3.3.2 Subframe 1 Parameter Characteristics	86
20.3.3.3.3 User Algorithms for Subframe 1 Data	86
20.3.3.3.3.1 User Algorithm for SV Clock Correction	88
20.3.3.3.3.2 L1-L2 Correction	90
20.3.3.3.3.3 Ionospheric Correction	91
20.3.3.3.3.4 Example Application of Correction Parameters	91
20.3.3.4 Subframes 2 and 3	91
20.3.3.4.1 Content of Subframes 2 and 3	93

20.3.3.4.2 Subframe 2 and 3 Parameter Characteristics	95
20.3.3.4.3 User Algorithm for Ephemeris Determination	97
20.3.3.4.3.1 Curve Fit Intervals	97
20.3.3.4.3.2 Parameter Sensitivity	101
20.3.3.4.3.3 Coordinate System	101
20.3.3.4.3.4 Geometric Range	102
20.3.3.5 Subframes 4 and 5	102
20.3.3.5.1 Content of Subframes 4 and 5	102
20.3.3.5.1.1 Data ID and SV ID	104
20.3.3.5.1.2 Almanac Data	106
20.3.3.5.1.3 SV Health	109
20.3.3.5.1.4 (Reserved)	112
20.3.3.5.1.5 (Reserved)	112
20.3.3.5.1.6 Anti-Spoof (A-S) Flags and SV Configurations	112
20.3.3.5.1.7 Almanac Reference Week	113
20.3.3.5.1.8 Universal Coordinated Time (UTC) Parameters	113
20.3.3.5.1.9 Ionospheric Data	114
20.3.3.5.1.10 Special Messages	117
20.3.3.5.1.11 Spare Data Fields	118
20.3.3.5.1.12 (Reserved)	118
20.3.3.5.2 Algorithm Related to Subframe 4 and 5 Data	118
20.3.3.5.2.1 Almanac	118
20.3.3.5.2.2 Almanac Reference Time	121
20.3.3.5.2.3 Almanac Time Parameters	121
20.3.3.5.2.4 Universal Coordinated Time (UTC)	122
20.3.3.5.2.5 Ionospheric Model	124
20.3.3.5.2.6 (Reserved)	125
20.3.4 Timing Relationships	129
20.3.4.1 Paging and Cutovers	129
20.3.4.2 SV Time vs. GPS Time	129
20.3.4.3 Speed of Light	129

20.3.4.4 Data Sets	130
20.3.4.5 Reference Times	132
20.3.5 Data Frame Parity	135
20.3.5.1 SV/CS Parity Algorithm	135
20.3.5.2 User Parity Algorithm	135

LIST OF FIGURES

Figure 3-1	Space Vehicle/NAV User Interfaces	6
Figure 3-2	Generation of Codes and Modulating Signals	16
Figure 3-3	X1A Shift Register Generator Configuration	15
Figure 3-4	X1B Shift Register Generator Configuration	19
Figure 3-5	X2A Shift Register Generator Configuration	20
Figure 3-6	X2 B Shift Register Generator Configuration	21
Figure 3-7	P-Code Generation	24
Figure 3-8	P-Code Signal Component Timing	25
Figure 3-9	G1 Shift Register Generator Configuration	29
Figure 3-10	G2 Shift Register Generator Configuration	30
Figure 3-11	C/A-Code Generation	31
Figure 3-12	C/A-Code Timing Relationships	32
Figure 3-13	Time Line Relationship of HOW Message	35
Figure 6-1	User Received Minimum Signal Levels	46
Figure 10-1	Letters of Exception	51
Figure 20-1	Data Format	67
Figure 20-2	TLM and HOW Formats	80
Figure 20-3	Sample Application of Correction Parameters	92
Figure 20-4	Ionospheric Model	126
Figure 20-5	Example Flow Chart for User Implementation of Parity Algorithm	137

LIST OF TABLES

Table 3-I	Code Phase Assignments	S
Table 3-II	Composite L1 Transmitted Signal Phase	13
Table 3-III	Received Minimum RF Signal Strength	13
Table 3-IV	P-Code Reset Timing	26
Table 3-V	Final Code Vector States	27
Table 20-1	Subframe 1 Parameters	87
Table 20-II	Ephemeris Data Definitions	94
Table 20-III	Ephemeris Parameters	96
Table 20-IV	Elements of Coordinate Systems	98
Table 20-V	Data IDs and SV IDs in Subframes 4 and 5	105
Table 20-VI	Almanac Parameters	108
Table 20-VII	NAV Data Health Indications	110
Table 20-VIII	Codes for Health of SV Signal Components	111
Table 20-IX	UTC Parameters	115
Table 20-X	Ionospheric Parameters	116
Table 20-XI	Spare Bits in Subframes 4 and 5	119
Table 20-XII	IODC Values and Data Set Lengths for Block 11 SVs	131
Table 20-XIII	Reference Times for Block II SVs	134
Table 20-XIV	Parity Encoding Equations	136

(This page intentionally left blank.)

∴

ICD-GPS-200C
10 OCT 1993

1. SCOPE

1.1 Scope. This Interface Control Document (ICD) defines the requirements related to the interface between the Space Segment (SS) of the Global Positioning System (GPS) and the Navigation User Segment (US) of the GPS.

1.2 Key Dates. The major milestones for which integration data shall be provided are:

a. (TBD)

1.3 ICD Approval and Changes. ARINC Research Corporation has been designated the Interface Control Contractor (ICC), and is responsible for the basic preparation, approval, distribution, and retention of the ICD in accordance with YEN 75-13A. The following signatories must approve this ICD to make it effective:

- | | |
|-------------------------------------|---|
| a. Space Segment Contractors | BLOCK I/II/IIA
Rockwell International,
Space Systems Division |
| | Block IIR
Martin Marietta,
AstroSpace Division |
| -- | |
| b. Control Segment Contractor | International Business Machines,
Federal Systems Company |
| c. User Segment Contractors | Rockwell International, Collins
Avionics & Communications Division |
| d. Navstar GPS Joint Program Office | SMC/CZ (AFMC) |

ICD-GPS-200C
10 OCT 1993

Initial signature approval of this ICD can be contingent upon a letter of exception delineating those items by paragraph numbers that are not a part of the approval. Such letters of exception can be prepared by any of the signatories and must be furnished to the ICC for inclusion in Appendix I of the approved and officially released version of the ICD.

Changes to the approved version of this ICD can be initiated by any of the signatories and must be approved by all above signatories. The ICC is responsible for the preparation of the change paper, change coordination, and the change approval by all signatories in accordance with YEN 75-13A. Designated signatories can approve proposed changes to this ICD without any increase in the scope of a specific contract by so specifying in a letter of exception.

Such letters of exception must be furnished to the ICC for inclusion in the released version of the approved change and in Appendix I of the subsequent revised issues of the ICD.

Whenever all the issues addressed by a letter of exception are resolved, the respective signatory shall so advise the ICC in writing. When some (but not all) of the exceptions taken by a signatory are resolved, the signatory shall provide the ICC with an updated letter of exception. Based on such notifications -- without processing a proposed interface revision notice (PIRN) for approval -- the ICC will omit the obsolete letter of exception from the next revision of the ICD and will substitute the new one (if required).

Review cycles for all Proposed Interface Revisions Notices (PIRNs) is 45 days after receipt by individual addressees unless a written request for a waiver is submitted to the ICC. Reviewing parties with delinquent responses will be charged with an automatic letter of exception.

ICD-GPS-200C
10 OCT 1993

2. APPLICABLE DOCUMENTS

2.1 Government Documents. The following documents of file issue specified contribute to the definition of the interfaces between the GPS Space Segment and the GPS Navigation User Segment, and form a part of this ICD to the extent specified herein.

Specifications

Federal

None

Military

None

Other Government Activity

None

Standards

Federal

None

Military

None

∴

Other Publications

ICD-GPS-203*,
current issue

Navstar GPS Selective Availability and Anti-Spoofing
Requirements (SECRET) (U)

ICD-GPS-207*,
current issue

Navstar GPS Selective Availability and Anti-Spoofing
Receiver Design Requirements (SECRET) (U)

YEN 75-13A
16 Nov 1979
with Change Notice 1

Interface Control Working Group

ICD-GPS-200C
10 OCT 1993

2.2 Non-Government Documents. The following documents of the issue specified contribute to the definition of the interfaces between the GPS Space Segment and the GPS Navigation User Segment and form a part of this ICD to the extent specified herein.

Specifications

None

Other Publications

None

* ICD-GPS-203 is the applicable document for the signatories of this document (ICD-GPS-200); for all other organizations the applicable document is ICD-GPS-207. In case of conflict between this document (ICD-GPS-200) and either ICD-GPS-203 or ICD-GPS-207, this document shall govern.

--

ICD-GPS-200C
10 OCT 1993

3. REQUIREMENTS

3.1 Interface Definition. As shown in Figure 3-1, the interface between the GPS Space Segment (SS) and the GPS navigation User Segment (US) consists of two radio frequency (RF) links: L1 and L2. Utilizing these links, the space vehicles (SVs) of the SS shall provide continuous earth coverage for signals which provide to the US the ranging codes and the system data needed to accomplish the GPS navigation (NAV) mission. These signals shall be available to a suitably equipped user with RF visibility to an SV. The related selective availability (SA) and anti-spoofing (A-S) requirements are defined in ICD-GPS-203 and/or in ICD-GPS-207 (see note in paragraph 2.1).

3.2 Interface Identification. The carriers of the L-band links are modulated by up to two bit trains, each of which normally is a composite generated by the Modulo-2 addition of a pseudo-random noise (PRN) ranging code and the downlink system data (referred to as N4V data).

3.2.1 Ranging Codes. Three PRN ranging codes are transmitted: the precision (P) code which is the principal NAV ranging code; the Y-code, used in place of the P-code whenever the A-S mode of operation is activated; and the coarse/acquisition (C/A) code which is used primarily for acquisition of the P (or Y) code (denoted as P(Y)). Appropriate code-division-multiplexing techniques allow differentiating between the SVs even though they all transmit at the same L-band frequencies. The SVs will transmit intentionally "incorrect" versions of the C/A and the P(Y) codes where needed to protect the users from receiving and utilizing anomalous NAV signals as a result of a malfunction in the SV'S reference frequency generation system. These two "incorrect" codes are termed non-standard C/A (NSC) and non-standard Y (NSY) codes. However, the requirements regarding Y-code and non-standard codes do not apply to Block I SVs.




Figure3-1. Space Vehicle/NAV User Interfaces

ICD-GPS-200C
10 OCT 1993

3.2.1.1 P-Code. The PRN P-code for SV ID number i is a ranging code, $P_i(t)$, of 7 days in length at a chipping rate of 10.23 Mbps. The 7 day sequence is the Modulo-2 sum of two sub-sequences referred to as X_1 and X_2 ; their lengths are 15,345,000 chips and 15,345,037 chips, respectively. The X_2 sequence is an X_2 sequence selectively delayed by 1 to 37 chips thereby allowing the basic code generation technique to produce a set of 37 mutually exclusive P-code sequences of 7 days in length. Of these, 32 are designated for use by SVS, while the remaining 5 are reserved for other purposes (e.g. ground transmitters, etc.). Assignment of these code phase segments by SV-ID number (or other use) is given in Table 3-I.

3.2.1.2 Y-code. The PRN Y-code, used in place of the P-code when the A-S mode of operation is activated, is defined in ICD-GPS-203 and/or in ICD-GPS-207 (see note in paragraph 2.1). The requirements regarding PRN Y-code do not apply to Block I SVS.

3.2.1.3 C/A Code. The PRN C/A Code for SV ID number i is a Gold code, $G_i(t)$, of 1 millisecond in length at a chipping rate of 1023 Kbps. The $G_i(t)$ sequence is a linear pattern generated by the Modulo-2 addition of two sub-sequences, G_1 and G_2 , each of which is a 1023 chip long linear pattern. The epochs of the Gold code are synchronized with the X_1 epochs of the P-code. As shown in Table 3-I, the G_2 sequence is a G_2 sequence selectively delayed by 5 to 950 chips, thereby generating a set of 36 mutually exclusive C/A-codes. Assignment of these by SV-ID (or other use) is also given in Table 3-I.

3.2.1.4 Non-standard Codes. The NSC and NSY codes, used to protect the user from a malfunction in the SV's reference frequency system (reference paragraph 3.2.1), are not for utilization by the user and, therefore, are not defined in this document. However, the requirements regarding Y-code and Non-standard codes do not apply to Block I SVs.

Table 3-I. Code Phase Assignments (sheet 1 of 2)

SV ID No.	GPS PRN Signal No.	Code Phase Selection		Code Delay Chips		First 10 Chips Octal* C/A	First 12 Chips Octal P
		C/A(G _{2i})	(X _{2i})	C/A	P		
1	1	2 ⊕ 6	1	5	1	1440	4444
2	2	3 ⊕ 7	2	6	2	1620	4000
3	3	4 ⊕ 8	3	7	3	1710	4222
4	4	5 ⊕ 9	4	s	4	1744	4333
5	5	1 ⊕ 9	5	17	5	1133	4377
6	6	2 ⊕ 10	6	1s	6	1455	4355
7	7	1 ⊕ 8	7	139	7	1131	4344
8	8	2 ⊕ 9	8	140	s	1454	4340
9	9	3 ⊕ 10	9	141	9	1626	4342
10	10	2 ⊕ 3	10	251	10	1504	4343
11	11	3 ⊕ 4	11	252	11	1642	
12	12	5 ⊕ 6	12	254	12	1750	
13	13	6 ⊕ 7	13	255	13	1764	
14	14	7 ⊕ 8	14	256	14	1772	
15	15	8 ⊕ 9	15	257	15	1775	
16	16	9 ⊕ 10	16	258	16	1776	
17--	17	1 ⊕ 4	17	469	17	1156	
1s -	1s	2 ⊕ 5	1s	470	1s	1 4 6 7	
19	19	3 ⊕ 6	19	471	19	1633	4343

* In the octal notation for the first 10 chips of the C/A code as shown in this column, the first digit (1) represents a "1" for the first chip and the last three digits are the conventional octal representation of the remaining 9 chips. (For example, the first 10 chips of the C/A code for PRN Signal Assembly No. 1 are: 1100100000).

** C/A codes 34 and 37 are common.

*** PRN sequences 33 through 37 are reserved for other uses (e.g. ground transmitters).

⊕ = "exclusive or"

NOTE: The code phase assignments constitute inseparable pairs, each consisting of a specific C/A and a specific P code phase, as shown above.

Table 3-1. Code Phase Assignments (sheet 2 of 2)

SV ID No.	GPS PRN Signal No.	Code Phase Selection		Code Delay Chips		First 10 Chips Octal* C/A	First 12 chips octal P
		C/A(G2 _i)	(X2 _i)	C/A	P		
20	20	4 ⊕ 7	20	472	20	1715	4343
21	21	5 ⊕ 8	21	473	21	1746	
22	22	6 ⊕ 9	22	474	22	1763	
23	23	1 ⊕ 3	23	509	23	1063	
24	24	4 ⊕ 6	24	512	24	1706	
25	25	5 ⊕ 7	25	513	25	1743	
26	26	6 ⊕ 8	26	514	26	1761	
27	27	7 ⊕ 9	27	515	27	1770	
28	28	8 ⊕ 10	28	516	28	1774	
29	29	1 ⊕ 6	29	559	29	1127	
30	30	2 ⊕ 7	30	860	30	1453	
31	31	3 ⊕ 8	31	861	31	1625	
32	32	4 ⊕ 9	32	862	32	1712	
***	33	5 ⊕ 10	33	863	33	1745	
***	34**	4 ⊕ 10	34	950	34	1713	
***	35	1 0 7	35	947	35	1134	
***	36	2 ⊕ 8	36	948	36	1456	
**	37**	4 ⊕ 10	37	950	37	1713	

* In the octal notation for the first 10 chips of the C/A code as shown in this column, the first digit (1) represents a "1" for the first chip and the last three digits are the conventional octal representation of the remaining 9 chips. (For example, the first 10 chips of the C/A code for PRN Signal Assembly No. 1 are: 1100100000).

** C/A codes 34 and 37 are common.

*** PRN sequences 33 through 37 are reserved for other uses (e.g. ground transmitters).

⊕ = "exclusive or"

NOTE: The code phase assignments constitute inseparable pairs, each consisting of a specific C/A and a specific P code phase, as shown above.

3.2.2 NAV Data. The system data, $D(t)$, includes SV ephemerides, system time, SV clock behavior data, status messages and C/A to P (or Y) code handover information. etc. The 50 bps data is Modulo-2 added to the P(Y)- and C/A- codes; the resultant bit-trains are used to modulate the L1 and L2 carriers. For a given SV, the data train $D(t)$, if present, is common to the P(Y) and C/A codes on both the L1 and L2 channels. The content and characteristics of data ID number 2 are given in Appendix II of this document. Data ID number 1 is no longer in use.

3.2.3 L-Band Signal Structure. The L1 link consists of two carrier components which are in phase quadrature with each other. Each carrier component is bi-phase shift key (BPSK) modulated by a separate bit train. One bit train is the Modulo-2 sum of the P(Y)-code and NAV data, while the other is the Modulo-2 sum of the C/A-code and the NAV data. The L2 link is BPSK modulated by only one of those two bit trains; the bit train to be used for L2 modulation is selected by ground command. A third modulation mode is also selectable on the L2 channel by ground command: it utilizes the P(Y)-code without the NAV data as the modulating signal. For a particular SV, all transmitted signal elements (carriers, codes and data) are coherently derived from the same on-board frequency source.

3.3 Interface Criteria. The criteria specified in the following define the requisite characteristics of the SS/US interface.

3.3.1 Composite Signal. The following criteria define the characteristics of the composite L-band signals.

3.3.1.1 Frequency Plan. The L-band signals shall be contained within two 20.46-MHz bands centered about L1 and L2. The carrier frequencies for the L1 and L2 signals shall be coherently derived from a common frequency source within the SV. The nominal frequency of this source -- as it appears to an observer on the ground -- is 10.23 MHz. The SV carrier frequency and clock rates -- as they would appear to an observer located in the SV -- are offset to compensate for relativistic effects. The clock rates are offset by $\Delta f/f = -4.4647 \times 10^{-10}$, equivalent to a change in the P-code chipping rate of 10.23 MHz offset by a $\Delta f = -4.5674 \times 10^{-3}$ Hz. This is equal to 10.22999999543 MHz. The nominal carrier frequencies (f_c) shall be 1575.42 MHz, and 1227.6 MHz for L1 and L2, respectively

3.3.1.2 Correlation Loss. Correlation loss is defined as the difference between the SV power received in a 20.46 MHz bandwidth and the signal power recovered in an ideal correlation receiver of the same bandwidth. On the L1 and L2 channels, the worst case correlation loss occurs when the carrier is modulated by the sum of the P(Y) code and the NAV data stream. For this case, the correlation loss apportionment shall be as follows:

1. SV modulation imperfections 0.6 dB
2. Ideal UE receiver waveform distortion 0.4 dB
(due to 20.46 MHz filter)

3.3.1.3 Carrier Phase Noise. The phase noise spectral density of the unmodulated carrier shall be such that a phase locked loop of 10 Hz one-sided noise bandwidth shall be able to track the carrier to an accuracy of 0.1 radians rms.

3.3.1.4 Spurious Transmissions. In-band spurious transmissions shall be at least 40dB below the unmodulated L1 and L2 carriers over the allocated 20.46 MHz channel bandwidth.

3.3.1.5 Phase Quadrature. The two L1 carrier components modulated by the two separate bit trains. (C/A-code plus data and P(Y)-code plus data) shall be in phase quadrature (within ± 100 milliradians) with the C/A signal carrier lagging the P signal by 90 degrees. Referring to the phase of the P carrier when $P_i(t)$ equals zero as the "zero phase angle", the P(Y)- and C/A-code generator output shall control the respective signal phases in the following manner: when $P_i(t)$ equals one, a 180-degree phase reversal of the P-carrier occurs; when $G_i(t)$ equals one, the C/A carrier advances 90 degrees; when the $G_i(t)$ equals zero, the C/A carrier shall be retarded 90 degrees (such that when $G_i(t)$ changes state, a 180-degree phase reversal of the C/A carrier occurs). The resultant nominal composite transmitted signal phases as a function of the binary state of the modulating signals are as shown in Table 3-II.

3.3.1.6 User-Received Signal Levels. The SV shall provide L1 and L2 navigation in accordance with the minimum levels specified in Table 3-III into a 3dB linearly polarized user receiving antenna (located near ground) at worst normal orientation, when the SV is above a 5-degree elevation angle. Additional related data is provided as supporting material in paragraph 6.3.1.

--

Table 3-II. Composite L1 Transmitted Signal Phase		
Nominal Composite L1 Signal Phase*	Code State	
	P	CIA
0°	0	0
-70.5°	1	0
+109.5°	0	1
1s0°	1	1

Relative to 0, 0 code state with positive angles leading and negative angles lagging.

Table 3-III. Received Minimum RF Signal Strength		
Channel	Signal	
	P(Y)	CIA
L1	-163.0 dBW	-160.0 dBW
L2	-166.0 dBW	or -166.0 dBW

3.3.1.7 Equipment Group Delay. Equipment group delay is defined as the delay between the L-band radiated output of a specific SV (measured at the antenna phase center) and the output of that SV'S on-board frequency source; the delay consists of a bias term and an uncertainty. The bias term is of no concern to the US since it is included in the clock correction parameters relayed in the NAV data, and is therefore accounted for by the user computations of system time (reference paragraph 20.3.3.3.1). The uncertainty (variation) of this delay as well as the difference between the L 1 vs the L2 delays are defined in the following.

3.3.1.7.1 Group Delay Uncertainty. The effective uncertainty of the group delay shall not exceed 3.0 nanoseconds (two sigma).

3.3.1.7.2 Group Delay Differential. The group delay differential between the radiated L1 and L2 P(Y) signals is specified as consisting of random plus bias components. The mean differential is defined as the bias component and will be either positive or negative. For a given navigation payload redundancy configuration, the absolute value of the mean differential delay shall not exceed 15.0 nanoseconds. The random variations about the mean shall not exceed 3.0 nanoseconds (two sigma).

3.3.1.8 Signal Coherence. All transmitted signals for a particular SV shall be coherently derived from the same on-board frequency standard; all digital signals shall be clocked in coincidence with the PRN transitions for the P-signal and occur at the P-signal transition speed. On the L 1 channel the data transitions of the two modulating signals (i.e. that containing the P(Y)-code and that containing the C/A-code) shall be such that the average time difference between the transitions does not exceed 10 nanoseconds (two sigma).

3.3.1.9 Signal Polarization The transmitted signal shall be right-hand circularly polarized (RHCP). For the angular range of ± 14.3 degrees from boresight, L1 ellipticity shall be no worse than 1.2 dB for Block II/IIA and shall be no worse than 1.8 dB for Block IIR SVS. L2 ellipticity shall be no worse than 3.2 dB for Block II/IIA SVS and shall be no worse than 2.2 dB for Block IIR over the angular range off 14.3 degrees from boresight.

3.3.2 PRN Code Characteristics. The characteristics of the P- and the C/A-codes are defined below in terms of their structure and the basic method used for generating them. The characteristics of the Y-code are defined in ICD-GPS-203 and/or ICD-GPS-207 (see note in paragraph 2.1). Figure 3-2 depicts a simplified block diagram of the scheme for generating the 10.23 Mbps $P_i(t)$ and the 1.023 Mbps $G_i(t)$ patterns (referred to as P- and C/A-codes respectively), and for Modulo-2 summing these patterns with the NAV bit train, $D(t)$, which is clocked at 50 bps. The resultant composite bit trains are then used to modulate the L-band carriers.

15

IRN-200C-001
ICD-GPS-200C
13 OCT 1995




Figure 3-2. Generation of Codes and Modulating Signals

ICD-GPS-200C
10 OCT 1993

3.3.2.1 Code Structure. The $P_i(t)$ pattern (P-code) is generated by the Modulo-2 summation of two PRN codes, $X_1(t)$ and $X_2(t - iT)$, where T is the period of one P-code chip and equals $(1.023 \times 10^7)^{-1}$ seconds, while i is an integer from 1 through 37. This allows the generations of 37 unique $P(t)$ code phases (identified in Table 3-1) using the same basic code generator.

The linear $G_i(t)$ pattern (C/A-code) is the Modulo-2 sum of two 1023-bit linear patterns, G_1 and G_2 . The latter sequence is selectively delayed by an integer number of chips to produce 36 unique $G(t)$ patterns (defined in Table 3-1).

3.3.2.2 P-Code Generation. Each $P_i(t)$ pattern is the Modulo-2 sum of two extended patterns clocked at 10.23 Mbps (X_1 and X_2). X_1 itself is generated by the Modulo-2 sum of the output of two 12-stage registers (X_{1A} and X_{1B}) short cycled to 4092 and 4093 chips respectively. When the X_{1A} short cycles are counted to 3750, the X_1 epoch is generated. The X_1 epoch occurs every 1.5 seconds after 15,345,000 chips of the X_1 pattern have been generated. The polynomials for X_{1A} and X_{1B} , as referenced to the shift register input, are:

$$\begin{aligned} X_{1A}: & 1 + X^6 + X^8 + X^{11} + X^{12}, \text{ and} \\ X_{1B}: & 1 + X^1 + X^2 + X^5 + X^8 + X^9 + X^{10} + X^{11} + X^{12}. \end{aligned}$$

Fig. 3-3
Samples of the relationship between shift register taps and the exponents of the corresponding polynomial, referenced to the shift register input, are as shown in Figures 3-3, 3-4, 3-5 and 3-6.




Figure 3-3. X1A Shift Register Generator Configuration




Figure 3-4. X1B Shift Register Generator Configuration




Figure 3-5. X2A Shift Register Generator Configuration




Figure 3-6. X2 B Shift Register Generator Configuration

The state of each generator can be expressed as a code vector word which specifies the binary sequence constant of each register as follows: (a) the vector consists of [the binary state of each stage of the register, (b) the stage 12 value appears at the left followed by the values of the remaining states in order of descending stage numbers, and (c) the shift direction is from lower to higher stage number with stage 12 providing the current output. This code vector convention represents the present output and 11 future outputs in sequence. Using this convention, at each X1 epoch, the XIA shift register is initialized to code vector 001001001000 and the XIB shift register is initialized to code vector 010101010100. The first chip of the XIA sequence and the first chip of the X1B sequence occur simultaneously in the first chip interval of any X 1 period.

The natural 4095 chip cycles of these generating sequences are shortened to cause precession of the X1B sequence with respect to the X1A sequence during subsequent cycles of the X1 A sequence in the X1 period. Re-initialization of the XIA shift register produces a 4092 chip sequence by omitting the last 3 chips (001) of the natural 4095 chip XIA sequence. Re-initialization of the XIB shift register produces a 4093 chip sequence by omitting the last 2 chips (0 1) of the natural 4095 chip X1B sequence. This results in the phase of the X1B sequence lagging by one chip for each XIA cycle in the X1 period.

The X1 period is defined as the 3750 XIA cycles (15,345,000 chips) which is not an integer number of X1B cycles. To accommodate this situation, the XIB shift register is held in the final state (chip 4093) of its 3749th cycle. It remains in this state until the X1A shift register completes its 3750th cycle (343 additional chips). The completion of the 3750th XIA cycle establishes the next X1 epoch which re-initializes both the XIA and X1B shift registers starting a new X 1 cycle.

The $X2_i$ sequences are generated by first producing an X2 sequence and then delaying it by a selected integer number of chips, i , ranging from 1 to 37. Each of the $X2_i$ sequences is then Modulo-2 added to the X1 sequence thereby producing up to 37 unique P(t) sequences.

The X2A and X2B shift registers, used to generate X2, operate in a similar manner to the X1A and X1B shift registers. They are short-cycled, X2A to 4092 and X2B to 4093, so that they have the same relative precession rate as the X1 shift registers. X2A epochs are counted to include 3750 cycles and X2B is held in the last state at 3749 cycle until X2A completes its 3750th cycle. The polynomials for X2A and X2B, as referenced to the shift register input, are:

$$\begin{aligned} \text{X2A: } & 1 + X^1 + X^3 + X^4 + X^5 + X^7 + X^8 + X^9 + X^{10} + X^{11} + X^{12}, \text{ and} \\ \text{X2B: } & 1 + X^2 + X^3 + X^4 + X^8 + X^9 + X^{12}. \end{aligned}$$

(The initialization vector for X2A is 100100100101 and for X2B is 0101010 10100),

The X2A and X2B epochs are made to precess with respect to the X1A and X1B epochs by causing the X2 period to be 37 chips longer than the X1 period. When the X2A is in the last state of its 3750th cycle and X2B is in the last state of its 3749th cycle, their transitions to their respective initial states are delayed by 37 chip time durations.

At the beginning of the GPS week, X1A, X1B, X2A and X2B shift registers are initialized to produce the first chip of the week. The precession of the shift registers with respect to X1A continues until the last X1A period of the GPS week interval. During this particular X1A period, X1B, X2A and X2B are held when reaching the last state of their respective cycles until that X1A cycle is completed (see Table 3-IV). At this point, all four shift registers are initialized and provide the first chip of the new week.

Figure 3-7 shows a fictional P-code mechanization. Signal component timing is shown in Figure 3-8, while the end-of-week reset timing and the final code vector states are given in Tables 3-IV and 3-V, respectively.




Figure 3-7. P-Code Generation

ICD-GPS-200C
10 OCT 1993




Figure 3-S. P-Code Signal Component Timing

Table S-IV. P-Code Reset Timing
(400 msec of 7-day period)

	Code Chip			
	X1A-Code	X1B-Code	X2A-Code	X2B-Code
<p style="text-align: center;">TIME</p>	1	345	1070	967

	3020	3367	&	3989

	3127	3471	4092	&

	3749	4093	4092	4093

4092*	4093	4092	4093	

* Last Chip of Week.

Table 3-V. Final Code Vector States			
Code	Chip Number	Vector State	Vector State for 1st Chip following Epoch
X1A	4091	100010010010	001001001000
	4092	000100100100	
X13	4092	100101010101	010101010100
	4093	001010101010	
X2A	4091	111001001001	100100100101
	4092	110010010010	
X2B	4092	000101010101	010101010100
	4093	001010101010	

NOTE: First Chip in each sequencers output bit whose leading edge occurs simultaneously with the epoch.

3.3.2.3 C/A-Code Generation. Each $G_i(t)$ sequence is a 1023-bit Gold-code which is itself the Modulo-2 sum of two 1023-bit linear patterns, G_1 and G_{2i} . The G_{2i} sequence is formed by effectively delaying the G_2 sequence by an integer number of chips ranging from 5 to 950. The G_1 and G_2 sequences are generated by 10-stage shift registers having the following polynomials as referred to in the shift register input (see Figures 3-9 and 3-10).

$$G_1 = X^{10} + X^3 + 1, \text{ and}$$

$$G_2 = X^{10} + X^9 + X^8 + X^6 + X^3 + X^2 + 1.$$

The initialization vector for the G_1 and G_2 sequences is 1111111111. The G_1 and G_2 shift registers are initialized at the P-coder X1 epoch. The G_1 and G_2 registers are clocked at 1.023 Mhz derived from the 10.23 Mhz P-coder clock. The initialization by the X1 epoch phases the 1.023Mhz clock to insure that the first chip of the C/A code begins at the same time as the first chip of the P-code.

The effective delay of the G_2 sequence to form the G_{2i} sequence is accomplished by combining the output of two stages of the G_2 shift register by Modulo-2 addition (see Figure 3-11). Thirty-six of the possible combinations are selected, one to correspond to each of the 36 different P-codes. Table 3-I contains a tabulation of the G_2 shift register taps selected and their corresponding P-code X_{2i} and PRN signal numbers together with the first several chips of each resultant PRN code. Timing relationships related to the C/A code are shown in Figure 3-12.




Figure 3-9. G1 Shift Register Generator Configuration





Figure 3-10. G2 Shift Register Generator Configuration

ICD-GPS-200C
 10 OCT 1993



REGISTER INPUTS	
C	- CLOCK
I	- INPUT
S	- SET ALL ONES

Figure 3-11. C/A-Code Generation




Figure3-12. C/A-Code Timing Relationships

3.3.3 Navigation Data. The content and format of (he NAV data for data ID number 2 are given in Appendix II of this document (reference paragraph 20.3.3.5.1.1). Data ID number 1 is no longer in use.


3.3.4 GPS Time and SV Z-Count. GPS time is established by the Control Segment and is referenced to a UTC (as maintained by the U.S. Naval Observatory) zero time-point defined as midnight on the night of January 5, 1980/morning of January 6, 1980. The largest unit used in stating GPS time is one week defined as 604,800 seconds. GPS time may differ from UTC because GPS time shall be a continuous time scale, while UTC is corrected periodically with an integer number of leap seconds. There also is an inherent but bounded drift rate between the UTC and GPS time scales. The OCS shall control the GPS time scale to be within one microsecond of UTC (Modulo one second).

The NAV data contains the requisite data for relating GPS time to UTC. The accuracy of this data during the transmission interval shall be such that it shall relate GPS time (maintained by the MCS of the CS) to UTC (USNO) within 90 nanoseconds (one sigma). This data is generated by the CS; therefore, the accuracy of this relationship may degrade if for some reason the CS is unable to upload data to a SV. At this point, it is assumed that alternate sources of UTC are no longer available, and the relative accuracy of the GPS/UTC relationship will be sufficient for users. Range error components (e.g. SV clock and position) contribute to the GPS time transfer error, and under normal operating circumstances (two frequency time transfers from SV(s) whose navigation message indicates a URA of eight meters or less), this corresponds to a 97 nanosecond (one sigma) apparent uncertainty at the SV. Propagation delay errors and receiver equipment biases unique to the user add to this time transfer uncertainty.

In each SV the XI epochs of the P-code offer a convenient unit for precisely counting and communicating time. Time stated in this reamer is referred to as Z-count, which is given as a 29-bit binary number consisting of two parts as follows:

- a. The binary number represented by the 19 least significant bits of the Z-count is referred to as the time of **week** (TOW) count and is defined as being equal to the number of XI epochs that have occurred since the transition from the previous **week**. The count is **short-cycled** such that the range of the TOW-count is from 0 to 403,199 XI epochs (equaling one **week**) and is reset to zero at the end of each **week**. The TOW-count's zero state is defined as that X 1 epoch which is coincident with the start of the present **week**. This epoch occurs at (approximately) midnight Saturday night-Sunday morning, where midnight is defined as 0000 hours on the Universal Coordinated Time (UTC) scale which is nominally referenced to the **Greenwich** Meridian. Over the years the occurrence of the "zero state epoch" may differ by a few seconds from 0000 hours on the UTC scale since UTC is periodically corrected with leap seconds while the TOW-count is continuous without such correction. To aid rapid ground lock-on to the P-code signal, a truncated version of the TOW-count, consisting of its 17 most significant bits, is contained in the hand-over word (HOW) of the L-Band **downlink** data stream; the relationship between the actual TOW-count and its truncated HOW version is illustrated by Figure 3-13.

- b. The ten most significant bits of the Z-count are a binary representation of the sequential number assigned to the present GPS **week** (Modulo 1024). The range of this count is from 0 to 1023 with its zero state being defined as that week which starts with the X 1 epoch occurring at approximately midnight on the night of January 5, 1980/morning of January 6, 1980. At the expiration of GPS week number 1023, the GPS week number will rollover to zero(0). Users must account for the previous 1024 weeks.



NOTES:

1. TO AID IN RAPID GROUND LOCK-ON THE HAND-OVER WORD (HOW) OF EACH SUBFRAME CONTAINS A TRUNCATED TIME-OF-WEEK (TOW) COUNT
2. THE HOW IS THE SECOND WORD IN EACH SUBFRAME (REFERENCE PARAGRAPH 20.3.3.2).
3. THE HOW-MESSAGE TOW COUNT CONSISTS OF THE 17 MSBs OF THE ACTUAL TOW COUNT AT THE START OF THE NEXT SUBFRAME.
4. TO CONVERT FROM THE HOW-MESSAGE TOW COUNT TO THE ACTUAL TOW COUNT AT THE START OF THE NEXT SUBFRAME. MULTIPLY BY FOUR.
5. THE FIRST SUBFRAME STARTS SYNCHRONOUSLY WITH THE END/START OF WEEK EPOCH.

Figure 3-13. Time Line Relationship of HOW Message

(This page intentionally left blank.)

4. NOT APPLICABLE

-1-

ICD-GPS-200C
10 OCT 1993

(This page intentionally left blank.)

ICD-GPS-200C
10 OCT 1993

5. NOT APPLICABLE

ICD-GPS-200C
10 OCT 1993

(This page intentionally left blank.)

6. NOTES

6.1 Acronyms

A-S	Anti-Spoofing
Autonav	Autonomous Navigation
BPSK	Bi-Phase Shift Key
Cs	Control Segment
DN	Day Number
EAROM	Electrically Alterable Read-Only Memory
GPS	Global Positioning System
HOW	Hand-Over Word
ICC	Interface Control Contractor
ICD	Interface Control Document
ID	Identification
IODC	Issue of Data, Clock
IODE	Issue of Data, Ephemeris
LSB	Least Significant Bit
LSF	Leap Seconds Future
MCS	Master Control Station
MSB	Most Significant Bit
NAV	Navigation
NDUS	Nudet Detection User Segment
NSC	Non-Standard C/A-Code
NSY	Non-Standard Y-code
OBCP	On-Board Computer Program
O c s	Operational Control Segment
PRN	Pseudo-Random Noise
RF	Radio Frequency
RM _s	Root Mean Square
SA	Selective Availability
SEP	Spherical Error Probable
S _s	Space Segment

SV	Space Vehicle
SVN	Space Vehicle Number
TBD	To Be Determined
TBs	To Be Supplied
TLM	Telemetry
TOW	Time Of Week
UE	User Equipment
URA	User Range Accuracy
URE	User R ange Error
u s	User Segment
USNO	U.S. Naval O bservatory
UTC	Universal Coordinated Time
WGS 84	World G eodetic System 1984
WN	Week Number

6.2 Definitions

6.2.1 User Range Accuracy. User range accuracy (URA) is a statistical indicator of the ranging accuracies obtainable with a specific SV. URA is a one-sigma estimate of the user range errors in the navigation data for the transmitting satellite. It includes all errors for which the Space and Control Segments are responsible. It does not include any errors introduced in the user set or the transmission media. While the URA may vary over a given subframe fit interval, the URA index (N) reported in the NAV message corresponds to the maximum value of URA anticipated over the fit interval.

6.2.2 SV Block Definitions. The following block definitions are given to facilitate discussion regarding the capability of the various blocks of GPS satellites to support the SV-to-US interface.

6.2.2.1 Developmental SVS. The original concept validation satellites developed by Rockwell International and designated as satellite vehicle numbers (SVNs) 1-11 are termed "Block I" SVS throughout this document. These SVS were designed to provide 3-4 days of positioning service without contact from the CS. These SVS transmit a configuration code of 000 (reference paragraph 20.3.3.5.1.6).

6.2.2.2 Operational SVS. The operational satellites are designated Block II, Block 11A and Block IIR SVS. Characteristics of these SVS are provided below. Modes of operation for these SVS and accuracy of positioning services provided are described in paragraphs 6.3.2 through 6.3.4. These SVS all transmit a configuration code of 001 (reference 20.3.3.5. 1.6). The navigation signal provides no direct indication of the type of the transmitting Sv.

6.2.2.2.1 Block II SVS. The first block of full scale operational SVS developed by Rockwell International are designated as SVNS 13-21 and are termed "Block II" SVS. These SVS were designed to provide 14 days of positioning service without contact from the CS.

6.2.2.2.2 Block IIASVs. The second block of full scale operational SVS developed by Rockwell International are designated as SVNS 22-40 and are termed "Block 11A" SVS. These SVS were designed to provide 180 days of positioning service without contact from the CS.

6.2.2.2.3 Block IIR SVS. The block of operational replenishment SVS developed by Martin Marietta are designated as SVNS 41-66 and are termed "Block IIR" SVS. These SVS will provide at least 14 days of positioning service without contact from the CS when the SVS are operating in the Block 11A mode and will provide a minimum of 150 days of positioning service without contact from the CS when operating in autonomous navigation (Autonav) mode.

6.2.3 Operational Interval Definitions. The following three operational intervals have been defined. These labels will be used to refer to differences in the interface definition as time progresses from SV acceptance of the last navigation data upload.

6.2.3.1 Normal Operations. The SV is undergoing normal operations whenever the fit interval flag (reference paragraph 20.3.3.4.3. 1) is zero.

6.2.3.2 Short-term Extended Operations. The SV is undergoing short-term extended operations whenever the fit interval flag is one and the IODE (reference paragraph 20.3.4.4) is less than 240.

6.2.3.3 Long-term Extended Operations. The SV is undergoing long-term extended operations whenever the fit interval flag is one and the IODE is in the range 240-255.

Note: the DoD Navigation User Segment and Time Transfer User have no requirement to operate, and may not operate properly, whenever any SV is operating in long-term extended operations.

6.3 Supporting Material

6.3.1 Received Signals. The guaranteed minimum user-received signal levels are defined in paragraph 3.3.1.6. As additional supporting material, Figure 6-1 illustrates the minimum power of the near-ground user-received L1 and L2 signals as a function of SV elevation angle using the following assumptions: (a) the signal is measured at the output of a 3 dB; linearly polarized receiving antenna; (b) the SV is above a 5 degree elevation angle; (c) the received signal levels are observed within the in-band allocation defined in paragraph 3.3.1. 1; (d) the atmospheric path loss is 2.0 dB; and (e) the SV attitude error is 0.5 degrees (towards reducing signal level). The actual SV attitude error will not exceed ± 0.5 degrees after the SV has stabilized to its final orbital state.




Figure 6-1. User Received Minimum Signal Levels

Higher received signals levels can be caused by such factors as SV attitude errors, mechanical antenna alignment errors, transmitter power output variations due to temperature variations, voltage variations and power amplifier variations, and due to a variability in link atmospheric path loss. The maximum received signal levels as a result of these factors is not expected to exceed -155.5 dBw and -153.0 dBw, respectively, for the P(Y) and C/A components of the L1 channel, nor -158.0 dBw for either signal on the L2 channel. This estimate assumes that the receiving antenna characteristics are as described above, the atmospheric loss is 0.6 dB and the SV attitude error is 0.5° (towards increased signal level).

6.3.2 Extended Navigation Mode (Block II/IIA). The Block II and IIA SVS are capable of being uploaded by the CS with 182 days of navigation data to support a 180 day positioning service. Due to memory retention limitations, the Block II SVS may not transmit correct data for the entire 180 days but are guaranteed to transmit correct data for at least 14 days to support short-term extended operations. Under normal conditions the CS will provide daily uploads to each SV, which will allow the SV to maintain normal operations as defined in paragraph 6.2.3.1 and described within this ICD. During normal operations, the SVS will have a user range error that is at or below a level required to support a positioning accuracy of 16 meters spherical error probable (SEP). In addition, the almanac data, UTC parameters and ionospheric data will be maintained current to meet the accuracy specified in this ICD.

If the CS is unable to upload the SVS (the CS is unavailable or the SV is unable to accept and process the upload), each SV will individually transition to short-term extended operations and eventually to long-term extended operations (based on time from each SV's last upload) as defined in paragraphs 6.2.3.2 and 6.2.3.3, and as further described throughout this ICD. As time from upload continues through these three operational intervals, the user range error of the SV will increase, causing a positioning service accuracy degradation. The rate of accuracy degradation is slow over the short-term extended operations interval, such that at the end of this interval (approximately 14 days after upload) the SV will be able to achieve a positioning accuracy of 425 meters SEP. The rate of accuracy degradation increases in the long-term extended interval, such that by the 180th day after the last upload, the positioning errors will have grown to 10 kilometers SEP. During these intervals the URA will continue to provide the proper estimate of the user range errors.

During short-term and long-term extended operations (approximately day 2 through day 182 after an upload), the almanac data, UTC parameters and ionospheric data will not be maintained current and will degrade in accuracy from the time of last upload.

6.3.3 Block 11A Mode (Block IIR). The Block IIR SVS, when operating in the Block 11A mode, will perform similarly to the Block 11A SVS and will provide at least 14 days of positioning service (through short-term extended operations) without contact from the CS.

6.3.4 Autonomous Navigation Mode. The Block IIR SV, in conjunction with a sufficient number of other Block IIR SVS, operates in an **Autonav** mode when commanded by the CS. Each Block IIR SV in the constellation determines its own ephemeris and clock correction parameters via SV-to-SV ranging, communication of data, and on-board data processing which updates data uploaded by the CS. In the **Autonav** mode the Block IIR SV will maintain normal operations as defined in paragraph 6.2.3.1 and as further described within this ICD, and will have a user range error that is at or below a level required to support 16 meter SEP accuracy. If the CS is unable to upload the SVS, the Block IIR SVS will maintain normal operations for period of at least 180 days after the last upload.

In the **Autonav** mode, the almanac data, UTC parameters and ionospheric data are still calculated and maintained current by the CS and uploaded to the SV as required. If the CS is unable to upload the SVS, the almanac data, UTC parameters and ionospheric data will not be maintained current and will degrade in accuracy from the time of the last upload.

10. APPENDIX I. LETTERS OF EXCEPTION

10.1 Scope. As indicated in paragraph 1.3, initial signature approval of this document, as well as approval of subsequent changes to the document, can be contingent upon a “letter of exception”. This appendix depicts such “letters of exception” when utilized by any signatory of this document in the initial approval cycle and/or in the change approval process. The ICC will omit such letters of exception from subsequent revisions of this document based on written authorization by the respective signatory (without processing a proposed interface revision notice (PIRN) for approval). ” When some (but not all) of the exceptions taken by a signatory are resolved, the signatory shall provide the ICC with an updated letter of exception for inclusion in the next ICD revision (without processing a PIRN for approval).

10.2 Applicable Documents. The documents listed in Section 2.0 shall be applicable to this appendix.

10.3 Letters of Exception. If signature approval of this document – as affixed to the cover page -- is marked by an asterisk, it indicates that the approval is contingent upon the exceptions taken by that signatory in a letter of exception. Any letter of exception which is in force for the revision of the ICD is depicted in Figure 10-1. Signatories for whom no letter of exception is shown have approved this version of the document without exception.

(This page intentionally left blank.)

Space Systems Division
Rockwell International Corporation
2600 Westminster Boulevard
P.O. Box 3644
Seal Beach, California 90740-76-14



Rockwell
International

In reply refer to 93MA3728

Date: September 22, 1993
To: The ARINC Companies
11770 E. Warner Ave., Suite 210
Fountain Valley, CA 92708
Subject: Rockwell International Letter of Exception to
ICD GPS-200 PIRN-200A-006NC, dated November
21, 1986,
Attention: Thomas R. Denigan
Reference: ARINC Companies FAX dated September 20, 1993,
T. R. Denigan to D. L. Butler, same subject.

It is Rockwell's position that the statement requested in the subject letter of exception be incorporated, as written, in the next revision to ICD-200. The 'B' revision of ICD-200 incorporated only the last portion of the requested changethe initialization vector for X2A is 100100100101 and for X2B is 010101010100." It is felt that the first portion of the sentence, "Using the same convention identified for X1A and X1B,..." will aid the reader of the ICD in understanding the derivation of the X2A and X2B terms.

ROCKWELL INTERNATIONAL
Space Systems Division

W. L. Young
W. L. Young, Manager
Engineer
Contracts & Proposals

F. E. Cooper 9/22/93
F. E. Cooper, Chief
GPS Program

cc: D. L. Butler
W. F. Fratzke

Figure 10-1. Letter of Exception (sheet 1 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

Collins Avionics & Communications Division
Rockwell International Corporation
350 Collins Road NE
Cedar Rapids, IA 52498
(319) 395-1000



September 23, 1993

ARINC Research Corporation
11770 Warner Avenue, Suite 210
Fountain Valley, CA 92708

Attention: Mr. Tom Denigan

Subject: Review of ICD-GPS-200B Outstanding Letters of Exception
in Preparation of ICD-GPS-200C

Dear Mr. Denigan:

A review of Rockwell International's Collins Avionics & Communications Division, outstanding Letters of Exception as listed in IRN-200B-007 to ICD-GPS-200B shows 2 Letters of Exception that have been satisfied or are no longer pertinent:

sheet 46, (letter dated March 31, 1987)
sheet 53 & 54, (letter dated September 10, 1986)

The following letters as listed in IRN-200B-007 to ICD-GPS-200B are still pertinent and are to be included in any revised ICD-GPS-200 releases:

sheet 54a, 54c (letter dated March 27, 1991)
sheet 56g (letter dated September 23, 1992)

Sincerely,

A handwritten signature in cursive script, appearing to read "C.S. Olson".

C.S. Olson
Program Manager

Figure 1 (0)-1, Letter of Exception (sheet 2 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

March 27, 1991

ARINC Research Corporation
4410 East Fountain Blvd., Suite 100
Colorado Springs, CO 80916

Attention: Ms. Cheryl Abendschan

Subject: Rockwell CACD Letter of Exception against PIRN-200B-001B (as corrected by ARINC memo on typos and oversights, 19 MAR 91)

The subject PIRN-200B-001B documents the extended navigation capabilities inherent in the Space Segment/User Segment interface as a result of the incorporation of mission package software release OR5.10 into the Control Segment. CACD'S approval of this PIRN, which indicates concurrence that the PIRN accurately reflects the as-built Control and Space Segments in the area of extended navigation, is given with exception.

CACD takes exception because:

1. The extended navigation capabilities documented by the PIRN are not a requirement of the GPS Phase III User Equipment (UE) contract FM701-S5-C-0038, the GPS UE Phase IV contract F0470 1-90-C-0092, or the GPS MAGR Contract F0470 1-91-C-0003. Therefore, the GPS User Equipment, which has been and will be developed under these contracts, do not operate in compliance with extended navigation.
2. While we may technically comment on the impact to the UE as a result of OR5.10 implementation, we cannot (as PIRN approval might otherwise indicate) verify that OR5.10 implements the extended navigation requirements identified in the PIRN.

In summary, "Long Term Extended" operations from 15 to 1 SO days following an upload from the Control Segment are not supported by the Phase III GPS UE. Attachment 1 contains the detailed comments on the PIRN items to which CACD takes exception.

Sincerely,

& ~ & —

J. L. Arnold
GPS Programs Manager

Enclosure

cc: Lt. Jim Dagley
Capt. Greg Laushine

Figure 10-1. Letter of Exception (sheet 3 of 14).

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

ATTACHMENT I

Rockwell CACD Exceptions [o PIRN-200B-001B

PIRN ITEM	Rockwell CACD Comment
<p>17, 18</p>	<p>These PIRN items document the change in the definition of the Week Number in subframe 1, word 3 due to the implementation of long term extended ephemeris curve tits which cross GPS week boundaries. The new definition states that the week number is the ten most significant bits of the Z-count and will represent the GPS week of the start of the data set transmission interval. Previously, the week number always represented the current GPS week of transmission. CACD takes exception to this redefinition because:</p> <ol style="list-style-type: none"> 1. The PIRN introduces an inconsistency with the definition of Z-count given in paragraph 3.3.4, page 33 which states that “the [en most significant bits of the Z-count area binary representation of the sequential number assigned to the present GPS week (Module 1024).” 2. Since the GPS week being transmitted by the Space Segment could vary from SV to SV (depending upon time of upload) and since the transmitted GPS week could be different from the current GPS week by one week starting on day 29 after an upload, the GPS UE could navigate using the wrong GPS week. Use of the wrong GPS week could cause navigation interruptions and could result in the incorrect time-tagging of the satellite data. The user could therefore be provided with navigation data which is marked valid when, in fact, it is not valid. This is an unacceptable situation.
<p>22,29,31, 57a, 57b,58, 60</p>	<p>These PIRN items document the change in the definition of the ephemeris fit interval flag for a value equal to 1 and its corresponding relationship to the IODC/IODE during extended operations. The GPS UE supports only a tit interval of 6 hours when the tit interval flag equals 1. The newly defined ephemeris tit intervals of 8, 14,26, 50,74, 9S, 122, and 146 hours for Long Term Extended Operations are not supported and the UE will compute 6 hour curve tits whenever these are in effect.</p>

Figure 10-1. Letters of Exception (sheet 4 of 14)

IRN-200C-001
 ICD-GPS-200C
 13 OCT 1995

ATTACHMENT I(cont.)

Rockwell CACD Exceptions to PIRN-200B-001B

PIRN ITEM	Rockwell CACD Comment
39, 40, 50, 54	<p>These PIRN items describe the almanac data sets and how the almanac URE grows throughout extended operations. The GPS UE requirements for almanac-based direct P-code TTFF (time to first fix) are only applicable to Normal Operations in which the almanac parameters have been updated within the last six days. Extended operations <u>may</u> jeopardize missions of those users who require efficient almanac-based direct P-code TTFFs.</p>
43	<p>This PIRN item documents the fact that the health summary in subframe 5, page 25 is only updated at the time of almanac upload. During extended operations the health summary may become outdated due to the length of time since the last upload.</p> <p>If the health summary becomes outdated and does not accurately reflect the status of the GPS constellation, the TTFF for the GPS UE may be delayed. This is due to the time wasted on the possible acquisition of unhealthy SVS which were marked "healthy" by the health summary. Also, attempts to acquire healthy SVS which are marked unhealthy will not be made. As a result, extended operations <u>may</u> jeopardize missions of those users who require efficient TTFF.</p>
45,46	<p>These PIRN items document the changes for the UTC parameter data sets during extended operations. The GPS UE uses the UTC parameters to provide the user with precise time. Exception is taken because:</p> <ol style="list-style-type: none"> 1. CACD is not confident that the accuracy of the UTC parameters can be maintained throughout extended operations. This accuracy is specified as 90 ns (one sigma) on ICD-GPS-200B page 32. As a result, extended operations <u>may</u> jeopardize missions of those users who require precise UTC. 2. Since the GPS UE does not account for the degraded accuracy of the UTC parameters as a function of time during extended operations, the user may be provided with an incorrect estimate of his time accuracy which again <u>may</u> jeopardize his mission. CACD believes the UTC parameters' accuracy, as a function of time, should be specified in some GPS system specification.

Figure 10-1. Letters of Exception (sheet 5 of 14).

IRN-200C-001
 ICD-GPS-200C
 13 OCT 1995

Collins Avionics & Communications Division
Rockwell International Corporation
350 Collins Road NE
Cedar Rapids, IA 52498
(319) 395-1000



September 23, 1992

ARINC Research Corporation
11770 Warner Avenue, Suite 210
Fountain Valley, CA 92708

Attention: Mr. Peter Fyfe

Subject: PIRN-200B-009A Rockwell CACD Letter of Exception

Dear Mr. Fyfe:

The subject PIRN-200B-009A which documents the changes to the Space Segment/User Segment interface for the Block III SVS is hereby approved by Rockwell CACD with the following exception:

The PIRN states that UTC parameters (PIRN items 4, 20), ionospheric model parameters (PIRN items 21, 27a), and almanac data (PIRN items 22a, 22b) will degrade when the Block III SVS do not receive an upload from the Control Segment. Since the III SVS indicate "normal operations" (curve fit interval flag of 4 hours) at all times, some user segment requirements cannot be met during "normal operations" in the absence of Control Segment uploads. These affected requirements are precise UTC time transfer and almanac-based direct P-code time to first fix.

The affected User Equipment (UE) is that designed and developed by Rockwell CACD under the GPS UE Phase III Contract F04701-S5-C-0038, GPS UE Phase IV Contract F04701-90-C-0092, and GPS MAGR Contract F04701-91-C-0003.

Sincerely,

A handwritten signature in cursive script, appearing to read "C.S. Olson".

C.S. Olson
Program Manager

CSS/jk

Figure 10-1. Letters of Exception (sheet 6 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

Collins Avionics & Communications Division
Rockwell International Corporation
350 Collins Road NE
Cedar Rapids, IA 52438
[31 9] 395-1000



June 12, 1995

ARINC Research Corporation
2250 East Imperial Highway, Suite 450
El Segundo, CA 90245-3509

Attention: Mr. Thomas Denigan
Subject: PIRN-200C-001 Rockwell CACD Letter of Exception
Enclosure: Approval sheet for PIRN-300C-001
References: ARINC Research Corporation letter dated January 16, 1995;
Subject: PIRN-200C-001 to ICD-GPS-200C

The subject PIRN-200C-001 is approved by Rockwell CACD with the following exception:

The effect of Item 2, "Change Section 20.3.3.5.2.2, page 121" of this PIRN is that computed almanac age in Rockwell CACD government User Equipment (UE) will be approximately 14 hours older than actual almanac age. Since almanac age computation is for display/output purposes only there is no impact to receiver operation or navigation solution accuracy. CACD computes an almanac time-of-transmission that is nominally the multiple of 2¹² seconds truncated from 3.5 days prior to the almanac reference time, t_{oa} . Item 2 of subject PIRN-200C-001 documents the change of t_{oa} from being nominally the multiple of 12¹² seconds truncated from 3.5 days (S4 hours) after the first valid transmission time for an almanac set to being nominally the multiple of 712 seconds truncated from 70 hours after the first valid transmission time for an almanac set. Therefore, Rockwell CACD government UE will compute and output an incorrect almanac age by approximately 14 hours.

Figure 10-1. Letters of Exception (sheet 7 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

The second sentence of paragraph 20.3.3.5.2.2, "The almanac is updated often enough to ensure that GPS time, t , shall differ from t_{sa} by less than 3.5 days during the transmission period", must not change. This is to ensure the proper resolution of the GPS week number associated with the almanac.

Technical questions concerning this matter should be referred to Lawrence Bums at (319)395-2616.

Sincerely,



Craig Olson
GPS Program Manager

Figure 10-1. Letters of Exception (sheet S of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995



RD001001935
October 1, 1993

Mr. Tom Denigan
ARINC Research Corporation
11770 Warner Avenue, suite 210
Fountain Valley, CA 92750

Subject: IBM "Letter of Exception" against ICD-GPS-200B as
Modified by IRN-200B-001B

Reference:

1. ICD-GPS-200B, dated November 30, 1987
2. IRN-200B-001B, dated April 15, 1991
3. IRN-200B-002, dated July 26, 1991
4. IRN-200B-003, dated December 2, 1991
5. IRN-200B-004, dated December 5, 1991
6. IRN-200B-005, dated December 16, 1991
7. IRN-200B-006, dated December 9, 1992
8. IRN-200B-007, dated July 19, 1993
9. IBM letter 020689-2, dated February 6, 1989
10. Contract F0470 1-90-C-0009

Dear Mr. Denigan:

With the release of the referenced IRN-200B-001 B through -007, [his letter represents the current IBM letter of exception against ICD-GPS-200B, replacing Reference 9.

The IBM contract does not support the following:

Block I end of data transmission (Paragraph 20.3.2)

The option of repeated almanacs for 12 or fewer SVS (Paragraphs 20.3.3.5.1.2, 20.3.3.5.1.3)

The use of pages 2, 3, 4, 5, 7, 8, 9, and 10 of subframe 4 for purpose other than almanac data for SVS 25 through 32 (Paragraphs 20.3.3.5.1, 20.3.3.5.1.1, 20.3.3.5.1.3, Table 20-V)

Figure 10-1. Letters of Exception (sheet 9 of 14)


IRN-200C-001
ICD-GPS-200C
13 OCT 1995

Mr. Tom Denigan

RD001001935
October 1, 1993

Questions and coordination related to the technical content of ICD-GPS-200 should be addressed to Ming Kang Chien at 301/240-6449.

Very truly yours,



Magdalena V. Clyne
Contract Administrator

cc: Capt. B. Schrimsher, SMC/CZGD
Lt. R. Layton, SMC/CZET

Figure 10-1. Letters of Exception (sheet 10 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

MARTIN MARIETTA ASTRO SPACE

POST OFFICE BOX 3555
PHILADELPHIA, PENNSYLVANIA 19101

17 August 1994
GPS IIR-CM-1046

ARINC Research Corporation
2250 E. Imperial Highway, Suite 450
El Segundo, CA 90245-3509

Attention: Ms. Pat Alexander

Subject: Approval of ICD-GPS-200, Revision C

Reference: Contract F04701-89-C-0073
ICD-GPS-200, Revision C dated 10 October 1993

Dear Ms. Alexander:

Martin Marietta Astro Space approves with exception ICD-GPS-200, Revision C as evidenced by the attached signed approval sheet. The areas of exception are both general and specific in nature.

General Areas of Exceptions

Martin Marietta takes exception to specific changes in requirements originally conveyed in IRN Nos. IRN-200B-001, IRN-200B-004, IRN-200B-005, and IRN-200B-006 of ICD-GPS-200B. The principal reason for these exceptions is that Martin Marietta's contract does not include requirements for Extended Navigation, User Range Accuracy bin structure, some aspects of the Time of Almanac requirements and the Spherical Error Probability of the navigation signals received by the navigation users. Detailed reasons for these exceptions are given below.

1. Extended Navigation

Martin Marietta takes exception to the application of Extended Navigation (EN) requirements, or the attribution of EN performance or EN performance verification to the Block IIR SV. Such application or attribution may inadvertently be construed from the overall context.

The Block IIA operational mode called Long Term Extended Operations/Extended Navigation" is undefined and not required in the Block IIR contract. There is no Block IIR requirement to support 180 days in the Block IIA mode without regular CS contacts and uploads. The Block IIR contract defines the Block IIA mode in the context of ICD-GPS-200B dated 30 November 1987 which describes a 14 day autonomy capability.

Figure 10-1. Letters of Exception (sheet 11 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

The Block IIR design supports 180 day autonomy in the context of the Autonomous Navigation mode and 14 day autonomy in the Block IIA mode. It may be possible to construct upload databases that will allow operation beyond 14 days with the current design, but this is not a current requirement. The Block IIR Space Vehicle does not support such an upload design, performance description, and performance verification.

Section 20.3.2, sentence 2 states "Block IIR SVS are designed to have sufficient memory to store 182 days of upload NAV data in the Block IIA mode . . ." Martin Marietta takes exception to a "182 day" NAV data storage requirement in the Block IIA mode. The Block IIR design and validation plan is required to provide performance and memory margin computed on 14 day storage in the IIA mode as defined in Sections 20.3.4.4 and 20.3.4.5 of the ICD-GPS-200B dated 30 November 1987.

Sections 20.3.4.4 and 20.3.4.5 with new Tables 20-XII and 20-XII 1, define different "days spanned", "fit intervals", and Transmission intervals compared to the 30 November 1987 ICD-GPS-200B. These changes are generated by some of the Extended Navigation upload characteristics for the Block IIA SV which supports "182 days" of data. Martin Marietta takes exception to evaluation and validation of the Block IIR design performance under these modified sections and tables.

2. URA Bin Structure

Martin Marietta takes exception to items relating to URA index to ranges of URA in meters appears to require the Block IIR SV in the Autonomous Navigation (AN) mode to transition from one index to the next at exactly the values of URA indicated. This specification of URA bins is not a defined requirement for Block IIR. The Block IIR AN design is based on the equations and the 'no better than' descriptions present in ICD-GPS-200B, in accordance with the Block IIR implementation.

When in the AN mode, the Martin Marietta design estimates URA on board the SV and converts the result to the index in the NAV user message by rearranging the equations and solving for the index. As a result, our design approximates, but does not exactly match, the description when Block IIR is in the AN mode.

When Block IIR is in the IIA mode, the Martin Marietta design does match the URA bin description exactly because we broadcast the index uploaded from the CS and the CS estimates URA.

3. Spherical Error Probable (SEP)

Martin Marietta takes exception to the IJRE statement in 6.3.4 since it implies Martin Marietta responsibility to relate Block IIR URE to 16 meters SEP.

Figure 10-1. Letters of Exception (sheet 12 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

IRN-200B-006 added section 6.3.4 on "Autonomous Navigation Mode." The third sentence states that the Block IIR SV in the Autonav mode "... will have a user range error that is at or below a level required to support 16 meter SEP accuracy." The Block IIR SV constellation, when authorized to operate in the Autonav mode, is required to provide 6 meters (1 sigma) URE. The 6 meter requirement is defined in SV Segment Specification (SS-SS-500). Martin Marietta has been advised that this independently derived 6 meter URE requirement does support the 16 meter SEP system requirement for a nominal geometric dilution of precision. The 16 meter SEP accuracy in the user equipment output is dependent on geometry of the SVs chosen by the URE for the solution. The 16 meter SEP accuracy is not a requirement for Block IIR Space Vehicle.

4. Time of Almanac (Toa)

Martin Marietta takes exception to paragraph 20.3.3.5.2.2, since it implies that the SV is required to ensure that time of almanac (Tea) values be the same for a given data set (when the SV health is changed by the CS) or that Toa differ for successive data sets (which contain changes in SV health). This is a CS responsibility.

Martin Marietta is concerned about the ambiguous CS/SV requirement to ensure that the described Toa values are presented to Users in Appendix II, paragraph 20.3.3.5.2.2.

ICD-GPS-200, Revision C deletes 'The CS shall ensure' in paragraph 20.3.3.5.2.2. This is a change from ICD-GPS-200B dated 11/30/87 which is applied to our contract. If so deleted, ICD-GPS-200B will be mute as to who ensures that "All Toa values in SF4&5 shall be the same for a given almanac data set and shall differ for successive data sets which contain changes in almanac parameters or SV health."

The Block IIR design is not required to, and does not, affect or check Toa based on the SV health settings described by this section. The Block IIR design depends on CS uploads for SV health and the relationship of SV health data to almanac reference time.

In an independent process, CS uploads for Toa values and almanacs are inputs to the on-board generation of Toa values when the Block IIR design propagates almanacs to remain within 3.5 days of GPS time. If the CS provides a valid upload, the Block IIR on-board processing will maintain that all Toa values in SF4&5 will be the same for a given almanac data set and will differ for successive data sets which contain changes in almanac parameters.

Figure 10-1. Letters of Exception (sheet 13 of 14)

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

Specific Exceptions

In addition, Martin Marietta takes exceptions to the specific requirements listed below:

Paragraph #	Description
20.3.3.3.1.1	Change of week number: Extended Navigation (EN).
Table "20-V	SV ID Nos. in Note 4 (EN).
6.2.3 -6.2.3.3	Definitions. CS responsibility. N/A to Block-IIIR.
6.3.2,6.3.3	Extended Navigation Mode description.
6.3.4	"... and will have . . . 16 meter SEP accuracy."
6.3.4	Orbit parameters. Narrative on almanac. N/A to Block-IIIR.
	Martin Marietta uses ICD-GPS-401 method.
20.3.2	"... 182 days of uploaded NAV data in the Block IIA . . ."
20.3.2	"(d) if a control . . . subframes will indicate ID = 1 . . ."
	IRN excludes Block-1 I PI.
20.3.3.4.1	CS requirement deleted. (Related to extended nav.).
20.3.3.5.1.2	Propagation of Toa requirements.
20.3.3.5.1.2	"For Block II . . . transmission interval."
20.3.3.5.2.2	Propagation of Toa requirements.
20.3.4.1	Reqmt for subframe changes at frame boundary.
20.3.4.4	Table 20-XII: Ext. Nav related.
Table 20-XII	IODC Requirements. Ext. Nav related.
20.3.4.4	Two hour data sets are not tested.
Table 20-XII	Transmission intervals. Ext. Nav related.

Note that if Martin Marietta has taken earlier exception to a change in any requirements in a previous revision of this document, Martin Marietta continues to take exception to that change. The retraction of an exception will be accomplished by a letter explicitly stating that the exception is no longer valid.

If there are any questions of a technical nature concerning the contents of this letter, please contact Dave Levin at (610) 354-3022. All other questions or comments should be addressed to the undersigned at (610) 354-1710.

Very truly yours,
 MARTIN MARIETTA ASTRO SPACE



D. Supow
 Manager, GPS Contracts
 GPS PMO

cc: Maj. Paul Schubert (CZEP)

/dd

Figure 10-1. Letters of Exception (sheet 14 of 14)

IRN-200C-001
 ICD-GPS-200C
 13 OCT 1995

20. APPENDIX II. GPS NAVIGATION DATA STRUCTURE FOR DATA ID NO. 2

20.1 Stove. This appendix describes the specific GPS navigation (NAV) data structure denoted by data ID number 2. This data ID number, when transmitted as part of the NAV data, shall be represented by the two-bit binary notation as 01. Data ID number 1 is no longer in use.

20.2 Applicable Documents.

20.2.1 Government Documents. In addition to the documents listed in paragraph 2.1, the following documents of the issue specified contribute to the definition of the NAV data related interfaces and form a part of this Appendix to the extent specified herein.

Specifications

None

Standards

None

Other Publications

None

20.2.2 Non-Government Documents. In addition to the documents listed in paragraph 2.2, the following documents of the issue specified contribute to the definition of the NAV data related interfaces and form a part of this Appendix to the extent specified herein.

Specifications

None

Other Publications

none


20.3 Requirements

20.3.1 Data Characteristics. The data stream shall be transmitted by the SV on the L 1 and L2 channels at a rate of 50 bps. The data stream, when present, shall be common to both of those L-band frequencies, irrespective of the PRN ranging code(s) used.

20.3.2 Message Structure. As shown in Figure 20-1, the message structure shall utilize a basic format of a 1500 bit long frame made up of five subframes, each subframe being 300 bits long. Subframes 4 and 5 shall be subcommutated 25 times each, so that a complete data message shall require the transmission of 25 full frames. The 25 versions of subframes 4 and 5 shall be referred to herein as pages 1 through 25 of each subframe. Each subframe shall consist of ten words, each 30 bits long; the MSB of all words shall be transmitted first.

Each subframe and/or page of a subframe shall contain a telemetry (TLM) word and a handover word (HOW), both generated by the SV, and shall start with the TLM/HOW pair. The TLM word shall be transmitted first, immediately followed by the HOW. The latter shall be followed by eight data words. Each word in each frame shall contain parity (reference Section 20.3.5).

==



--- RESERVED
 P = 6 PARITY BITS
 t = 2 NONINFORMATION BEARING BITS USED FOR PARITY COMPUTATION (SEE PARAGRAPH 20.3.5)
 C = TLM BITS 23 AND 24 WHICH ARE RESERVED

Figure 20-1. Data Format (sheet 1 of 10)





Figure 20-1. Data Format (sheet 2 of 10)



- RESERVED
P = 6 PARITY BITS
t = 2 NONINFORMATION BEARING BITS USED FOR PARITY COMPUTATION (SEE PARAGRAPH 20.3.5)
C = TLM BITS 23 AND 24 WHICH ARE RESERVED

Figure 20-1. Data Format (sheet 3 of 10)




Figure 20-1. Data Format (sheet 4 of 10)






Figure 20-1. Data Format(sheet 5 of 10)




RESERVED
P = 6 PARITY BITS
t = 2 NONINFORMATION BEARING 31TS USED FOR PARITY COMPUTATION (SEE PARAGRAPH 20.3.5)
C = TLM BITS 23 AND 24 WHICH ARE RESERVED
NOTE: PAGES 2, 3, 4, 5, 7, 8, 9 & 10 OF SUBFRAME 4 HAVE THE SAME FORMAT AS PAGES 1 THROUGH 24 OF SUBFRAME 5

Figure 20-1. Data Format (sheet 6 of 10)




--- RESERVED
P = 5 PARITY BITS
t = 2 NONINFORMATION BEARING BITS USED FOR PARITY COMPUTATION (SEE PARAGRAPH 20.35)
C = TLM BITS 23 AND 24 WHICH ARE RESERVED
NOTE: PAGES 2, 3, 4, 5, 7, 8, 9 & 10 OF SUBFRAME 4 HAVE THE SAME FORMAT AS PAGES 1 THROUGH 24 OF SUBFRAME 5

Figure 20-1. Data Format (sheet 7 of 10)



— RESERVED
P = 6 PARITY BITS
t = 2 NONINFORMATION BEARING BITS USED FOR PARITY COMPUTATION(SEE PARAGRAPH 20.3.5)
C = TLM BITS 23 AND 24 WHICH ARE RESERVED
NOTE: PAGES 2,3, 4,5,7, 8, 981007 SUBFRAME 4 HAVE THE SAME FORMAT AS PAGES 1 THROUGH 25 OF SUBFRAME 5

Figure 20-1. Data Format (sheet S of IO)



THE INDICATED PORTIONS OF WORDS 3 THROUGH 10 OF PAGES 13, 14, & 15 ARE SPARES, WHILE THOSE OF PAGE 17 ARE RESERVED FOR SPECIAL MESSAGES (PLUS SPARES) PER PARAGRAPH 203.3.5.1.10
 RESERVED
 P = 6 PARITY BITS
 t = 2 NONINFORMATION BEARING 911S USED FOR PARITY COMPUTATION (SEE PARAGRAPH 20.3.5)
 c = TLM BITS 23 AND 24 WHICH ARE RESERVED
 NOTE: PAGES 2, 3, 4, 5, 7, 8, 9, 810 OF SUBFRAME 4 HAVE THE SAME FORMAT AS PAGES 1 THROUGH 24 OF SUBFRAME 5

Figure 20-1. Data Fern-iat (sheet 10 of 10)

Block II and IIA SVS are designed with sufficient memory capacity for storing 182 **days** of uploaded NAV data. However, the memory retention of these SVS will determine the duration of data transmission. Block IIR SVS are designed to have sufficient memory to store 182 days of uploaded NAV data in the Block 11.4 mode and to store 210 days of CS data needed to generate NAV data on-board in the Autonav mode. Alternating ones and zeros will be transmitted in words 3 through 10 in place of the normal NAV data whenever the SV cannot locate the requisite valid control or data element in its on-board computer memory. The following specifics apply to this default action: (a) the parity of the affected words will be invalid, (b) the two trailing bits of word 10 will be zeros (to allow the parity of subsequent subframes to be valid -- reference paragraph 20.3.5), (c) if the problem is the lack of a data element, only the directly related subframe(s) will be treated in this manner, (d) if a control element cannot be located, this default action will be applied to all subframes and all subframes will indicate ID = 1 (i.e., an ID-code of 001) in the HOW (reference paragraph 20.3.3.2) (Block IIR SVS indicate the proper subframe ID for all subframes.) and (e) certain failures of data which may occur in the SV memory or during an upload will cause the SV to transmit in non-standard codes (NSC and NSY) which would preclude normal use by the US. Normal NAV data transmission will be resumed by the SV whenever a valid set of elements becomes available.

Block I SVS can store only 3-4 days of uploaded data. Whenever Block I SVS reach the end of the uploaded data, they will transmit a pattern of ones and zeros in words 3 through 10 of each subframe with two trailing zeros in word 10. Further, the Block ISVs do not have the capacity of transmitting alternating ones and zeros in words 3 through 10 in place of the normal NAV data in default cases specified in the preceding paragraph.

Block 11 SVS are uploaded with 182 days of NAV data. However, the EAROM retentivity for these SVS is designed and guaranteed for only 14 days. Therefore, Block II SV memory is most likely to fail sometime during long-term extended operations after repeated write operations. In the case of memory failure, the SV will transmit alternating ones and zeros in word 3-10 as specified in the above paragraph.

Block 11A SVS are also uploaded with 182 days of data. However, the EAROM retentivity for these SVS is designed and guaranteed for 180 days.

The memory retentivity for the Block IIR SVS is designed and guaranteed for 210 days.

Although the data content of the SVS will be temporarily reduced during the upload process, the transmission of valid NAV data will be continuous. The data capacity of specific operational SVS may be reduced to accommodate partial memory failures.

--

20.3.3 Message Content. The format and contents of the TLM word and the HOW, as well as those of words three through ten of each subframe/page, are described in the following subparagraphs (message content related to SA is defined in ICD-GPS-203 and/or ICD-GPS-207 -- see note in paragraph 2.1). The timing of the subframes and pages is covered in Section 20.3.4.

20.3.3.1 Telemetry Word. Each TLM word is 30 bits long, occurs every six seconds in the data frame, and is the first word in each subframe/page. The format shall be as shown in Figure 20-2. Bit 1 is transmitted first. Each TLM word shall begin "with a preamble, followed by the TLM message, two reserved bits, and six parity bits. The TLM message contains information needed by the authorized user as defined in ICD-GPS-203 and/or ICD-GPS-207 (see note in paragraph 2.1), and by the CS, as described in the related SS/CS interface documentation.

20.3.3.2 Handover Word (HOW). The HOW shall be 30 bits long and shall be the second word in each subframe/page, immediately following the TLM word. A HOW occurs every 6 seconds in the data frame. The format and content of the HOW shall be as shown in Figure 20-2. The MSB is transmitted first. The HOW begins with the 17 MSBS of the time-of-week (TOW) count. (The full TOW count consists of the 19 LSBS of the 29-bit Z-count). These 17 bits correspond to the ToW-count at the X1 epoch which occurs at the start (leading edge) of the next following subframe (reference paragraph 3.3.4).

--




Figure 20-2. TLM and HOW Formats

Bit 18 is used in two ways: (a) on SVs that predesignated by configuration code 000, bit 18 is the roll momentum dump flag with a "1" in this bit-position indicating that anon-conservative (thruster type) momentumdump has occurred since the last upload (this flag is reset at a new end-of-message transmission at the conclusion of the next upload); and (b) on SVS designated by configuration code 001, bit 18 is an "alert" flag. When this flag is raised (bit 18 = "1"), it shall indicate to the unauthorized user that the SV URA may be worse than indicated in subframe 1 and that he shall use that SV at his own risk. The authorized user shall refer to ICD-GPS-203 and/or ICD-GPS-207 (see note in paragraph 2. 1).

Bit 19 also has a dual role: (a) on SVS that are designated by configuration code 000 in page 25 of subframe 4, bit 19 is used as a synchronization flag; and (b) on SVS designated by configuration code 001, bit 19 is an anti-spoof (A-S) flag.

When used as a synchronization flag, a "0" in bit position 19 indicates that the SV is in synchronism which is defined as the condition in which the leading edge of the TLM word is coincident with the X1 epoch. If bit 19 is a "1", this condition may not exist; i.e., the SV is not in synchronism, and further data from this SV should not be used since it may be erroneous. When used as an A-S flag, a "1" in bit-position 19 indicates that the A-S mode is ON in that SV.

Bits 20, 21, and 22 of the HOW are the ID code of the subframe in which that particular HOW is the second T1 era. The ID code shall be as follows:

<u>Subframe</u>	<u>ID Code</u>
1	001
2	010
3	011
4	100
5	101

20.3.3.3 Subframe 1. The content of words three through ten of **subframe 1** are defined below, followed by related algorithms and material pertinent to use of the data.

20.3 .3.3.1 Subframe 1 Content. The third through tenth words of **subframe 1** shall each contain six parity bits as their **LSBs**; in addition, two **non-information** bearing bits shall be provided as bits 23 and 24 of word ten for parity computation purposes. The remaining 190 bits of words three through ten shall contain the clock parameters and other data described in the following.

..

The clock parameters describe the SV time scale **during** the period of validity. The parameters in a data set shall be valid during the **interval** of time in which they are transmitted and shall remain valid for an-additional period of time after **transmission** of the **next** data set has started. The timing information for **subframes**, pages, and **data** sets is covered in Section 20.3.4.

20.3.3 .3.1.1 Week Number. The ten MSBS of word three shall contain **the** ten MSBS of the 29-bit Z-count as qualified herein. These ten bits shall represent the number of the current GPS week at the start of the data set transmission **interval** with “all zeros” indicating week ‘O’. The GPS week number **increments** at each end/start of week epoch. For Block II SVS in long-term **extended** operations, **beginning approximately 28** days after upload, **the transmission** week number may not correspond to the **actual GPS week** number due to curve fit **intervals** that cross week boundaries.

20.3.3 .3.1.2 Code(s) on L2 Channel. Bits 11 and 12 of word three shall indicate which code(s) is (are) commanded ON for the L2 channel, as follows:

- 00 = Reserved,
- 01 = P code ON,
- 10 = C/A code ON.

20.3 .3.3.1.3 SV Accuracy. Bits 13 through 16 of word three shall give the URA index of the SV (reference paragraph 6.2. 1) for the unauthorized user. The URA index (N) is an integer in the range of 0 through 15 and has the following relationship to the URA of the SV.

<u>URA INDEX</u>	<u>URA (meters)</u>		
0	0.00	< URA ≤	2.40
1	2.40	< URA ≤	3.40
2	3.40	< URA ≤	4.85
3	4.85	< URA ≤	6.85
4	6.85	< URA ≤	9.65
5	9.65	< URA ≤	13.65
6	13.65	< URA ≤	24.00
7	24.00	< URA ≤	48.00
8	48.00	< URA ≤	96.00
9	96.00	< URA ≤	192.00
10	192.00	< URA ≤	384.00
11	384.00	< URA ≤	768.00
12	768.00	< URA ≤	1536.00
13	1536.00	< URA ≤	3072.00
14	3072.00	< URA ≤	6144.00
15	6144.00	< URA (or no accuracy prediction is available - unauthorized users are advised to use the SV at their own risk.)	

For each URA index (N), users may compute a nominal URA value (X) as given by:

- If the value of N is 6 or less, $X = 2^{(1+N/2)}$,
- If the value of N is 6 or more, but less than 15, $X = 2^{(N-2)}$,
- N = 15 shall indicate the absence of an accuracy prediction and shall advise the unauthorized user *to use* that SV at his own risk.

For N = 1, 3, and 5, X should be rounded to 2.8, 5.7, and 11.3 meters, respectively.

20.3 .3.3.1.4 SV Health. The six-bit health indication given by bits 17 through 22 of word three refers to the transmitting SV. The MSB shall indicate a summary of the health of the NAV data, where

0 = all NAV data are OK,

1 = some or all NAV data are bad.

The five LSBS shall indicate the health of the signal components in accordance with the codes given in paragraph 20.3.3.5.1.3. The health indication shall be given relative to the “as designed” capabilities of each SV (as designated by the configuration code - see paragraph 20.3.3.5.1.6). Accordingly, any SV which does not have a certain capability will be indicated as “healthy” if the lack of this capability is inherent in its design or if it has been configured into a mode which is normal from a user standpoint and does not require that capability.

Additional SV health data are given in subframes 4 and 5. The data given in subframe 1 may differ from that shown in subframes 4 and/or 5 of other SVS since the latter may be updated at a different time.

20.3.3 .3.1.5 Issue of Data, Clock (IODC). Bits 23 and 24 of word three in subframe 1 shall be the two MSBS of the ten-bit IODC term; bits one through eight of word eight in subframe 1 shall contain the eight LSBS of the IODC. The IODC indicates the issue number of the data set and thereby provides the user with a convenient means of detecting any change in the correction parameters. Constraints on the IODC as well as the relationship between the IODC and the IODE (issue of data, ephemeris) terms are defined in paragraph 20.3.4.4.

Long-term Extended Operations. For Block 11 SVS, whenever the fit interval flag indicates a fit interval greater than 4 hours, the IODC can be used to determine the actual fit interval of the data set (reference section 20.3.4.4).

20.3 .3.3.1.6 Data Flag for L2 P-Code. When bit 1 of word four is a "1", it shall indicate that the NAV data stream was commanded OFF on the P-code of the L2 channel.

20.3.3 .3.1.7 (Reserved)

20.3 .3.3.1.8 Estimated Group Delay Differential. Bits 17 through 24 of word seven contain the L1-L2 correction term, T_{GD} , for the benefit of "L1 only" or "L2 only" users; the related user algorithm is given in paragraph 20.3.3.3.3.

;-

20.3.3.3.1.9 SV Clock Correction. Bits nine through 24 of word eight, bits one through 24 of word nine, and bits one through 22 of word ten contain the parameters needed by the users for apparent SV clock correction (t_{oc} , a_{f2} , a_{f1} , a_{f0}). The related algorithm is given in paragraph 20.3.3.3.3.

20.3.3.3.2 Subframe 1 parameter Characteristics. For those parameters whose characteristics are not fully defined in Section 20.3.3.3.1, the number of bits, the scale factor of the LSB (which shall be the last bit received), the range, and the units shall be as specified in Table 20-1.

20.3.3.3.3 User Algorithms for Subframe 1 Data. The algorithms defined below (a) allow all users to correct the code phase time received from the SV with respect to both SV code phase offset and relativistic effects, (b) permit the "single frequency" (L1 or L2) user to compensate for the effects of SV group delay differential (the user who utilizes both frequencies does not require this correction, since the clock parameters account for the induced effects), and (c) allow the "two frequency" (L1 and L2) user to correct for the group propagation delay due to ionospheric effects (the single frequency user may correct for ionospheric effects as described in paragraph 20.3.3.5.2.5).

--

Table 20-I. Subframe 1 Parameters

Parameter	No. of Bits**	Scale Factor (LSB)	Effective Range***	units
Code on L2	2	1		discretes
Week No.	10	1		week
2 P data flag	1	1		discrete
V accuracy	4			(see test)
V health	6	1		discretes
T _{GD}	8*	2 ⁻³¹		seconds
IODC	10			(see test)
oc	16	2 ⁴	604.754	seconds
a ₂	8*	2 ⁻⁵⁵		sec/sec ²
a ₁	16*	2 ⁻⁴³		sec/sec
a ₀	22*	2 ⁻³¹		seconds

* Parameters so indicated shall be two's complement, with the sign bit (+ or -) occupying the MSB;

** See Figure 20-1 for complete bit allocation in subframe;

*** Unless otherwise indicated in this column, effective range is the maximum range attainable with indicated bit allocation and scale factor.

20.3.3 3.3.1 User Algorithm for SV Clock Correction. The polynomial defined in the following allows the user to determine the effective SV PRN code phase offset referenced to the phase center of the antennas (Δt_{sv}) with respect to GPS system time (t) at the time of data transmission. The coefficients transmitted in subframe I describe the offset apparent to the two-frequency user for the interval of time in which the parameters are transmitted. This estimated correction accounts for the deterministic SV clock error characteristics of bias, drift and aging, as well as for the SV implementation characteristics of group delay bias and mean differential group delay. Since these coefficients do not include corrections for relativistic effects, the user's equipment must determine the requisite relativistic correction: "Accordingly, the offset given below includes a term to perform this function.

The user shall correct the time received from the SV with the equation (in seconds)

$$t = t_{sv} - \Delta t_{sv} \quad (1)$$

where

$$\begin{aligned} t &= \text{GPS system time (seconds),} \\ t_{sv} &= \text{effective SV PRN code phase time at message transmission time (seconds),} \\ \Delta t_{sv} &= \text{SV PRN code phase time offset (seconds).} \end{aligned}$$

The SV PRN code phase offset is given by

$$\Delta t_{sv} = a_{f0} + a_{f1}(t - t_{oc}) + a_{f2}(t - t_{oc})^2 + \Delta t_r \quad (2)$$

where

a_{f0} , a_{f1} and a_{f2} are the polynomial coefficients given in subframe 1. t_{oc} is the clock data reference time in seconds (reference paragraph 20.3.4.5), and Δt_r is the relativistic correction term (seconds) which is given by

$$\Delta t_r = Fe(A)^{1/2} \sin E_k.$$

The orbit parameters (e, A, E_k) used here are described in discussions of data contained in subframes 2 and 3, while F is a constant whose value is

$$F = \frac{-2\mu^{1/2}}{c^2} = -4.442\ 807633\ (10)^{-10}\ \text{sec}/(\text{meter})^{1/2},$$

where

$$\mu = 3.986005 \times 10^{14} \frac{\text{meters}^3}{\text{second}^2} \quad \text{value of Earth's universal gravitational parameters}$$

$$c = 2.99792458 \times 10^8 \frac{\text{meters}}{\text{second}} = \text{speed of light.}$$

Note that equations (1) and (2), as written, are **coupled**. While the coefficients a_1 and a_2 are generated by using GPS time as indicated in equation (2), **sensitivity** of t_{sv} to t is negligible. This negligible **sensitivity** will allow the user to **approximate** t by t_s in equation (2). The value of t must account for beginning or end of week crossovers. That is, **if** the quantity $t - t_{oc}$ is greater than 302,400 seconds, subtract 604,800 seconds from t . **If** the quantity $t - t_{oc}$ is less than -302,400 seconds, add 604,800 seconds to t .

The control segment will utilize the following alternative but equivalent expression for the relativistic correction when estimating the NAV parameters:

$$\Delta t_r = - \frac{2 \vec{R} \cdot \vec{V}}{c^2}$$

where

- \vec{R} is the instantaneous position vector of the SV,
- \vec{V} is the instantaneous velocity vector of the SV, and
- c is the speed of light. (Reference paragraph 20.3.4.3).

It is immaterial whether the vectors \vec{R} and \vec{V} are expressed in earth-fixed, rotating coordinates or in **earth-centered, inertial** coordinates.

20.3.3 .3.3.2 L1-L2 Correction. The L1 and L2 correction term, T_{GD} , is calculated by the CS to account for the effect of SV group delay differential between L1 and L2 based on measurements made by the SV contractor during factory testing. This correction term is only for the benefit of "single-frequency" (L1 or L2) users; it is necessitated by the fact that the SV clock offset estimates reflected in the ~~agg~~ clock correction coefficient (see paragraph 20.3.3.3.3. 1) are based on the effective PRN code phase as apparent with two frequency ionospheric corrections. Thus, the user who utilizes the L1 frequency only shall modify the code phase offset in accordance with paragraph 20.3.3 .3.3.1 with the equation

$$(\Delta t_{SV})_{L1} = \Delta t_{SV} - T_{GD}$$

where T_{GD} is provided to the user as subframe 1 data. For the user who utilizes L2 only, the code phase modification is given by

$$(\Delta t_{SV})_{L2} = \Delta t_{SV} - \gamma T_{GD}$$

where, denoting the nominal center frequencies of L1 and L2 as f_{L1} and f_{L2} respectively,

$$\gamma = (f_{L1}/f_{L2})^2 = (1575.42/1227.6)^2 = (77/60)^2$$

∴

The value of T_{GD} is not equal to the mean SV group delay differential, but is equal to the delay differential multiplied by $1/(1-\gamma)$. That is,

$$T_{GD} = \frac{1}{1-\gamma} (t_{L1} - t_{L2})$$

where t_{L1} is the GPS time the i^{th} frequency signal is transmitted from the SV.

20.3.3 .3.3.3 Ionospheric Correction. The two frequency (L1 and L2) user shall correct for the group delay due to ionospheric effects by applying the relationship:

$$PR = \frac{PR_2 - \gamma PR_1}{1 - \gamma}$$

where

PR = pseudorange corrected for ionospheric effects,
PR_i = pseudorange measured on the L-band channel indicated by the subscript

and γ is as defined in paragraph 20.3.3.3.3.2. The clock correction coefficients are based on "two frequency" measurements and therefore account for the effects of mean differential delay in SV instrumentation.

20.3 .3.3.3.4 Example Application of Correction Parameters. A typical system application of the correction parameters for a user receiver is shown in Figure 20-3. The ionospheric model referred to in Figure 20-3 is discussed in paragraph 20.3 .3.5.2.5 in conjunction with the related data contained in page 1S of subframe 4.

20.3.3.4 Subframes 2 and 3. The contents of words three through ten of subframes 2 and 3 are defined below, followed by material pertinent to the use of the data.




Figure 20-3. Sample Application of Correction Parameters

20.3.3.4.1 Content of Subframes 2 and 3. The third through tenth words of subframes 2 and 3 shall each contain six parity bits as their LSBs; in addition, two non-information bearing bits shall be provided as bits 23 and 24 of word ten of each subframe for parity computation purposes. Bits 255 through 292 of subframe 2 shall be spares containing alternating ones and zeros with valid parity (reference paragraph 20.3.3.5.1.11). The remaining 375 bits of those two subframes shall contain the ephemeris representation parameters of the transmitting SV.

The ephemeris parameters describe the orbit during the curve fit intervals described in section 20.3.4. Table 20-II gives the definition of the orbital parameters using terminology typical of Keplerian orbital parameters; it shall be noted, however, that the transmitted parameter values are expressed for a coordinate system which allows the best trajectory fit in Earth fixed coordinates for each specific fit interval. The user shall not interpret intermediate coordinate values as pertaining to any conventional or stable coordinate system.

--

Table 20-11. Ephemeris Data Definitions

Mo	Mean Anomaly at Reference Time
An	Mean Motion Difference From Computed Value
e	Eccentricity
$(A)^{1/2}$	Square Root of the Semi-Major Axis
(OMEGA) ₀	Longitude of Ascending Node of Orbit Plane at Weekly Epoch
i ₀	Inclination Angle at Reference Time
ω	Argument of Perigee
OMEGADOT	Rate of Right Ascension
IDOT	Rate of Inclination Angle
c _{uc}	Amplitude of the Cosine Harmonic Correction Term to the Argument of Latitude
C _{us}	Amplitude of the Sine Harmonic Correction Term to the Argument of Latitude
C _{rc}	Amplitude of the Cosine Harmonic Correction Term to the Orbit Radius
C _{rs}	Amplitude of the Sine Harmonic Correction Term to the Orbit Radius
C _{ic}	Amplitude of the Cosine Harmonic Correction Term to the Angle of Inclination
C _{is}	Amplitude of the Sine Harmonic Correction Term to the Angle of Inclination
t _{oe}	Reference Time Ephemeris (reference paragraph 20.3.4.5)
IODE	Issue of Data (Ephemeris)

The issue of ephemeris data (IODE) term shall provide the user with a convenient means for detecting any change in the ephemeris representation parameters. The IODE is provided in both subframes 2 and 3 for the purpose of comparison with the 8 LSBS of the IODC term in subframe 1. Whenever these three terms do not match, a data set cutover has occurred and new data must be collected. The timing of the IODE and constraints on the IODC and IODE are defined in paragraph 20.3.4.4.

Any change in the subframe 2 and 3 data will be accomplished with a simultaneous change in both IODE words. The CS shall assure that the ~~toe~~ value, for at least the first data set transmitted by an SV after an upload, is different from that transmitted prior to the cutover.

A "fit interval" flag is provided in subframe 2 to indicate whether the ephemerides are based on a four-hour fit interval or a fit interval greater than four hours (reference paragraph 20.3.3.4.3.1).

20.3 .3.4.2 Subframe 2 and 3 Parameter Characteristics. For each parameter contained in subframes 2 and 3, the number of bits, the scale factor of the LSB (which shall be the last bit received), the range, and the units shall be as specified in Table 20-111.

--

Table 20-111. Ephemeris Parameters				
Parameter	No. of Bits**	Scale Factor (LSB)	Effective Range***	Units
IODE	8			(see text)
C_{rs}	16*	2^{-5}		meters
Δn	16*	2^{-43}		semi-circles/see
M_0	32*	2^{-31}		semi-circles
c_{uc}	16*	2^{-29}		radians
e	32	2^{-33}	0.03	dimensionless
C_{us}	16*	2^{-29}		radians
$(A)^{1/2}$	32	2^{-19}		meters ^{1/2}
t_{oc}	16	2^4	604,784	seconds
C_{ic}	16*	2^{-29}		radians
(OMEGA)O	32*	2^{-31}		semi-circles
C_{is}	16*	2^{-29}		radians
i_0	32*	2^{-31}		semi-circles
C_{rc}	16*	2^{-5}		meters
ω	32*	2^{-31}		semi-circles
OMEGADOT	24*	2^{-43}		semi-circles/sec
IDOT	14*	2^{-43}		semi-circles/sec
<p>* Parameters so indicated shall be two's complement, with the sign bit (+ or -) occupying the MSB; ** See Figure 20-1 for complete bit allocation in subframe; *** Unless otherwise indicated in this column, effective range is the maximum range attainable with indicated bit allocation and scale factor.</p>				

20.3.3.4.3 User Algorithm for Ephemeris Determination. The user shall compute the earth fixed coordinates of position for the phase center of the SVS' antennas utilizing a variation of the equations shown in Table 20-IV. Subframes 2 and 3 parameters are Keplerian in appearance; the values of these parameters, however, are obtained via a least squares curve fit of the predicted ephemeris of the phase center of the SVS' antennas (time-position quadruples; t, x, y, z). Particulars concerning the periods of the curve fit, the resultant accuracy, and the applicable coordinate system are given in the following subparagraphs.

20.3.3 .4.3.1 Curve Fit Intervals. Bit 17 in word 10 of subframe 2 is a "fit interval" flag which indicates the curve-fit interval used by the CS in determining the ephemeris parameters, as follows:

- O = 4 hours,
- 1 = greater than 4 hours.

The relationship of the curve-fit interval to transmission time and the timing of the curve-fit intervals is covered in section 20.3.4.

:-

Table 20-IV. Elements of Coordinate Systems (sheet 1 of 3)

$\mu = 3.986005 \times 10^{14} \text{ meters}^3/\text{sec}^2$	WGS 84 value of the earth's universal gravitational parameter
$\dot{\Omega}_e = 7.2921151467 \times 10^{-5} \text{ rad/sec}$	WGS 84 value of the earth's rotation rate
$A = (\sqrt{A})^2$	Semi-major axis
$n_0 = \sqrt{\frac{\mu}{A^3}}$	Computed mean motion (rad/see)
$t_k = t - t_{oc}^*$	Time from ephemeris reference epoch
$n = n_0 + \Delta n$	Corrected mean motion
$M_k = M_0 + nt_k$	Mean anomaly

* t is GPS system time at time of transmission, i.e., GPS time corrected for transit time (range/speed of light). Furthermore, t_k shall be the actual total time difference between the time t and the epoch time t_{oc} , and must account for beginning or end of week crossovers. That is, if t_k is greater than 302,400 seconds, subtract 604,800 seconds from t_k . If t_k is less than -302,400 seconds, add 604,800 seconds to t_k .

Table 20-IV. Elements of Coordinate Systems (sheet 2 of 3)

$$M_k = E_k - e \sin E_k$$

Kepler's Equation for Eccentric Anomaly
(may be solved by iteration) (radians)

$$v_k = \tan^{-1} \left\{ \frac{\sin v_k}{\cos v_k} \right\}$$

True Anomaly

$$= \tan^{-1} \left\{ \frac{\sqrt{1-e^2} \sin E_k / (1-e \cos E_k)}{(\cos E_k - e) / (1-e \cos E_k)} \right\}$$

$$E_k = \cos^{-1} \left\{ \frac{e + \cos v_k}{1 + e \cos v_k} \right\}$$

Eccentric Anomaly

$$\Phi_k = v_k + \omega$$

Argument of Latitude

$$\delta u_k = c_{us} \sin 2\Phi_k + c_{uc} \cos 2\Phi_k$$

Argument of Latitude Correction

$$\delta r_k = c_{rs} \sin 2\Phi_k + c_{rc} \cos 2\Phi_k$$

Radius Correction

$$\delta i_k = c_{is} \sin 2\Phi_k + c_{ic} \cos 2\Phi_k$$

Inclination Correction

} Second Harmonic Perturbations

$$u_k = \Phi_k + \delta u_k$$

Corrected Argument of Latitude

$$r_k = A(1 - e \cos E_k) + \delta r_k$$

Corrected Radius

$$i_k = i. + \delta i_k + (\text{IDOT}) t_k$$

Corrected Inclination

Table 20-IV. Elements of Coordinate Systems (sheet 3 of 3)

$$\left. \begin{aligned} x_k' &= r_k \cos u_k \\ y_k' &= r_k \sin u_k \end{aligned} \right\}$$

Positions in **orbital** plane.

$$\Omega_k = \Omega_0 + (\dot{\Omega} - \dot{\Omega}_e) t_k - \dot{\Omega}_e t_{oe}$$

Corrected longitude of ascending node.

$$\left. \begin{aligned} x_k &= x_k' \cos \Omega_k - y_k' \sin \Omega_k \\ y_k &= x_k' \sin \Omega_k + y_k' \cos \Omega_k \\ z_k &= y_k' \sin i_k \end{aligned} \right\}$$

Earth-fixed coordinates.

20.3.3 .4.3.2 Parameter Sensitivity. The sensitivity of the SV'S antenna phase center position to small perturbations in most ephemeris parameters is extreme. The sensitivity of position to the parameters $(A)^{1/2}$, C_{π} and C_{π} is about one meter/meter. The sensitivity of position to the angular parameters is on the order of 10^8 meters/semicircle, and to the angular rate parameters is on the order of 1012 meters/semicircle/second. Because of this extreme sensitivity to angular perturbations, the value of π used in the curve fit is given here. π is a mathematical constant, the ratio of a circle's circumference to its diameter. Here π is taken as

$$\pi = 3.1415926535898.$$

20.3 .3.4.3.3 Coordinate System. The equations given in Table 20-IV provide the SV's antenna phase center position in the WGS 84 earth-centered, earth-fixed reference frame defined as follows:

ORIGIN = Earth's center of mass*

Z-AXIS = Parallel to the direction of the CONVENTIONAL INTENTIONAL ORIGIN (CIO) for polar motion, as defined by the BUREAU INTERNATIONAL DE L'HEURE (BIH) on the basis of the latitudes adopted for the BIH stations**

X-AXIS = Intersection of the WGS 84 reference meridian plane and the plane of the mean astronomic equator, the reference meridian being parallel to the zero meridian defined by the BUREAU INTERNATIONAL DE L'HEURE (BIH) on the basis of the longitudes adopted for the BIH stations***

Y-AXIS = Completes a right-handed, earth-centered, earth-fixed orthogonal coordinate system, measured in the plane of the mean astronomic equator 90° east of the X-axis***

- * Geometric center of WGS 84 ellipsoid
- ** Rotation axis of WGS 84 ellipsoid
- *** X, Y axes of WGS 84 ellipsoid

20.3.3.4.3.4 **Geometric Range.** The user shall account for the effects due to earth rotation rate (reference Table 20-IV) during the time of signal propagation so as to evaluate the path delay in an inertially stable coordinate system. Specifically, if the user works in earth-fixed coordinates he should add $(-h, y \dot{A} t, \dot{\Omega}_e x \dot{A} t, 0)$ to his position (x, y, z) .

20.3.3.5 **Subframes 4 and 5.** Both subframe 4 and 5 are subcommutated 25 times each; the 25 versions of these subframes are referred to as pages 1 through 25 of each subframe. With the possible exception of "spare" pages and explicit repeats, each page contains different specific data in words three through ten. As shown in Figure 20-1, the pages of subframe 4 utilize six different formats, while those of subframe 5 use two. The content of words three through ten of each page is described below, followed by algorithms and material pertinent to the use of the data. ----

20.3.3.5.1 **Content of Subframes 4 and 5.** Words three through ten of each page contain six parity bits as their LSBs; in addition, two non-information bearing bits are provided as bits 23 and 24 of word ten in each page for parity computation purposes. The data contained in the remaining bits of words three through ten of the various pages in subframes 4 and 5 are described in the following subparagraphs.

.4 brief summary of the various data contained in each page of subframes 4 and 5 is as follows:

a. Subframe 4:

- Pages 1, 6, 11, 16 and 21: (reserved);
- Pages 2, 3, 4, 5, 7, 8, 9 and 10: almanac data for SV 25 through 32 respectively. These pages may be **designated** for **other** functions; the format and **content** for **each page** is defined by the SV ID of that page. In this case, the six-bit health **word** of page 25 is set to "6 ones" (**Refer to** 20.3.3.5. 1.3) and the SV ID of the page **will not** have a value in the range of 25 through 32;
- Pages 12, 19, 20, 22, 23 and 24: (reserved);
- Pages 13, 14 and 15: spares;
- Page 17: **special** messages;
- Page 18: ionospheric and UTC data;
- Page 25: A-S flags/SV configurations for 32 SVS, plus SV health for SV 25 through 32.

b. Sub frame 5:

- Pages 1 through 24: almanac data for SV 1 through 24;
- Page 25: SV health data for SV 1 through 24, the almanac reference time and the almanac reference **week** number.

20.3.5 .5.1.1 Data ID and SV ID. The two MSBS of word three in each page shall contain the data ID which defines the applicable GPS NAV data structure. Data ID one (denoted by binary code 00) was utilized during Phase I of the GPS program and is no longer in use; data ID two (denoted by binary code 01) is described in this Appendix. Future data IDs will be defined as necessary.

As shown in Table 20-V, the data ID is utilized to provide one of two indications: (a) for those pages which are assigned to contain the almanac data of one specific SV, the data ID defines the data structure utilized by that SV whose almanac data are contained in that page; and (b) for all other pages, the data ID denotes the data structure of the transmitting SV.

The SV ID is given by bits three through eight of word three in each page as shown in Table 20-V. Specific IDs are reserved for each page of subframes 4 and 5; however, the SV ID of pages 2, 3, 4, 5, 7, 8, 9 and 10 of subframe 4 may change for each page to reflect the alternate contents for that page. The SV IDs are utilized in two different ways: (a) for those pages which contain the almanac data of a given SV, the SV ID is the same number that is assigned to the PRN code phase of that SV (reference Table 3-I), and (b) for all other pages the SV ID assigned in accordance with Table 20-V serves as the "page ID". IDs 1 through 32 are assigned to those pages which contain the almanac data of specific SVs (pages 1-24 of subframe 5 and pages 2-5 and 7-10 of subframe 4). The "0" ID (binary all zeros) is assigned to indicate a dummy SV, while IDs 51 through 63 are utilized for pages containing other than almanac data of a specific SV. The remaining IDs (33 through 50) are unassigned.

Pages which contain identical data (for more frequent repetition) carry the same SV ID (e.g., in subframe 4, pages 1, 6, 11, 16 and 21 carry an ID of 57, while pages 12 and 24 are designated by an ID of 62).

Table 20-V. Data IDs and SV fDs in Subframes 4 and 5

Page	Subframe 4		Subframe 5	
	Data ID	SV ID*	Data ID	Sv ID*
1	Note(2)	57	Note(1)	1
2 Note(3)	Note(1)	25	Note(1)	2
3 Note(3)	Note(1)	26	Note(1)	3
4 Note(3)	Note(1)	27	Note(1)	4
5 Note(3)	Note(1)	28	Note(1)	5
6	Note(2)	57	Note(1)	6
7 Note(3)	Note(1)	29	Note(1)	7
8 Note(3)	Note(1)	30	Note(1)	8
9 Note(3)	Note(1)	31	Note(1)	9
10 Note(3)	Note(1)	32	Note(1)	10
11	Note(2)	57	Note(1)	11
12	Note(2)	62	Note(1)	12
13	Note(2)	52	Note(1)	13
14	Note(2)	53	Note(1)	14
15	Note(2)	54	Note(1)	15
16	Note(2)	57	Note(1)	16
17	Note(2)	55	Note(1)	17
18	Note(2)	56	Note(1)	18
19	Note(2)	58 Note(4)	Note(1)	19
20	Note(2)	59 Note(4)	Note(1)	20
21	Note(2)	57	Note(1)	21
22	Note(2)	60 Note(4)	Note(1)	22
23	Note(2)	61 Note(4)	Note(1)	23
24	Note(2)	62	Note(1)	24
25	Note(2)	63	Note(2)	25

* Use "O" to indicate "dummy" SV. When using "O" to indicate dummy SV, use the data ID of the transmitting SV.

Note 1: Data ID of that SV whose SV ID appears in that page.

Note 2: Data ID of transmitting SV.

Note 3: Pages 2, 3, 4, 5, 7, 8, 9, and 10 of subframe 4 may contain almanac data for SVS 25 through 32, respectively, or data for other functions as identified by a different SV ID from the value shown.

Note 4: SV ID may vary.

ICD-GPS-200C
10 OCT 1993

20.3.3 .5.1.2 Almanac Data. Pages 1 through 24 of subframe 5, as well as pages 2 through 5 and 7 through 10 of subframe 4 contain the almanac data and a SV health word for up to 32 SVS (the health word is discussed in paragraph 20.3.3.5. 1.3). The almanac data are a reduced-precision subset of the clock and ephemeris parameters. The data occupy all bits of words three through ten of each page except the eight MSBS of word three (data ID and SV ID), bits 17 through 24 of word five (SV health), and the 50 bits devoted to parity. The number of bits, the scale factor (LSB), the range, and the units of the almanac parameters are given in Table 20-VI. The algorithms and other material related to the use of the almanac data are given in paragraph 20.3.3.5.2.

The almanac message for any dummy SVS shall contain alternating ones and zeros with valid parity. For twelve or fewer SVS, almanacs may be repeated within the 25-cycle subcommutation limit. Whenever this option is exercised, the following constraints shall apply: (a) each page of subframes 4 and 5, which is assigned by Table 20-V to one of the active SVS in orbit, must contain the almanac data of that SV to which it is assigned by Table 20-V, (b) those almanac-type pages which remain unused per the above rule, shall then be re-assigned to carry a duplicate set of almanac data for the active orbiting SV, (c) these page re-assignments shall be in ascending order of page numbers (starting with subframe 5, followed by subframe 4) being used for SVS having an ascending order of SV IDs, and (d) each re-assigned page must carry the SV ID of that SV whose almanac data it contains.

The almanac parameters shall be updated by the CS at least once every 6 days while the CS is able to upload the SVS. If the CS is unable to upload the SVS, the accuracy of the almanac parameters transmitted by the SVS will degrade over time.

For Block I SVS, one or two sets of almanac data is uploaded to cover the 3-4 days of valid data transmission. For Block II and IIA SVS, three sets of almanac shall be used to span 182 days. The first and second sets will be transmitted for up to six days each; the third set is intended to be transmitted for the duration of the 182 days from the last upload, but the duration of transmission will depend on the individual SV'S capability to retain data in memory. All three sets are based on six-day curve fits that correspond to the first six days of the transmission interval. For Block IIR SVS, multiple sets of almanac parameters shall be uploaded to span 210 days.

--

Table 20-VI. Almanac Parameters				
Parameter	No. of Bits**	Scale Factor (LSB)	Effective Range***	Units
e	16	2^{-21}	602.112	dimensionless
t_{oa}	s	2^{12}		seconds
δ_i ****	16*	2^{-19}		semi-circles
OMEGADOT	16*	2^{-38}		semi-circles/sec
$(A)^{1/2}$	24	2^{-11}		meters ^{1/2}
(OMEGA)O	24*	2^{-23}		semi-circles
ω	24*	2^{-23}		semi-circles
M_o	24*	2^{-23}		semi-circles
a_{p0}	11*	2^{-20}		seconds
\dot{a}_{p1}	11*	2^{-38}		sec/sec

* Parameters so indicated shall be two's complement with the sign bit (+ or -) occupying the MSB;

** See Figure 20-1 for complete bit allocation in subframe;

*** Unless otherwise indicated in this column, effective range is the maximum range attainable with indicated bit allocation and scale factor;

**** Relative to $i_0 = 0.30$ semi-circles.

20.3.3 .5.1.3 SV Health. Subframes 4 and 5 contain two types of SV health data: (a) each of the 32 pages which contain the clock/ephemeris related almanac data provide an eight-bit SV health status word regarding the SV whose almanac data they carry, and (b) the 25th page of subframe 4 and of subframe 5 jointly contain six-bit health status data for up to 32 SVs.

The three MSBS of the eight-bit health words indicate health of the NAV data in accordance with the code given in Table 20-VII. The six-bit words provide a one-bit summary of the NAV data's health status in the MSB position in accordance with paragraph 20.3.3.3.1.4. The five LSBS of both the eight-bit and the six-bit words provide the health status of the SV's signal components in accordance with the code given in Table 20-VIII. A special meaning is assigned, however, to the "6 ones" combination of the six-bit health words in the 25th page of subframes 4 and 5: it indicates that "the SV which has that ID is not available and there may be no data regarding that SV in that page of subframes 4 and 5 that is assigned to normally contain the almanac data of that SV" (NOTE: (a) this special meaning applies to the 25th page of subframes 4 and 5 only; and (b) there maybe data regarding another SV in the almanac-page referred to above as defined in paragraph 20.3.3.5.1.1). The health indication shall be given relative to the "as designed" capabilities of each SV (as designated by the configuration code — see paragraph 20.3.3.5. 1.6). Accordingly, any SV which does not have a certain capability will be indicated as "healthy" if the lack of this capability is inherent in its design or it has been configured into a mode which is normal from a user standpoint and does not require that capability.

Table 20-VII. NAV Data Health Indications

Bit Position in Page			Indication
137	138	139	
0	0	0	ALL DATA OK
0	0	1	PARITY FAILURE -- some or all parity bad
0	1	0	TLM/HOW FORMAT PROBLEM -- any departure from standard format (e.g., preamble misplaced and/or incorrect, etc.), except for incorrect Z-count, as reported in HOW
0	1	1	Z-COUNT IN HOW BAD -- any problem with Z-count value not reflecting actual code phase
1	0	0	SUBFRAMES 1, 2, 3-- one or more elements in words three through ten of one or more subframes are bad
1	0	1	SUBFRAMES 4,5 -- one or more elements in words three through ten of one or more sub frames are bad
1	1	0	ALL UPLOADED DATA BAD -- one or more elements in words three through ten of any one (or more) subframes are bad
1	1	1	ALL DATA BAD -- TLM word and/or HOW and one or more elements in any one (or more) subframes are bad

Table 20-VIII. Codes for Health of SV Signal Components

MSB L S B	Definition
0 0 0 0 0	All Signals OK
0 0 0 0 1	All Signals Weak*
0 0 0 1 0	All Signals Dead
0 0 0 1 1	All Signals Have No Data Modulation
0 0 1 0 0	L1 P Signal Weak
0 0 1 0 1	L1 P Signal Dead
0 0 1 1 0	L1 P Signal Has No Data Modulation
0 0 1 1 1	L2 P Signal Weak
0 1 0 0 0	L2 P Signal Dead
0 1 0 0 1	L2 P Signal Has No Data Modulation
0 1 0 1 0	L1 C Signal Weak
0 1 0 1 1	L1 C Signal Dead
0 1 1 0 0	L1 C Signal Has No Data Modulation
0 1 1 0 1	L2 C Signal Weak
0 1 1 1 0	L2 C Signal Dead
0 1 1 1 1	L2 C Signal Has No Data Modulation
1 0 0 0 0	L1 & L2 P Signal Weak
1 0 0 0 1	L1 & L2 P Signal Dead
1 0 0 1 0	L1 & L2 P Signal Has No Data Modulation
1 0 0 1 1	L1 & L2 C Signal Weak
1 0 1 0 0	L1 & L2 C Signal Dead
1 0 1 0 1	L1 & L2 C Signal Has No Data Modulation
1 0 1 1 0	L1 Signal Weak*
1 0 1 1 1	L1 Signal Dead
1 1 0 0 0	L1 Signal Has No Data Modulation
1 1 0 0 1	L2 Signal Weak*
1 1 0 1 0	L2 Signal Dead
1 1 0 1 1	L2 Signal Has No Data Modulation
1 1 1 0 0	SV <u>Is</u> Temporarily Out (Do not use this SV during current pass**)
1 1 1 0 1	SV <u>Will Be</u> Temporarily Out (Use with caution**)
1 1 1 1 0	Spare
1 1 1 1 1	More Than One Combination Would Be Required To Describe Anomalies (Except those marked by **)

* 3 to 6 dB below specified power level due to reduced power output, excess phase noise, SV attitude, etc.

Additional SV health data are given in subframe 1. The data given in subframes 1, 4, and 5 of the other SVS may differ from that shown in subframes 4 and/or 5 since the latter may be updated at a different time.

The eight-bit health status words shall occupy bits 17 through 24 of word five in those 32 pages which contain almanac data for individual SVS. The six-bit health status words shall occupy the 24 MSBS of words four through nine in page 25 of subframe 5 plus bits 19 through 24 of word 5, the 24 MSBS of word 9, and the 15 MSBS of word 10 in page 25 of subframe 4.

The predicted health data will be updated at the time of upload when a new almanac has been built by the CS. The transmitted health data may not correspond to the actual health of the transmitting SV or other SVS in the constellation.

20.3.3 .5.1.4 (Reserved).

20.3.3 .5.1.5 (Reserved).

20.3.3.5.1.6 Anti-Spoof (A-S) Flags and SV Configurations. page 25 of subframe 4 shall contain a four-bit-long term for each of up to 32 SVS to indicate the A-S status and the configuration code of each SV. The MSB of each four-bit term shall be the A-S flag with a "1" indicating that A-S is ON. The three LSBS shall indicate the configuration of each SV using the following code:

<u>Code</u>	<u>SV Configuration</u>
000	"Block I" SV (memory capacity for 3-4 days of uploaded data)
001	"Block II" SV (A-S capability, plus flags for A-S and "alert" in HOW; memory capacity as described in paragraph 20.3.2).

Additional codes will be assigned in the future. should the need arise.

These four-bit terms shall occupy bits 9 through 24 of word three, the 24 MSBs of words four through seven, and the 16 MSBs of word eight, all in page 25 of subframe 4.

Since the anti-spoof information is updated by the CS at the time of upload, the anti-spoof data may not correspond to the actual anti-spoof status of the transmitting SV or other SVS in the constellation.

20.3.3.5.1.7 Almanac Reference Week. Bits 17 through 24 of word three in page 25 of subframe 5 shall indicate the number of the week (WN_a) to which the almanac reference time (t_{oa}) is referenced (see paragraphs 20.3.3.5.1.2 and 20.3.3.5.2.2). The WN_a term consists of the eight LSBS of the full week number. Bits 9 through 16 of word three in page 25 of subframe 5 shall contain the value of t_{oa} which is referenced to this WN_a .

20.3.3.5.1.8 Universal Coordinated Time (UTC) Parameters. The 24 MSBs of words six through nine plus the eight MSBs of word ten in page 18 of subframe 4 shall contain the parameters related to correlating UTC time with GPS time. The bit length, scale factors, ranges, and units of these parameters are given in Table 20-IX. The related algorithms are described in paragraph 20.3.3.5.2.4.

--

The UTC parameters shall be updated by the CS at least once every six days while the CS is able to upload the SVS. If the CS is unable to upload the SVS, the accuracy of the UTC parameters transmitted by the SVS will degrade over time.

20.3.3 .5.1.9 Ionospheric Data. The ionospheric parameters which allow the "L1 only" or "L2 only" user to utilize the ionospheric model (reference paragraph 20.3.3 .5.2.5) for computation of the ionospheric delay are contained in page 18 of subframe 4. They occupy bits 9 through 24 of word three plus the 24 MSBS of words four and five. The bit lengths, scale factors, ranges, and units of these parameters are given in Table 20-X.

The ionospheric data shall be updated by the CS at least once every six days while the CS is able to upload the SVS. If the CS is unable to upload the SVs, the ionospheric data transmitted by the SVS may not be accurate.

Table 20-IX. UTC Parameters

Parameter	No. of Bits**	Scale Factor (LSB)	Effective Range***	Units
A ₀	32*	2 ⁻³⁰	602,112	seconds
A ₁	24*	2 ⁻⁵⁰		sec/sec
A _{tLS}	8*	1	7	seconds
t _{ot}	8	7 ¹²		seconds
WN _t	s	1		weeks
WN _{LSF}	s	1		weeks
DN	8****	1		days
A _{tLSF}	s*	1		seconds

* Parameters so indicated shall be two's complement with the sign bit (+ or -) occupying the MSB;

** See Figure 20-1 for complete bit allocation in subframe;

*** Unless otherwise indicated in this column, effective range is the maximum range attainable with indicated bit allocation and scale factor;

**** Right justified.

Table 20-X. Ionospheric Parameters				
Parameter	No. of Bits**	Scale Factor (LSB)	Effective Range***	Units
α_0	8*	2^{-30}		seconds
α_1	8*	2^{-27}		sec/semi-circle
α_2	8*	2^{-24}		sec/(semi-circle) ²
α_3	s*	2^{-21}		sec/(semi-circle) ³
β_0	8*	γ^{11}		seconds
β_1	8*	2^{1i}		sec/semi-circle
β_2	8*	γ^{16}		sec/(semi-circle) ²
β_3	8*	γ^{16}		sec/(semi-circle) ³

* Parameters so indicated shall be two's complement with the sign bit (+ or -) occupying the MSB;

** See Figure 20-1 for complete bit allocation in subframe;

*** Unless otherwise indicated in this column, effective range is the maximum range attainable with indicated bit allocation and scale factor.

20.3.3.5.1.10 Special Messages. Page 17 of subframe 4 shall be reserved for special messages with the specific contents at the discretion of the operating command. It shall accommodate the transmission of 22 eight-bit ASCII characters. The requisite 176 bits shall occupy bits 9 through 24 of word three, the 24 MSBS of words four through nine, plus the 16 MSBS of word ten. The eight MSBS of word three shall contain the data ID and SV ID, while bits 17 through 22 of word ten shall be spares containing alternating one and zeros. The remaining 50 bits of words three through ten are used for parity (six bits/word) and parity computation (two bits in word ten). The eight-bit ASCII characters shall be limited to the following set:

<u>Alphanumeric Character</u>	<u>ASCII Character</u>	<u>Code (Octal)</u>
A - Z	A - Z	101-132
0 - 9	0 - 9	060-071
+	+	053
.	.	055
. (Decimal point)	.	056
' (Minute mark)	'	047
° (Degree sign)	°	370
/	/	057
Blank	Space	040
''	''	072
“ (Second mark)	“	042

20.3.3.5.1.11 Spare Data Fields. All bits of words three through ten, except the 58 bits used for data ID, SV (page)ID, parity (six LSBS in each word) and parity computation (bits 23 and 24 of word ten) of pages 13, 14 and 15 of subframe 4, and those almanac pages assigned SV ID of zero are designated as spares. In addition, as shown in Table 20-XI, several smaller groups of spare bits exist in subframes 4 and 5. These spare bit positions of each word shall contain a pattern of alternating ones and zeros with valid word parity.

20.3.3.5.1.12 (Reserved).

20.3.3.5.2 Algorithms Related to Subframe 4 and 5 Data. The following algorithms shall apply when interpreting Almanac, Universal Coordinated Time, and Ionospheric data in the Navigation message.

20.3.3.5.2.1 Almanac. The almanac is a subset of the clock and ephemeris data, with reduced precision. The user algorithm is essentially the same as the user algorithm used for computing the precise ephemeris from the one subframe 1, 2, and 3 parameters (see Table 20-IV). The almanac content for one SV is given in Table 20-VI. A close inspection of Table 20-VI will reveal that a nominal inclination angle of 0.30 semicircles is implicit and that the parameter δ_i (correction to inclination) is transmitted, as opposed to the value computed by the user. All other parameters appearing in the equations of Tables 20-IV, but not included in the content of the almanac, are set to zero for SV position determination. In these respects, the application of the Table 20-IV equations differs between the almanac and the ephemeris computations.

Table 20-XI. Spare Bits in Subframe 4 and 5			
Subframe	Page(s)	Word	Spare Bit Positions in Word
4	12, 19, 20, 22, 23, 24	9	9 - 24
	1, 6, 11, 12, 16, 19, 20, 21, 22, 23, 24	10	1 - 22
	17	10	17-22
	1s	10	9-22
	25	8	17-13
	25	10	19-22
5	25	10	4 - 22
NOTE:	In addition, all bits of words three through ten in pages 13, 14, and 15 of subframe 4 (except the 58 bits used for data ID, SV (page) ID, parity and parity computation) are also designated as spares.		

The user is cautioned that the sensitivity to small perturbations in the parameters is even greater for the almanac than for the ephemeris, with the sensitivity of the angular rate terms over the interval of applicability on the order of 10^{14} meters/(semicircle/second). An indication of the URE provided by a given almanac during each of the operational intervals is as follows:

<u>Operational Interval</u>	Almanac Ephemeris URE (estimated by analysis) <u>1 sigma (meters)</u>
Normal	900 ^{*,†}
Short-term Extended	900- 3,600*
Long-term Extended	3600 - 300,000*

* URE values generally tend to degrade quadratically over time. Larger errors may be encountered during eclipse seasons and whenever a propulsive event has occurred.

† After the CS is unable to upload the SVS, URE values for the Block IIR SVS operating in the Autonav mode tend to degrade quadratically such that the URE will approach 300,000 meters 1 sigma at 180 days.

20.3.3 .5.2.2 Almanac Reference Time.

Normal and Short-term Extended Operations. The almanac reference time, t_{oa} , is some multiple of 2^{12} seconds occurring approximately 70 hours after the valid transmission time for this almanac data set (reference 20.3.4.5). The almanac is updated often enough to ensure that GPS time, t , shall differ from t_{oa} by less than 3.5 days during the transmission period. The time from epoch t_k shall be computed as described in Table 20-IV, except that t_{oe} shall be replaced with t_{oa} .

Long-term Extended Operations. During long-term extended operations or if the user wishes to extend the use time of the almanac beyond the time span that it is being transmitted, one must account for crossovers into time spans where these computations of t_k are not valid. This may be accomplished without time ambiguity by recognizing that the almanac reference time (t_{oa}) is referenced to the almanac reference week (WN_a), both of which are given in word three of page 25 of subframe 5 (see paragraph 20.3.3.5.1.7).

All t_{oa} values in subframes 4 and 5 shall be the same for a given almanac data set and shall differ for successive data sets which contain changes in almanac parameters or SV health. Note that cutover to a new upload may occur between the almanac pages of interest and page 25 of subframe 5 (reference paragraph 20.3.4. I), and thus there may be a temporary inconsistency between t_{oa} , in the almanac page of interest, and in word 3 of page 25 of subframe 5. The t_{oa} mismatch signifies that this WN_a may not apply to the almanac of interest and that the user must not apply almanac data until the pages with identical values of t_{oa} are obtained.

20.3.3 .5.2.3 Almanac Time Parameters. The almanac time parameters shall consist of an 1 I-bit constant term (a_0) and a 1 I-bit first order term (a_1). The applicable first order polynomial, which shall provide time to within 2 microseconds of GPS time (t) during the interval of applicability, is given by

$$t = t_{sv} - \Delta t_{sv}$$

where

$$\begin{aligned}
 t &= \text{GPS system time (seconds),} \\
 t_{sv} &= \text{effective SV PRN code phase time at message transmission time} \\
 &\quad \text{(seconds),} \\
 \Delta t_{sv} &= \text{SV PRN code phase time offset (seconds).}
 \end{aligned}$$

The SV PRN code phase offset is given by

$$\Delta t_{sv} = a_{f0} + a_{f1} t_k$$

where the computation of t_k is described in paragraph 20.3.3.5.2.2, and the polynomial coefficients a_{f0} and a_{f1} are given in the almanac. Since the periodic relativistic effect is less than 25 meters, it need not be included in the time scale used for almanac evaluation. Over the span of applicability, it is expected that the almanac time parameters will provide a statistical URE component of less than 135 meters, one sigma. This is partially due to the fact that the error caused by the truncation of a_{f0} and a_{f1} may be as large as 150 meters plus 50 meters/day relative to the t_{0a} reference time.

∴

During extended operations (short-term and long-term) the almanac time parameter may not provide the specified time accuracy or URE component.

20.3.3 .5.2.4 Universal Coordinated Time (UTC). Page 1S of subframe 4 includes: (1) the parameters needed to relate GPS time to UTC, and (2) notice to the user regarding the scheduled future or recent past (relative to NAV message upload) value of the delta time due to leap seconds (Δt_{LSF}), together with the week number (WN_{LSF}) and the day number (DN) at the end of which the leap second becomes effective. "Day one" is the first day relative to the end/start of week and the WN_{LSF} value consists of the eight LSBS of the full week number. The user must account for the truncated nature of this parameter as well as truncation of WN , WN_t , and W_{LSF} due to rollover of the full week number (see paragraph 3.3.4@). The CS shall manage these parameters such that the absolute value of the difference between the untruncated WN and WN_{LSF} values shall not exceed 127.

Depending upon the relationship of the effectivity date to the user's current GPS time, the following three different UTC/GPS-time relationships exist:

a. Whenever the effectivity time indicated by the WN_{LSF} and the DN values is not in the past (relative to the user's present time), and the user's present time does not fall in the time span which starts at $DN + 3/4$ and ends at $DN + 5/4$, the UTC/GPS-time relationship is given by

$$t_{UTC} = (t_E - \Delta t_{UTC})[\text{Modulo } 86400 \text{ seconds}]$$

where t_{UTC} is in seconds and

$$\Delta t_{UTC} = \Delta t_{LS} + A_0 + A_1 (t_E - t_{ot} + 604800 (WN - WN_t)), \text{ seconds};$$

t_E = GPS time as estimated by the user on the basis of correcting t_{sv} for factors described in paragraph 20.3.3.3.3 as well as for ionospheric and SA (dither) effects;

Δt_{LS} = delta time due to leap seconds;

A_0 and A_1 = constant and first order terms of polynomial;

t_{ot} = reference time for UTC data (reference 20.3.4.5);

WN = current week number (derived from subframe 1);

WN_t = UTC reference week number.

The estimated GPS time (t_E) shall be in seconds *relative* to end/start of week. The reference time for UTC data (t_{ot}) shall be referenced to the start of that week whose number (WN_t) is given in word eight of page 1 S in subframe 4. The WN_t value consists of the eight LSBs of the full week number. The user must account for the truncated nature of this parameter as well as truncation of WN , WN_t , and WN_{LSF} due to rollover of the full week number (see paragraph 3.3.4(b)). The CS shall manage these parameters such that the absolute value of the difference between the untruncated WN and WN_t values shall not exceed 127.

b. Whenever the user's current time falls within the time span of $DN + 3/4$ to $DN + 5/4$, proper accommodation of the leap second event with a possible week number transition is provided by the following expression for UTC:

$$t_{UTC} = W[\text{Modulo}(86400 + \Delta t_{LSF} - \Delta t_{LS})], \text{ seconds:}$$

where

$$w = (t_E - \Delta t_{UTC} - 43200) [\text{Modulo } 86400] + 43200, \text{ seconds;}$$

and the definition of Δt_{UTC} (as given in 20.3.3.5.2.4a above) applies throughout the transition period. Note that when a leap second is added, unconventional time values of the form 23:59:60.xxx are encountered. Some user equipment may be designed to approximate UTC by decrementing the running count of time within several seconds after the event, thereby promptly returning to a proper time indication. Whenever a leap second event is encountered, the user equipment must consistently implement carries or borrows into any year/week/day counts.

c. Whenever the effectivity time of the leap second event, as indicated by the WN_{LSF} and DN values, is in the "past" (relative to the user's current time), the relationship previously given for t_{UTC} in 20.3.3.5.2.4a above is valid except that the value of Δt_{LSF} is substituted for Δt_{LS} . The CS will coordinate the update of UTC parameters at a future upload so as to maintain a proper continuity of the t_{UTC} time scale.

20.3.3.5.2.5 Ionospheric Model. The "two frequency" (L1 and L2) user shall correct the time received from the SV for ionospheric effect by utilizing the time delay differential between L1 and L2 (reference paragraph 20.3.3.3.3.3). The "one frequency" user, however, may use the model given in Figure 20-4 to make this correction.

It is estimated that the use of this model will provide at least a 50 percent reduction in the single - frequency user's RMS error due to ionospheric propagation effects. During extended operations, or for the Block IIR SVS in the Autonav mode if the CS is unable to upload the SVS, the use of this model will yield unpredictable results.

20.3.3.5.2.6 (Reserved).

::

The ionospheric correction model is given by

$$T_{\text{iono}} = \begin{cases} F \left[5.0 \cdot 10^{-9} + (\text{AMP}) \left(1 - \frac{x^2}{2} + \frac{x^4}{24} \right) \right], & |x| < 1.57 \\ F \cdot (5.0 \cdot 10^{-9}) & , 1X121.57J \end{cases} \quad (\text{sec})$$

where

T_{iono} is referred to the L1 frequency; if the user is operating on the L2 frequency, the correction term must be multiplied by y (reference paragraph 20.3.3.3.2),

$$\text{AMP} = \begin{cases} \sum_{n=0}^3 \alpha_n \phi_m^n, & \text{AMP} \geq 0 \\ \text{if AMP} < 0, \text{AMP} = 0 \end{cases} \quad (\text{sec})$$

\therefore

$$x = \frac{2\pi(t - 50400)}{\text{PER}}, \quad (\text{radians})$$

$$\text{PER} = \begin{cases} \sum_{n=0}^3 \beta_n \phi_m^n, & \text{PER} \geq 72,000 \\ \text{if PER} < 72,000, \text{PER} = 72,000 \end{cases} \quad (\text{sec})$$

$$F = 1.0 + 16.0 [0.53 - E]^3$$

and α_n and β_n are the satellite transmitted data words with $n = 0, 1, 2,$ and 3 .

Figure 20-4. Ionospheric Model (Sheet 1 of 3)

Other equations that must be solved are

$$\phi_m = \phi_i + 0.064 \cos(\lambda_i - 1.617) \quad (\text{semi-circles})$$

$$\lambda_i = \lambda_u - \psi \frac{n^A}{\cos \phi_i} \quad (\text{semi-circles})$$

$$\phi_i = \begin{cases} @.+ \psi \cos A (\text{semi-circles}), |\phi_i| \leq 0.416 \\ \text{if } \phi_i > +0.416, \text{ then } \phi_i = +0.416 \\ \text{if } \phi_i < -0.416, \text{ then } \phi_i = -0.416 \end{cases} \quad (\text{semi-circles})$$

$$\psi = \frac{0.0137}{E + 0.11} - 0.022 \quad (\text{semicircles})$$

$$t = 4.32 * 10^4 \lambda_i + \text{GPS time} \quad (\text{See})$$

where

$0 \leq t < 86400$: therefore, if $t \geq 86400$ seconds, subtract 86400 seconds;

if $t < 0$ seconds, add 86400 seconds.

Figure 20-4. Ionospheric Model (Sheet 2 of 3)

The terms used in computation of ionospheric delay areas follows:

•Satellite Transmitted Terms

α_n	the coefficients of a cubic equation representing the amplitude of the vertical delay (4 coefficients - S bits each)
β_n	the coefficients of a cubic equation representing the period of the model (4 coefficients - S bits each)

•Receiver Generated Terms

E	elevation angle between the user and satellite (semi-circles)
A	azimuth angle between the user and satellite, measured clockwise positive from the true North (semi-circles)
ϕ_u	user geodetic latitude (semi-circles) WGS-84
λ_u	user geodetic longitude (semi-circles) WGS-84
GPS time -	receiver computed system time

•Computed Terms

X	phase (radians)
F	obliquity factor (dimensionless)
t	local time (see)
ϕ_m	geomagnetic latitude of the earth projection of the ionospheric intersection point (mean ionospheric height assumed 350 km) (semi-circles)
λ_i	geodetic longitude of the earth projection of the ionospheric intersection point (semi-circles)
ϕ_i	geodetic latitude of the earth projection of the ionospheric intersection point (semi-circles)
ψ	earth's central angle between the user position and the earth projection of ionospheric intersection point (semicircles)

Figure 20-4. Ionospheric Model (Sheet 3 of 3)

20.3.4 Timing Relationships. The following conventions shall apply:

20.3.4.1 Paging and Cutovers. At end/start of week (a) the cyclic paging of subframes 1 through 5 shall restart with subframe 1 regardless of which subframe was last transmitted prior to end/start of week, and (b) the cycling of the 25 pages of subframes 4 and 5 shall restart with page 1 of each of the subframes, regardless of which page was the last to be transmitted prior to the end/start of week. Cutovers to newly updated data for subframes 1, 2, and 3 occur on frame boundaries (i. e., Modulo 30 seconds relative to end/start of week). Newly updated data for subframes 4 and 5 may start to be transmitted with any of the 25 pages of these subframes.

20.3.4.2 SV Time vs. GPS Time. In controlling the SVS and uploading of data, the CS shall allow for the following timing relationships:

- a. **Each SV operates on its own SV time:**
- b. **All time-related data** in the TLM word and the HOW shall be in SV-time:
- c. All other data in the NAV message shall be relative to GPS time:
- d. The acts of transmitting the NAV message shall be executed by the SV on SV time.

20.3.4.3 Speed of Light. The speed of light used by the CS for generating the data described in the above paragraphs is

$$c = 2.99792458 \times 10^8 \text{ meters per second}$$

which is the official WGS-84 speed of light. The user shall use the same value for the speed of light in all computations.

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

20.3.4.4 Data Sets. The IODE is an S bit number equal to the S LSBS of the 10 bit IODC of the same data set. The following rules govern the transmission of IODC and IODE values in different data sets: (1) The transmitted IODC will be different from any value transmitted by the SV during the preceding seven days; (2) The transmitted IODE will be different from any value transmitted by the SV during the preceding six hours; (3) For Block I SVS, the IODCs shall be any numbers in the range 0 to 1023 excluding those values of IODCs that correspond to IODES values in the range 240 to 255. For Block II SVS, the range of IODC will be as given in Table 20-XII.

Cutovers to new data sets will occur only on hour boundaries except for the first data set of a new upload. The first data set may be cut-in (reference paragraph 20.3.4. 1) at any time during the hour and therefore may be transmitted by the SV for less than one hour. During short-term operations, cutover to 4-hour sets and subsequent cutovers to succeeding 4-hour data sets will always occur Modulo 4 hours relative to end/start of week. Cutover from 4-hour data sets to 6-hour data sets shall occur Modulo 12 hours relative to end/start of week. Cutover from 12-hour data sets to 24-hour data sets shall occur Modulo 24 hours relative to end/start of week. Cutover from a data set transmitted 24 hours or more occurs on a Modulo 24-hour boundary relative to end/start of week.

The start of the transmission interval for each data set corresponds to the beginning of the curve fit interval for the data set. Each data set remains valid for the duration of its curve fit interval.

--

Table 20-XII. IODC Values and Data Set Lengths for Block 11 SVS			
Days Spanned	Transmission Interval (hours)	Curve Fit Interval (hours)	IODC Range (Note 1)
1	1 (Note 4)	4	(Note 2)
2-14	4	6	(Note 2)
15-16	6	8	240-247
17-20	12	14	248-255, 496 (Note 3)
21-27	24	26	497-503
28-41	48	50	504-510
42-59	72	74	511, 752-756
60-87	96	98	757-763
88-122	120	122	764-767, 1008-1010
123-182	144	146	1011-1020

Note 1: For transmission intervals of 6 hours or greater, the IODC values shall be transmitted in increasing order.

Note 2: IODC values for blocks with 2- or 4-hour transmission intervals (at least the first 14 days after upload) shall be any numbers in the range 0 to 1023 excluding those values of IODC that correspond to IODE values in the range 240-255, subject to the constraints on re-transmission given in paragraph 20.3.4.4.

Note 3: The ninth 12-hour data set may not be transmitted.

Note 4: Some SVS will have transmission intervals of 2 hours per paragraph 20.3.4.4.

Normal Operations. The subframe 1, 2, and 3 data sets are transmitted by the SV for periods of one hour, The corresponding curve fit interval is four hours. Block II, Block 11A, and Block IIR SVS in the Block 11A mode will deviate. They will transmit subframe 1, 2, and 3 data sets for periods of two hours. The corresponding curve-fit interval will be four hours.

Short-term and Long-term Extended Operations. For the first 2 to 3 days of short-term] operations, Block I SVS will transmit data sets for periods of four hours. (Block I SVS can only store a total of 3-4 days of uploaded data.) The corresponding curve fit internals are six hours. For Block II SVS, the transmission intervals and curve fit intervals with the applicable IODC ranges are given in Table 20-XII.

20.3.4.5 Reference Times. Many of the parameters which describe the SV state vary with true time, and must therefore be expressed as time functions with coefficients provided by the Navigation Message so as to be evaluable by the user equipment. These include the following parameters as functions of GPS time:

- a. SV time,
- b. Mean anomaly,
- c. Longitude of ascending node,
- d. UTC,
- e. Inclination.

Each of these parameters is formulated as a polynomial in time. The specific time scale of expansion can be arbitrary. Due to the short data field lengths available in the Navigation Message format, the nominal epoch of the polynomial is chosen near the midpoint of the expansion range so that quantization error is small. This results in time epoch values which can be different for each data set. Time epochs contained in the Navigation Message and the different algorithms which utilize them are related as follows:

<u>Epoch</u>	<u>Application Algorithm Reference</u>
t_{oc}	20.3.3 .3.3.1
t_{oe}	20.3.3.4.2
t_{oa}	20.3.3.5.2.2 and 20.3.3 .5.2.3
t_{ot}	20.3.3 .5.2.4

For Block I SVs, the following describes the nominal selection, which will be reexpressed Modulo 604,800 seconds in the Navigation Message:

$t_{oc}, t_{oe} \approx$ 2 hours after the first valid transmission time for 4-hour fit interval data sets, and 3 hours after the start of transmission for 6-hour fit interval data sets.

$t_{oa}, t_{ot} \approx$ 70 hours after the first valid transmission.

For Block II SVS, Table 20-XIII describes the nominal selection which will be expressed Modulo 604,800 seconds in the Navigation Message.

The coefficients of expansion are obviously dependent upon choice of epoch, and thus the epoch time and expansion coefficients must be treated as an inseparable parameter set. Note that a user applying current navigation data will normally be working with negative values of $(t-t_{oc})$ and $(t-t_{oe})$ in evaluating the expansions.

The CS will introduce small deviations from the nominal if necessary to preclude possible data set transition ambiguity when a new upload is cut over for transmission. A change from the reference time is used to indicate a change of values in the data set.

IRN-200C-001
ICD-GPS-200C
13 OCT 1995

Table 20-XIII. Reference Times for Block II SVS					
Fit Interval (hours)	Transmission Interval (hours)	Hours After First Valid Transmission Time			
		t_{oc} (clock)	t_{oe} (ephemeris)	t_{oa} (almanac)	t_{ot} (UTC)
4	1 ⁴	2	2		
6	4	3	3		
8	6	4	4		
14	12	7	7		
26	24	13	13		
50	48	25	25		
74	72	37	37		
98	96	49	49		
122	120	61	61		
146	144	73	73		
144 (6 days)	144			70	70
144 (6 days)	40s0			70	70
* Some SVs will have transmission intervals of 2 hours per paragraph 20.3.4.4.					

20.3.5 Data Frame Parity. The data signal shall contain parity coding according to the following conventions.

30.3.5.1 SV/CS Parity Algorithm. This algorithm links 30-bit words within and across subframes of ten words using the (32,26) Hamming Code described in Table 20-XIV.

20.3.5.2 User Parity Algorithm. As far as the user is concerned, several options are available for performing data decoding and error detection. Figure 20-5 presents an example flow chart that defines one way of recovering data (d_n) and checking parity. The parity bit D_{30} is used for recovering raw data. The parity bits D_{29} and D_{30} , along with the recovered raw data (d_n) are Modulo-2 added in accordance with the equations appearing in Table 20-XIV for $D_{25} \dots D_{30}$, which provide parity to compare with transmitted parity $D_j \dots D_{30}$.

::

Table 20-XIV. Parity Encoding Equations

D_1	=	$d_1 \oplus D_{30}^*$
D_2	=	$d_2 \oplus D_{30}^*$
D_3	=	$d_3 \oplus D_{30}^*$
•		•
•		•
•		•
•		•
D_{24}	=	$d_{24} \oplus D_{30}^*$
D_{25}	=	$D_{29}^* \oplus d_1 \oplus d_2 \oplus d_3 \oplus d_5 \oplus d_6 \oplus d_{10} \oplus d_{11} \oplus d_{12} \oplus d_{13} \oplus d_{14} \oplus d_{17} \oplus d_{18} \oplus d_{20} \oplus d_{23}$
D_{26}	=	$D_{30}^* \oplus d_2 \oplus d_3 \oplus d_4 \oplus d_6 \oplus d_7 \oplus d_{11} \oplus d_{12} \oplus d_{13} \oplus d_{14} \oplus d_{15} \oplus d_{18} \oplus d_{19} \oplus d_{21} \oplus d_{24}$
D_{27}	=	$D_{29}^* \oplus d_1 \oplus d_3 \oplus d_4 \oplus d_5 \oplus d_7 \oplus d_8 \oplus d_{12} \oplus d_{13} \oplus d_{14} \oplus d_{15} \oplus d_{16} \oplus d_{19} \oplus d_{20} \oplus d_{22}$
D_{28}	=	$D_{30}^* \oplus d_2 \oplus d_4 \oplus d_5 \oplus d_6 \oplus d_8 \oplus d_9 \oplus d_{13} \oplus d_{14} \oplus d_{15} \oplus d_{16} \oplus d_{17} \oplus d_{20} \oplus d_{21} \oplus d_{23}$
D_{29}	=	$D_{30}^* \oplus d_1 \oplus d_3 \oplus d_5 \oplus d_6 \oplus d_7 \oplus d_9 \oplus d_{10} \oplus d_{14} \oplus d_{15} \oplus d_{16} \oplus d_{17} \oplus d_{18} \oplus d_{21} \oplus d_{22} \oplus d_{24}$
D_{30}	\therefore =	$D_{29}^* \oplus d_3 \oplus d_5 \oplus d_6 \oplus d_8 \oplus d_9 \oplus d_{10} \oplus d_{11} \oplus d_{13} \oplus d_{15} \oplus d_{19} \oplus d_{22} \oplus d_{23} \oplus d_{24}$

where

d_1, d_2, \dots, d_{24} are the source data bits;

the symbol * is used to identify the last 2 bits of the previous word of the subframe;

$D_{25}, D_{26}, \dots, D_{30}$ are the computed parity bits;

$D_1, D_2, \dots, D_{29}, D_{30}$ are the bits transmitted by the SV;

\oplus is the "Modulo-2" or "Exclusive-Or" operation.




Figure 20-5. Example Flow Chart for User Implementation of Parity Algorithm

(This page intentionally left blank.)

∴

