

Improving Colorado Transportation Through Investigation and Innovation: A Status Report on CDOT Research Activities

June 1999

PROTECTED UNDER INTERNATIONAL COPYRIGHT ALL RIGHTS RESERVED. NATIONAL TECHNICAL INFORMATION SERVICE U.S. DEPARTMENT OF COMMERCE Colorado Department of Transportation CDOT-DTD-R-99-6

Contents

Introduction...pg.1 Strategic Direction...pg. 2 Mission Statement...pg.1

Is This the Only Way I Can Have My Research Needs Addressed?...pg. 4 How Does the Research Branch Decide Which Research Studies to Do?...pg. 3

Research Study Panels...pg. 6 Research Funding...pg. 4

The Peer Exchange...pg. 6

University Participation in Research...pg. 8

Research Branch Staff ...pg. 8

Library Services...pg. 12 Technology Transfer...pg. 10

Current Research Studies

In-Place Voids...pg. 16

Stone Matrix Asphalt Pavements...pg. 17

Use of Pre-Compaction Technology for Better Pavement Performance...pg. 19

PCCP Texturing Methods...pg. 20

SHRP - Seasonal Monitoring Program Update...pg. 23

SHRP - SPS-4 Experiment, Joint Geometry Evaluation, SH 287 South of Lamar...pg. 25 SHRP - AASHTO Task Force of SHRP Implementation Lead State Program...pg. 24

SHRP - Joint Resealing Experiment, I-25 (MP 260-261), Contract H-106...pg. 26

SHRP - SPS-2 Experiment, Study of Structural Factors in Rigid Pavements...pg. 28

Cracking in Bridge Decks: Cause and Mitigation...pg. 30

Evaluating Performance and Design Assumptions of a Mechanically Stabilized Earth (MSE) Wall...pg. 33

Calcium Nitrite Corrosion Inhibitor...pg. 35

Reinforced Soil Abutment and Piers Demonstration...pg. 36

Performance of the Reinforced Soil Abutments of Meadows/Founders Bridge Over I-25 at Working Loads...pg. 38

Backfill of Earth Retaining Walls: Design Parameters and Construction Specifications...pg. 40

Evaluating Bedrock Bridge Scour Potential...pg. 41

Effect of Magnesium Chloride on Asphalt Pavements...pg. 42

High Altitude Snow and Ice Control: Effects on Water Quality...pg. 44

Effects of Cattails on Wetlands...pg. 45

Cost of Sanding...pg. 46

Hamburg Rut Tester Implementation...pg. 47

Evaluation of Slope Stabilization Methods...pg. 48

Sites with Promise...pg. 50

Integration of Ramp Metering with Ramp Traffic Signals...pg. 51

Parametric Cost Estimation Research...pg. 52

I-70 West Link Travel Time Study...pg. 52

Interaction Between Pedestrians and Vehicles Using Smart Signing...pg. 53

Cross Modal Performance Measures...pg. 54

Effects of Geometric Characteristics of Interchanges on Truck Safety...pg. 56

Geofabric Interceptor Drains...pg. 57

Centerline Rumble Strips...pg. 58

1996-1998 Completed Research Studies and Implementation Statements...pg. 59

Introduction

structures, environmental, safety, smart highways/intelligent transportation systems, multi-Transportation Through Investigation and Innovation: A Status Report on CDOT Research This Colorado Department of Transportation Research Branch report "Improving Colorado Activities" highlights current and completed research studies from January 1996-present. report focuses on seven subject areas: asphalt and concrete pavements, bridges and modal, and technology transfer services.

CDOT study manager is listed following each current study. You are invited to call them with If you would like additional information on any of the studies presented within this report, a any questions you may have.

Mission Statement


save Colorado citizens money, time, and lives while preserving the environment and quality of life through the development and deployment of innovative products, materials, and methods The mission of the Research, Development, and Technology Transfer (RD&T) Program is to in transportation.

Strategic Direction

posed of several upper level managers at CDOT. has been working toward focusing the program into areas of strategic importance to CDOT. The RIC is com-Due to the limited amount of funds available for research, the Research and Implementation Council (RIC)

continue more than a single budget year, an annual review is necessary as strategic issues change and already-funded research is expected to address some of the current strategic issues. Every year in either late summer or early fall, the RIC meets to consider the strategic direction that CDOT research should take for the next budget year. Even though it is expected that the strategic direction would

research oversight teams, the RIC set the following focus areas for research contracts During 1998, under the leadership of CDOT's Deputy Chief Engineer, and based on input from the technical



traditional areas of pavements and structures would continue as experimental feature evaluations. evaluation of experimental features on construction projects. It was perceived that research in the more The RIC also recommended setting aside contract funds to supplement staff resources for pilot studies and the

How Does the Research Branch Decide Which Research Studies to Do?

Research needs, in the form of problem statements, are solicited every August from CDOT employees, FHWA technical research oversight team composed of subject matter experts then evaluates the submitted problem tions to the RIC. The RIC then prioritizes these problem statements for funding in the next fiscal year. The TRIS) with their technical knowledge and experience in the field, the oversight team submits recommenda-Division office employees, Metropolitan Planning Organizations, and Colorado universities. A corresponding statements. Combining literature searches from the national Transportation Research Information Service criteria for the prioritization of the problem statements includes the following questions.

Vcan the research effectively address the problem with the time and budget proposed?

√Have others, including state DOTs, already conducted research to solve a similar problem?

 $\sqrt{\mathrm{Is}}$ the problem an urgent or emerging issue to CDOT?

√Do the potential benefits justify the cost of the research?

√Does the research fit the strategic needs of CDOT? Is this the only way that CDOT can have a research need addressed?


Is This the Only Way I Can Have My Research Needs Addressed?

Engineer. are available to conduct these evaluations upon the request of a Region office to the Research Coordination construction project, the above solicitation and prioritization process is not necessary. Research staff members Simply put, no. When a research need is the evaluation and documentation of an experimental feature on a

subsequent years of evaluation are normally funded under the State Planning and Research (SP&R) RD&T program. formally evaluated. Funding for the first year is normally provided by the construction project account and dance with Procedural Directive 3.1, all experimental features incorporated into Federal-Aid projects must be An experimental feature is a method, material, or practice which is not a state or industry standard. In accor-

Research Funding

Officials (AASHTO), the Local Technical Assistance Program, staff salaries, and operating costs are taken out, grammed for a RD&T program. The total CDOT Research Branch budget has been around \$1.5 million dollars there remains approximately \$500,000 each year for contract research. Research Program (NCHRP) per agreement with the American Association of State Highway and Transportation two percent of the federal funds provided to the states for transportation must be set aside for planning and for several years. (see chart next page) After funds needed to support the National Cooperative Highway research activities. Federal law further mandates that a minimum of 25 percent of SP&R funds must be pro-Research studies are funded through a federal set-aside called the SP&R program. Federal law mandates that



Research Study Panels

of the findings. progress reports and presentations and decides on the changes in the Scope of Work that may be needed consultant, another state or federal agency, or CDOT staff. The study panel tracks the research through statement and then selects the research entity to conduct the research. The entity can be a university, a the product of the research. The study panel determines the scope of work that will address the problem sometimes interested others, who have expertise in the subject area or have a vested interest in implementing or operation of Colorado's transportation system. Each study panel is made up of CDOT personnel, and produces a product that will have direct application in either the planning, design, construction, maintenance, formed. The study panel plays a key role in assuring that the study addresses the problem statement and Once a study has been identified for funding through the RIC and budget process, a research study panel is They review and approve the final research report and make recommendations regarding the implementation

research process. to take this opportunity to thank the numerous study panel members for their role in, and dedication to, the While it would be impossible to list all the study panel members at this point, the Research Branch would like

The Peer Exchange

research organizations. Colorado hosted members from the Washington State and Pennsylvania DOT, Region dated by federal regulation, consists of a team of research managers from state DOTs, FHWA , and other In 1998, the CDOT Research Branch underwent its first "peer exchange." The peer exchange, which is man8 FHWA, and the FHWA Colorado Division for its peer exchange. The purpose of the peer exchange is actually a formalized technology transfer activity where RD&T policies and procedures are reviewed with the intent of the host state, review policies and procedures, speak with customers, and then make final recommendations improving each participating state's overall RD&T management process. Peer exchange members travel to to management. Recommended improvements for Colorado included:

•Making adjustments in the membership of the Research and Implementation Council;

•Establishing a cooperative agreement with the University of Colorado at Denver to streamline the contracting process; •Including an implementation action plan in each research study that also defines success/failure for the plan, and; and

 Establishing a standardized report format that includes an executive summary and implementation recommendation.

All recommended improvements have been accomplished.

r

University Participation In Research

able in the universities, their participation provides a good value to CDOT and a training ground for engineerthe study panels are encouraged to select one of Colorado's universities. When appropriate expertise is availuted research problem statements and Colorado universities have been selected to conduct the majority of Colorado School of Mines have all participated in the CDOT RD&T program over the years. Each has contribing students who may someday contribute to Colorado's transportation system. research for CDOT. While the study panels may select whoever they wish to conduct the research for CDOT, The University of Colorado at Denver, the University of Colorado at Boulder, Colorado State University, and the

Research Branch Staff (in alphabetical order)

mentation, Bridge Deck Cracking and Steel Corrosion Structures, Geotechnical Engineering, Mechanically Stabilized Retaining Walls and Slopes, Materials, Instru-Naser Abu-Hejleh (303) 757-9522 naser.abu-hejleh@dot.state.co.us

Concrete Pavements, SHRP Coordination, Preventive Maintenance, Subgrades, Traffic Loads Ahmad Ardani (303) 757-9978 ahmad.ardani@dot.state.co.us

Richard Griffin (303) 757-9973 <u>richard.griffin@dot.state.co.us</u> Research Program Administration

Asphalt Pavements, Crumb Rubber, Polymers, Stone Matrix Asphalt (SMA), Wearing Surfaces Donna Harmelink (303) 757-9518 donna.harmelink@dot.state.co.us

Avalanche Control, Deicing, Environmental Research, Road Weather Information Systems Werner Hutter (303) 757-9975 werner.hutter@dot.state.co.us

Beth Moore (303) 757-9220 <u>beth.moore@dot.state.co.us</u> Research Implementation, Colorado Local Technical Assistance Program (LTAP)

Skip Outcalt (303) 757-9984 skip.outcalt@dot.state.co.us Maintenance Liaison, Research Support

Joan Pinamont (303) 757-9972 joan.pinamont@dot.state.co.us CDOT Library, Research Web Site Administration

Principal Investigator: Person with the primary responsibility for performing and documenting a research

study panel. The Study Manager and Principal Investigator are normally the same person when the PI is an Study Manager: A CDOT employee, responsible for keeping the research study moving and servicing the employee within the Research Branch.

Technology Transfer Program

play boards, videos, training and the use of computer technology such as the CDOT intranet and internet sites new technologies and methods are accomplished with the use of visual aids such as reports, brochures, disusers of research are unaware of the research or are unable to determine its usefulness. Promotion of the and research findings developed by the CDOT Research Branch and to a lesser degree, research developments made by other state DOT's and national research organizations. Research dollars can be wasted if potential It is the goal of the Technology Transfer Program to promote the utilization of new transportation technology

SHONDAININ

publishes the research status report. Newsletter is sent to 750 transportation professionals both in and out-of-state. Technology Transfer also The Technology Transfer program publishes the Research Newsletter on a quarterly basis. The Research

Deployed Research

and the use of this research within CDOT. To see some examples of how research results are being used in the department, see "1996-1998 Completed Research Studies" on page 59. The Technology Transfer Program is currently tracking the deployment of research that has been completed

CDOT Transportation Library

of the library users come from outside the department. (For more on the Transportation Library, see "Library Services" on pages 12-14.) Transportation Library provides library service to approximately 150 customers per month. On average, 30% The Technology Transfer Program also provides administration of the CDOT Transportation Library. The CDOT

Colorado LTAP

job, road materials, pavements and others. LTAP also publishes a quarterly newsletter. To reach the Colorado Program (LTAP) which provides training for Colorado local governments both in current and new technologies and methods. LTAP also offers a "Road Scholar" training program consisting of twelve basic training modules presented over a two-year period. Subjects covered in the two-year program include drainage, safety on the The Technology Transfer Program also coordinates administration of the Colorado Local Technical Assistance LTAP program please call 1-888-848-5827.

Program Manager: Beth Moore

Ŧ

Library Services

books and reports. The in-house collection is supplemented with electronic resources from the Internet and the world. Circulation of library materials is limited to residents of the State of Colorado. The collection of materials in the state. The library, which is open to the public, handles requests for information from all over faculty, historians, and attorneys all take advantage of the library's extensive resources DIALOG. City, county, state and federal employees, transportation consultants and contractors, students and more than 14,000 publications includes CD-ROMs, audio and video cassettes, periodicals, and slides, as well as The CDOT Transportation Library has the largest, most comprehensive collection of transportation-related

Web Pages

Research Newsletters, an index of CDOT Research Reports, and dozens of links to very useful web sites. The acquisition lists, an index of video cassettes available for loan, online CDOT electronic documents, CDOT online catalog of the library's collection. The current pages, meanwhile, contain the monthly CDOT Library Research Branch information, including the library, are now on the web. Reaction to the library pages has been very positive. It is expected that the current library pages will soon be enhanced by the addition of an URL is: http://www.dot.state.co/us/business/library/index.htm

Collection Development

also take advantage of the popular career/personal development collection, which includes selections on requests, a core collection of computer software "how-to" books has been established. CDOT employees can financing, design-build, intelligent-vehicle systems, geosynthetics, and anti-icing. In response to employee Every effort is made to keep up with transportation trends and anticipate requests for materials. The Staff Collection development plays an important role in providing timely, accurate information to library customers. Librarian is always on the lookout for new resources on such topics as partnering, benchmarking, innovative



resumes, interviews, grammar, presentations, customer service, conflict resolution, management, and reengineering.

<u>egislation</u>

and the status of pending legislation are performed on a regular basis. Impromptu internet training is provided for those who prefer to do their own searches. tions, the US Code, the Federal Register, Office of Management and Budget Circulars, the text of various laws US Code Annotated and the Code of Federal Regulations. Internet searches of the Code of Federal Regulament the library's legislative collection, which includes Federal Registers and transportation-related titles of the The Internet has proven to be extremely useful for tracking federal legislation. It is frequently used to supple-


Transportation Research Information Services (TRIS) Searches


ject headings. Search results are sent out on e-mail. federal reports, conference proceedings, papers, and monographs on virtually all aspects of transportation. Research Board (TRB). It provides international coverage of research-in-progress, journal articles, state and Database records contain document titles, publication information, document availability, abstracts, and subtransportation-related topic. TRIS is a bibliographic database maintained and operated by the Transportation CDOT employees can ask the Staff Librarian to perform customized searches of the TRIS database on any


Interlibrary Loan/Document Delivery

If the library does not have an article or publication requested by a CDOT employee for use on a specific workloan, but Colorado residents are welcome to borrow materials for two weeks. Denver Public Library) or a document delivery service. CDOT Library materials are not available for interlibrary related project, the Staff Librarian will try to obtain the materials through interlibrary loan (courtesy of the

Current Research Studies







In-Place Voids

environmental conditions in Colorado, these pavement design changes created new distresses in areas of the distress of rutting is typically found in pavements which consolidate to less than 3%. Stripping and cracking distresses are more likely to occur in pavements that consolidate to no less than 6% or 7%. Over the years, state which had not previously experienced these type of distress. High traffic in a high temperature area and changes have been made to the pavement design process statewide. Because of the various traffic and low traffic in a cold temperature area need different mix designs. The pavement design process assumes a pavement will consolidate to 4% air voids under traffic loading. The

various traffic and environmental conditions in Colorado. were identified. Mixes were designed using varying laboratory compactive efforts that corresponded to the research study was initiated in 1992. Traffic was divided into five categories and four environmental zones To address the different environmental and traffic conditions when designing asphalt mixes in Colorado a

environmental conditions. Results from this study will be available in early 2000. will help identify mix design adjustments. This will make it possible to "customize" designs based on traffic and mance are tied together as they relate to air voids, monitoring the air voids in asphalt pavements over time period, cores will be taken each year to monitor in-place voids over time. Since pavement design and perfor-Twenty three sites were identified for evaluation within the various traffic and climatic zones. Over the study

Principal Investigator: Donna Harmelink Study Manager: Donna Harmelink

Stone Matrix Asphalt Pavements

hot bituminous mixes that have been used in Europe for over 20 years. These pavements provide a very durable In 1994, CDOT constructed its first project using Stone Matrix Asphalt (SMA). SMA pavements are gap-graded, wearing surface and can be placed in thin lifts (2 inches and under.)

tion techniques. This project successfully demonstrated design, production and placement of the European SMA evaluation sections. The nine evaluation sections were constructed using different additives and varied construc-Region 3. This project contained the mix design that had shown the best performance during evaluations on SH which led to the construction and evaluation of the two next projects. The second project, constructed in 1995, complicated by the fact that the maximum thickness of the asphalt wearing surface is limited to 4 inches. Since is located in downtown Denver on the Colfax viaduct between Federal Blvd and Osage Street. Asphalt overlays considered to be the most cost-effective solution. The third project, constructed in 1996, is located on I-70 in Under this study there are three SMA projects being evaluated. The first, located on SH 119, contained nine on bridge decks are common in Colorado, however, the typical replacement of the existing asphalt overlay is SMA pavements are durable, and can be placed in thin lifts, the decision to place an SMA on this bridge was

projects are performing well. None of the projects have demonstrated any significant amount of rutting. The final preliminary results on the SH 119 project indicate that the severity of cracking and raveling found in each evaluation section is directly related to the amount of cracking found in the evaluation section. (The more cracking and raveling the section has the more severe the cracking and raveling is.) The section that has the least amount of cracking on SH119 contains the same additive that was used on the Colfax bridge and on I-70. Both of these evaluation on this study will be completed in Fall 1999.

Principal Investigator: Donna Harmelink Study Manager: Donna Harmelink



Use of Pre-Compaction Technology for Better Pavement Performance

densities typically found in the remainder of the asphalt mat. Lower densities at the longitudinal joint increase tion of the unconfined edge at the joint is difficult to obtain, resulting in lower densities in the joint area than The longitudinal joint between asphalt mats has typically been a major area for pavement distress. Compacthe susceptibility to permeability which in turn increases the deterioration of the pavement through cracking and raveling

national study seven longitudinal joint construction techniques were used in Colorado. In 1997, CDOT imple-In 1994, CDOT participated in a national study initiated to evaluate longitudinal joint construction. Under this mented a revised standard method for constructing longitudinal joints (1" vertical step at the top of joint with a 3:1 taper) based on the preliminary results from this study. This national study will conclude in 1999

provisions for obtaining higher densities in longitudinal joint areas. Results from this study will be available in the mat. The intent of this study is to evaluate the pre-compaction technology and not to evaluate the "Joint In 1997, a research study was initiated to evaluate the "Joint Maker System." This system is being marketed achieved and improves the pavement performance, CDOT's current practices can be modified to incorporate as a method that will pre-compact the longitudinal joint to within 2% of the densities found in the center of Maker System" only. If this technology demonstrates that higher densities at the longitudinal joint can be December 2000,

Principal Investigator: Donna Harmelink

Study Manager: Donna Harmelink

This "Joint Maker" is installed on the edge of the paving machine.

PCCP Texturing Methods


transverse, randomly spaced vs. uniformly spaced and more importantly micro vs. macro textures? ride quality of concrete pavements? What is the most cost-effective surface texture that provides adequate What are the impacts of various surface textures on the frictional characteristics, noise properties and overall friction and at the same time is quiet? Is it the tinned or the sawed textures? How about longitudinal vs.

and the smooth tire at three different speeds of 40, 50 and 65 miles per hour. Noise data were acquired at east of Denver, between mileposts 335-338. Data acquisition included frictional data using both the ribbed various surface textures and to develop guidelines and specifications for future construction. Altogether, nine three locations: inside the test vehicle, behind right rear tire and next to the right shoulder. test sections with varying textural characteristics were established on I-70, eastbound approximately 60 miles In an attempt to answer these questions, CDOT Research initiated a study to investigate the pros and cons of

The interim results of this study revealed the following:

- The smooth-tire is more sensitive to changes in the surface texture than the ribbed- tire and its use over the ribbed tire is recommended;
- ·Longitudinal macro and micro-texture were the most quiet surfaces based on the sound pressure levels taken at the shoulder, inside the test vehicle, and at rear tire; and
- The use of the sand patch test as a texture-depth-measuring device is highly recommended. Excellent correlation was achieved between the sand patch test and the smooth-tire skid numbers.

CDOT has already adopted the longitudinal tinning as a preferred method of texturing concrete pavements. The longitudinal tinning is less expensive to install and produces much less noise. A final report for this study will be out by the end of 1999. Principal Investigator: Ahmad Ardani Study Manager: Ahmad Ardani



SHRP - Seasonal Monitoring Program Update

attempt to establish a relationship between pavement response and deflection measurements taken at differvariations in moisture and temperature on pavement response. The SHRP seasonal monitoring program will ent times of the year for a given climatic zone. A variety of data is being acquired at this site on a monthly Colorado's SHRP monitoring site is one of 64 sites across the country that is being monitored on a monthly basis by the SHRP Regional Contractor. This experiment will evaluate and monitor the impact of seasonal basis, it includes the following:

Moisture and temperature of the subgrade at 12-inch intervals;

Ambient temperature;

Frost penetration depth at 2-inch intervals;

Rainfall and ground water table depth;

Falling weight deflectometer data (FWD); and

Pavement surface elevation.

Work is currently under way to establish a correlation between the back-calculated resilient modulus using the FWD and the laboratory-measured resilient modulus. The expected goal is to use the back-calculated values for characterization of subgrade, base and the pavement surface. The ultimate goal of this program is to rationally use the acquired deflection data for evaluation, analysis and design. This project is ongoing.

Principal Investigator: Ahmad Ardani

Study Manager: Ahmad Ardani

SHRP - AASHTO Task Force on SHRP Implementation Lead State Program

state will transfer its knowledge of a technology and share its proficiency with others in order to advise new users of potential benefits and ultimately to shorten their learning period. that has gained expertise by working closely with a particular SHRP technology. An AASHTO designated lead the implementation of high-payoff SHRP technologies among states. A lead state is a transportation agency The AASHTO Task Force on SHRP Implementation developed the concept of "lead state" in order to facilitate

Altogether, seven key high payoff products have been designated by AASHTO for lead state implementation. They are as follows:

- Innovative Pavement Maintenance Materials: Colorado, Idaho, Iowa, and Pennsylvania,
- ·High Performance Concrete: Missouri, Nebraska, New Hampshire, Texas, Virginia, and Washington;
- ·Superpave: Indiana, Maryland, New York, Texas, and Utah;
- Anti-Icing/Roadway Weather Information Station: Colorado, Iowa, Minnesota, Nevada;
- ·Concrete Assessment and Rehabilitation: Missouri, Virginia;
- ·Preventive Maintenance: Georgia, Michigan, Minnesota and Texas; and
- Alkali Silica Reactivity: Pennsylvania, North Carolina.

Contact: Ahmad Ardani, Innovative Pavement Maintenance Materials

Research Branch)

Wayne Lupton, Anti-Icing/Roadway Weather Information Station (Region III Maintenance)

SHRP - SPS-4 Experiment, Joint Geometry Evaluation, SH 287 South of Lamar

ness of various joint geometry as well as sealed and non-sealed joints. CDOT installed twenty test sections on SH 287 near the Oklahoma/Colorado state line. The width of the joints installed for this study were either 1/8, performance of rigid pavements. The study panel modified this experiment in order to examine the effective-The SPS-4 experiment was originally designed to examine the effects of sealed vs. non-sealed joints on the 1/4, and 3/8 inches, both with and without sealant materials.

ment. CDOT has also adopted this new joint design and is well positioned to realize a substantial savings for cut 3/8" joints. The only difference was that the narrower joints were less labor-intensive and required much The results of this study revealed that the single cut 1/8" joints were as effective as CDOT's standard double less sealant materials. Arizona has already adopted this new joint design, saving 57 cents per linear foot of joint. This equates to an approximately 2 million dollar savings for every 100 miles of 2-lane concrete paveyears to come.

Principal Investigator: Ahmad Ardani

Study Manager: Ahmad Ardani


SHRP - Joint Resealing Experiment, I-25 (MP 260 -261), Contract H-106

32 test sections were installed, using a variety of joint sealant materials, of which 16 were replicates. field performance evaluation of various joint sealant materials, designs, and installation procedures. A total of Highway Research Program (SHRP) initiated contract H-106. In this experiment, researchers will conduct a In order to address the deficiencies of current joint resealing materials, designs, and practices, the Strategic

looked for and recorded were adhesion loss, cohesion loss, spalling, and stone intrusion. poured sealants. The evaluation consisted of visual inspection on a foot-by-foot basis. The primary distresses for every sealant material, and the flushed and overband configuration which were used only for the hot-Three different sealant configurations were used for this study, the conventional recessed configuration used

be available in 1999. the recessed and overband configuration was among the best performing. The final results of this study will One product, Dow 888, out-performed all the other sealants. For the hot-poured sealant, Koch 9005 using

Principal Investigator: Ahmad Ardani Study Manager: Ahmad Ardani



SHRP - SPS-2 Experiment, Study of Structural Factors in Rigid Pavements

evaluated under the SHRP program until year 2007 include the following combination of factors: experiment include concrete thickness, concrete strength, base type, lane width, drainage and environmental environmental and structural factors on the performance of rigid pavements. The factors studied under this 13 different test sections on I-76, approximately 18 miles east of Denver. These test sections which are being factors such as temperature, moisture and soil type. CDOT participated in this national study by constructing The SPS-2 experiment was developed as a coordinated national experiment to address the effects of various

- Concrete thickness at two levels of 8 and 11 inches;
- ·14-day flexural strength of 550, 650 (state standard) and 900 PSI;
- Non-draining bases: lean concrete base (LCB) and dense graded aggregate base;
- Draining bases: permeable asphalt treated base with edge drain and transverse interceptor drain; and
- Lane width at two levels of 12 and 14 inches with untied shoulders.

greater slab warping under these conditions. conjunction with higher strength mixes (14-day 900 psi) show higher deflection, indicating the presence of inch sections, reflecting the relatively lower structural capacity of these sections. LCB sections, particularly in deflection magnitude of the widened lane and the state standard sections. Deflections are higher for the 8the ride quality for the sections. However, analysis of the deflection data reveals variations in load carrying capacity. Both widened lane sections and the state standard section with tied concrete shoulder exhibited Virtually no distress is evident in any of these sections at this time. Profile data indicates virtually no change lower deflections than those with untied shoulders. At present, no difference can be identified between the

while the 900 psi section's average is 34. The pavement surface of the 550 psi sections shows noticeable wear evaluation will determine if the 550 psi mix (lower cement content) in fact results in a shorter performance life, in the wheel paths exposing the aggregate, while the 900 psi sections exhibit very little surface wear. Future One interesting observation, friction data collected in June of 1998 by CDOT indicates a significant difference between the 550 and the 900 psi test sections. The average friction numbers for the 550 psi sections is 51, or improved friction quality.

Principal Investigator: Ahmad Ardani

Study Manager: Ahmad Ardani

Cracking in Bridge Decks: Cause and Mitigation


the maintenance costs and shortening service life. and allow moisture and deicing chemicals to reach bridge components that were previously well-protected by the deck. Extensive bridge deck cracking poses a serious risk to the durability of the entire bridge, increasing Cracking in bridge decks has become a serious concern in recent years. These cracks extend though the deck


eventually in the field on a trial basis. modified concrete mix designs and evaluate their resistance performance in the laboratory first and then the use of larger amounts of Type F fly ash in silica fume concrete. It recommended that CDOT use these sought to propose ways to improve existing concrete mixes to reduce the severity of deck cracking. Recomidentification of materials, construction, and design factors that influence deck cracking. The study also mendations of the first phase support the use of Type II cement, reducing the cement content in concrete and This research project will be completed in two phases. The first phase, already completed, looked at the

decks needs to be gathered. the current database is limited and additional information on the performance of newly constructed bridge procedure currently in use by CDOT is a step forward and effective for the control of deck cracking. However, In phase two of the project, currently underway, the researchers have found that the deck concrete curing

and will be crack mapped by CDOT-Research to assess the severity of the deck cracking problem with the deck was cast will also be reviewed and incorporated into the database. It is expected that the results of this concrete mixes currently being used by CDOT. The material, construction, and weather records at the time the As a result of this need, seven newly-constructed bridge decks in the metro Denver area have been selected study will assess the performance of current CDOT bridge deck concrete mixes and determine what outstanding bridge deck issues need further study.

Principal Investigators: Benson Shing, University of Colorado at Boulder and Naser Abu-Hejleh Study Manager: Naser Abu-Hejleh





LŢ.


Evaluating Performance and Design Assumptions of a Mechanically Stabilized Earth (MSE) Wall

structed. This MSE wall, developed by CDOT and the now defunct Colorado Transportation Institute, was built to support the traffic leaving I-25 north and connecting to I-70. The funding from this study will be used to For this particular project at 38th and Fox in metro Denver, a new, innovative retaining wall system was conevaluate the performance and the design assumptions of this MSE wall.

For this MSE wall, full-length panels were placed at specified amount of back batter and mounted in place tiebacks and welded wire fabric inserted in the backfill. The loosening of the flexible rebar bolts limits the with a couple feet of flow fill on the front and back. These panels are backfilled behind them with rebar earth pressure on panels, and allows wire fabric reinforced backfill to take the load. The MSE wall was instrumented at two locations with inclinometers and strain gages. Additional monitoring of the wall included survey measurements to observe vertical and horizontal movements. Wall movements and strains were monitored throughout the construction and continued until the entire project was completed.

provide important conclusions regarding the future design, construction, and use of this type of wall. If shown to be successful, the MSE wall can save money, resources and time in the construction of future projects. It is Currently analyses are being performed on the collected measured data and are being compared to the measured stresses and movements with predictions from the current design assumption. This comparison will estimated that this design saved the project up to \$500,000.

Principal Investigator: Jonathan Wu, University of Colorado at Denver



Calcium Nitrite Corrosion Inhibitor

CDOT Research staff, with a 3% sodium chloride solution have shown no electrochemical activity in two years of ponding. Preliminary findings indicate that calcium nitrite could be used as a possible alternative to epoxy-As current practice, epoxy-coated steel is being used by CDOT as the primary corrosion protection system for chemical added to the concrete mixture, may provide supplemental corrosion protection. Calcium nitrite has Colorado bridges. In some cases where severe steel corrosion conditions are expected, calcium nitrate, a been studied as a corrosion inhibitor and set accelerator for over twenty years. Test cells, constructed by coated steel in bridge decks. Benefits would include a shorter development length, ease of handling, less storage constraints than are necessary with epoxy coated steel and a reduced cost.

This study is evaluating a bridge deck constructed at Kettle Creek near Colorado Springs with half black steel measurements have been collected and no corrosion activity is occurring. Interestingly, preliminary results that have not been verified by CDOT, show the corrosion protection abilities of the concrete mixed with calnstalled in the deck and will be monitored at two-to-three year intervals. At present, two corrosion activity with calcium nitrite added to the concrete and half epoxy-coated steel. Corrosion monitoring devices were cium nitrite have increased since construction. Research has prepared a technical note on corrosion protection of embedded steel in Colorado on existing and new concrete bridges. This technical note was prepared to provide information and guidance to CDOT bridge designers.

Principal Investigators: Naser Abu-Hejleh and W.R. Grace

Reinforced Soil Abutment and Piers Demonstration


structures were constructed with a "roadbase" backfill and internally reinforced with layers of a woven geotextile. demonstrate the cost and functionality of geosynthetic reinforced backfill technologies as bridge supports. The Reinforced, dry-stacked hollow-cored concrete blocks were used as facing. In this study, two geosynthetic-reinforced soil bridge piers and one bridge abutment were constructed, seeking to

prediction of the movements of geogrid reinforced abutment in the new Founders/Meadows bridge over I-25. This were monitored. The satisfactory performance of the bridge abutment cleared the way for the design and for more traffic space along I-25. bridge is the first of its kind in the United States, and one of the many advantages of this structure is that it allows The west pier and the abutment structures were load tested and the movements of the facing and reinforcements

investigation and geotechnical analyses and identified the possible causes of this excessive movement. need for grouting the top four blocks, currently in CDOT specifications. A CDOT Research team conducted a field the concentrated surface loading near the edge of mechanically stablized earth walls. In addition, it supported the The top four feet of the west pier has moved outward. This behavior alerted our engineers to the importance of

when designing similar structures. structures movements, internal conditions, and material properties will be used as a reference by CDOT engineers durability of geotextile fabric buried in the structures for around thirty months will be evaluated. The measured the blocks, fabric, and backfill soil will be conducted. Additional field and lab testing will be performed. The Finally, the structures will be dismantled and removed, during which a forensic analysis of the internal conditions of

Principle investigators: Phase I - Jonathan Wu, University of Colorado at Denver, Phase II and III - Naser Abu-Hejleh




Working Loads The Performance of the Reinforced Soil Abutments of Meadows/Founders Bridge Over I-25 at

conservative due to the fact that it is the first of its kind in standard highway practices and the critical importo not only provide bridge support, but reduce bridge approach settlement. The design of this bridge is overly geogrid reinforced earth wall is the subject of this evaluation. The geogrid-reinforced foundation is expected tance of this structure to support six lanes over I-25. The construction of a shallow strip spread foundation supporting the bridge abutment and placed directly on a

bridge structure and roadway approach. project because the projected settlements of the foundations and the reinforced soil mass are small. This Bridge abutments directly supported on the reinforced soil mass are more economical and were used in this reinforced soil structure allowed for more space along I-25 and less differential vertical movement between the

sure vertical movement. The collected performance data will then be analyzed to achieve three objectives. clude pressure cells, strain gages, settlement transducers, and an inclinometer with magnetic plates to meamonitored at critical locations until the structure's long-term movements cease. Monitoring instruments in-The movements and stresses experienced by this structure under working loads at various stages will be

be to monitor the effectiveness of the reinforced backfill behind the abutment and the sleeper foundation in reducing bridge approach settlement. The third and final objective will be to assist the development of a under typical service loading conditions with prediction from current design procedure. The next objective will verified and calibrated computer model that can be used to later analyze and design critical mechanically The first objective will be to compare the measured stresses and movements experienced by the structure reinforced earth retaining walls under service load conditions. When complete, this study will provide conclusions regarding the future design, construction and use of reinforced soil abutments in Colorado.



Backfill of Earth Retaining Walls: Design Parameters and Construction Specifications

encompass a fairly wide range of different high-quality soils. While most Class 1 soils are suited for construction of with a backfill not meeting Class 1 criteria have shown satisfactory performance characteristics. Class 1 materials Class 1 material. However, field experience has indicated that many reinforced soil retaining walls constructed reinforced soil retaining walls, it is conceivable that some Class 1 soils may not be suitable backfill material The prevailing specifications for the construction of reinforced soil retaining walls require that the backfill be

for retaining walls. The possibility of using RAP for the construction of retaining walls is highly desirable since ances. The construction specifications should allow the design parameters to be efficiently verified in construction and construction specifications for earth retaining walls in general and for reinforced soil retaining walls in particusoil tests, and design is based on existing models. The second objective is to develop backfill selection guidelines and the design parameters of earth retaining walls, where construction acceptance is based on existing standard Colorado has an abundant supply of this material. The final objective is a preliminary feasibility study of employing reclaimed asphalt pavement (RAP) as a backfill lar. Various backfill selection criteria will also be developed for retaining walls with different performance toler-This study has three objectives. The first is to perform basic cost optimization between construction specifications

soils meeting the backfill Class 1 specifications. of a wide range of Colorado soils and aggregates instead of the current limit of using only high quality granular structures, even more savings are expected from this study. It is also expected that there will be better utilization resulted in significant savings. Since the backfill is the most expensive component of mechanically stabilized earth construction of earth retaining structures. Many internally reinforced soil projects constructed in Colorado have When concluded, this study will provide the necessary backfill soil information needed for the safe and economical

Principal Investigator: Jonathan Wu, University of Colorado at Denver Study Manager: Naser Abu-Hejleh

Evaluating Bedrock Bridge Scour Potential

Bridge foundations on sedimentary bedrock are currently designed by either treating the bedrock material as if it were noncohesive, as in the current FHWA guidelines, or using some other qualitative method to reduce the foundation depth to a more reasonable figure. A rational method is needed to quantify the scourability* of various bedrock materials, and thus have a more quantitative method of determining required foundation depths. This study will establish procedures to quantify the scourability of sedimentary bedrock and other cohesive and consolidated materials. The procedures will then be verified though laboratory testing.

*Scour is the removal of soils and rocks from streambeds and streambanks by the erosive action of flowing water that can result in bridge failure.

Principle Investigator: Steve Smith, Woodward Clyde

Effect of Magnesium Chloride on Asphalt Pavements - A Quick Study


investigate any potential problems associated with magnesium chloride. the bonding of overlays, crack filling, and permanent pavement marking. This quick study was authorized to last five years. And while successful for their intended purpose, these chemicals have been suspected to affect Anti-icing and deicing for snow and ice control using magnesium chloride have been used in Colorado for the

of field cores from highway segments where magnesium chloride had been used prior to overlays. used in Colorado. In all, a total of 18 samples were tested for shear strength. As can be seen in the graph, there are only minimal differences in shear strength. The study will be continued to investigate bond properties ducted for two asphalt mix designs and the two magnesium chloride suppliers (Envirotech and GMCO) that are and subsequently "overlaid" with the second layer. Control samples were not treated. The tests were con-One layer of these samples was immersed in representative solutions of magnesium chloride for three days, ratory experiment was conducted to measure the shear strength of two-layer laboratory compacted samples. ride or sodium chloride, would have similar effects because they are similar in chemical characteristics. A labomagnesium chloride, it is reasonable to assume that other chemical deicing substances, such as calcium chlo-A survey of other states revealed that these problems either do not exist, or the problems have not been attributed to the use of chemical deicing/anti-icing. Although most respondents had little or no experience with

markings and the effect that magnesium chloride may have on them. markings. CDOT is, however, going to do additional evaluations and will establish a test site for pavement In addition, there is currently no indication that magnesium chloride has had a negative effect on pavement

Principal Investigator: Werner Hutter Study Manager: Werner Hutter





■Control ■ Envirotech □ GMCO

High Altitude Snow and Ice Control: Effects on Water Quality


of magnesium chloride deicing material on plant life and water quality. mental concerns, and commercial interests. This three-year study is being conducted to investigate the effects Snow and ice control at high elevations in Colorado is a unique problem, requiring a balance of safety, environ-

Of particular concern is the survivability of the Boreal Toad (see below), a species that is normally indigenous no deleterious effects on either plant or aquatic life. 1999. All data to date indicate that the amount of deicing chemicals at concentrations used at this time have to northern regions. The research is 75% complete, with a final report to be published in the summer of

deicing material, but at the expected dilution rates, there appear to be no further contamination problems. Some concern had been voiced after the first year of the study in regard to heavy metal constituents in the

Principal Investigator: William Lewis, Western Environment Analyst

Study Manger: Werner Hutter



44 Boreal Toad

Effects of Cattails on Wetlands

Wetland mitigation is a federally-mandated program for highway projects. CDOT uses considerable funds to design, build, acquire water rights, and to purchase nursery grown plants for wetland mitigation. Unwanted cattail invasion compromises this effort and puts an additional financial burden on CDOT when the nursery grown plants are overrun by cattails.

which could affect growth patterns. Data analysis from field experiments will result in the development of a This study investigates the conditions under which a balanced growth can be established, by assessing the various water depths that are enhancing cattail expansion in addition to the evaluation of other variables, statistical model, which will facilitate the design of wetlands.

Principal Investigator: David Cooper, Colorado State University

Study Manager: Werner Hutter

ost of Sanding

much higher cost of these materials even though they are very effective under most conditions. providing safe passage for Colorado motorists. Recent use of chemical deicing has been limited due to the The traditional method for snow and ice control using a sand and salt mixture has been the mainstay of

potentially prove the chemical deicing materials to be competitive. associated with sand removal in guardrail locations and drainage maintenance. A cost/benefit analysis could limited to, issues concerning accelerated pavement wear, paint stripe deterioration, increased labor time currently not included in the cost figures but impact the maintenance budget. They include, but are not This research work will examine the complete cost of sanding. Many aspects of the sanding operations are

\$30 million dollars in Colorado. breakage, and paint damage to vehicles. They estimate that annual claims for windshield breakage are about The insurance industry has expressed a desire to participate in this study. Their concerns relate to windshield

surely impact the quantities applied to our roads. Although the use of sand and salt will probably continue, the increased use of alternate deicing materials will

Principal Investigator: N.Y. Chang, University of Colorado at Denver Study Manager: Werner Hutter

Hamburg Rut Tester Implementation

rado has become a pacesetter in asphalt testing across the country. The European equipment is considered the In 1991, Colorado was selected to demonstrate the European asphalt testing equipment. Since that time Colostate-of-the-art and is used for validating Superpave.

mixes as well as all of the Superpave mixes. The Hamburg rut tester is a device that allows true performance During the 1994 and 1995 construction season, Hamburg tests were performed on project-produced mix on most interstate projects in Colorado. In 1996, Hamburg testing was performed on 100 and 125 End Point Stress (EPS) resting of the various project mixes in an accelerated fashion. Since 1994, the Hamburg testing equipment has only been used for project bonuses. No correlation between the values obtained from the Hamburg testing equipment and field performance has been made.

during construction. Information from the project produced mix and the cores will help develop a correlation mance. The pavements selected were from projects that had had Hamburg testing on project-produced material In the fall of 1998, in-place cores were obtained from existing pavements to evaluate long-term field perforbetween Hamburg tests on project mix and actual field performance. The information obtained through this research will also be used to determine the proper test temperature for performance prediction. This performance prediction allows the European equipment to be implemented into the Colorado asphalt mix program, and will supplement the SHRP mix design and evaluation methods which were also implemented at the same time.

Principal Investigator: Skip Outcalt Study Manager: Skip Outcault

Evaluation of Slope Stabilization Methods

erosion control (in effect during the 60's) were applied to the cut and fill slopes created during construction. spring and summer, wash away the top layer of soil and prevent vegetation from establishing itself. vary in size to over two meters in diameter. The snowmelt runoff, combined with the severe rain storms of State highway 40, west of Berthoud Pass, as we see it now was built in the early 60's. Standard practices for These slopes consist of highly erodible and unstable sandy soils mixed with a large quantity of rocks, which

for the application on future projects in this and similar areas. Enhancement funds became available for the 1995 construction season to rehabilitate some of the eroded slopes. This project is testing various cost-effective erosion control materials and installation techniques to provide data

give designers more information on product usage for future projects that incorporate erosion control products in steep and rugged environments performance will be written during the fall of 2000. This report and the data collected during the study should zones. These three zones will be evaluated for constructability and overall performance on the better than 1 to Seventeen materials, from erosion mats and mulches to different tackifiers are being used within three work 1 slopes that are normal for Berthoud Pass. A construction report, "Evaluation of Slope Stabilization Methods: US-40 Berthoud Pass" CDOT-DTD-R-96-6 was published in March 1996. A final report documenting overall

Principal Investigator: Skip Outcalt Study Manager: Skip Outcalt



Sites with Promise

the analysis performed by the CDOT Accident Records and Analysis Group, show that this assumption is road is directly proportional to the amount of traffic. Recent research findings, independently confirmed by rates. The use of accident rate is based on the assumption that the number of accidents on a segment of Over the last 50 years of modern road building, highway safety has been measured in terms of accident invalid and often leads to poor investments into safety improvements.

ADT and accident count for a unit of road section over a unit of time. highway system. SPF accurately reflects the complex relationship between the amount of traffic measured in the process of developing Safety Performance Functions (SPF) for all road classes on the Colorado State To replace the accident rate based approach, the CDOT Accident Records and Analysis Group is presently in

mended for implementation. volved in the study will provide technical assistance in the development of the new Colorado-specific SSPF for and ranking candidate sites for safety improvement, known as Sites with Promise (SWIP) will be recomselected roadway classes and junctions. Following the development of the SSPF, a procedure for selecting tions (SSPF) that have been developed to date by CDOT. After the first stage is completed, members in-The first stage of this study will involve the examination and evaluation of Simple Safety Performance Func-

CDOT to a new level in its ability to identify and address locations with potential for safety improvement. The use of SPF in deciding what constitutes a genuine safety problem in need of remedial action will elevate

Study Manager: Skip Outcalt Principal Investigator: Jake Kononov, Safety and Traffic Engineering Branch and Dave Hattan, Felsburg, Holt, and Ullevig

Integration of Ramp Metering with Ramp Traffic Signals

This research project will develop traffic control strategies to coordinate ramp metering and the adjacent traffic signals to reduce delay and queue lengths on the ramp and nearby signalized streets. The effort will focus on hardware and software technologies in place, and will also consider several scenarios of improvements to the a core set of strategies, based on current ramp metering algorithms. The research is focusing on calibrating hardware and/or software. The benefits associated with each scenario will be investigated. The second half of the project will focus on testing a given set of strategies for two or three interchanges such as Belleview an existing simulation model on a limited basis to develop the potential control strategies based on current and I-25, Orchard and I-25, or any on south I-225.

Principal Investigator: Sarosh Khan, University of Colorado at Denver Study Manager: Rich Griffin

Parametric Cost Estimation Research

inconsistency was cited as an area of concern in a legislative audit report. covers both the accessibility of historic data and a method to analyze the data. During the development of the CDOT currently lacks a consistent source for estimating project costs at the sketch planning level. The lack last long-range statewide plan, a number of different methods were used to estimate project costs. This

reliable long-range multi-modal parametric cost estimates when little is known about the project. To address this problem, a company has been hired to establish methodologies to generate consistent and

Principal Investigator: Kathy Yelle and Roy Johnson, Info Tech Study Manager: Richard Griffin

I-70 West Link Travel Time Study

to travel from one section to the next) on the I-70 west corridor, Denver to Vail, based on vehicles used as instrumented with radio modem devices with built in GPS units to report locations at pre-specified intervals. probes. The Research program is funding phase two: instrumentation. In phase two, selected vehicles will be its performance for computing estimation of link travel times. The field instrumentation demonstration will test the algorithm prototype developed in phase one and evaluate This study will demonstrate a prototype system for estimating link travel times (the time that it takes a vehicle

tion of this nature be offered to the private sector to market a value-added service to the general public? Institutional issues and public acceptance will also be examined. For example, can public sector data collecWhat will be the value for the private shuttle operators to participate in this program? Will the public use the information, pay for it, and believe it?

Principal Investigator: Sarosh Khan, University of Colorado at Denver

Study Manager: Rich Griffin

Interaction Between Pedestrians and Vehicles Using Smart Signing

centerline for passenger pickup or drop-off. In other words, the buses will only drop-off the passengers on the Aspen. There are currently over 15 bus stops and a RFTA policy that does not allow for buses to cross the The Roaring Fork Transit Authority (RFTA) serves the communities along SH 82 from Glenwood Springs to side in which the bus is travelling. As a result, a number of informal pedestrian crossing areas have been created; a potential hazard on this high-speed highway. A possible solution to this problem is to provide real-time information to drivers regarding upcoming pedestrian activity. This research study will test the effectiveness of a pedestrian activiated warning sign. The effectiveness of the warning sign was established through speed and break-time studies with pedestrians present and various messages displayed. The research will determine the most effective message, the best method to activate the sign, and the driver and pedestrian response. Driver surveys were also conducted to determine the most memorable, effective warning message. Results of this research may be used to implement the system thoughout this corridor and other appropriate locations in the state. Part of the funding for this project was provided by Region 3.

Principal Investigator: CK Centennial

Study Manager: Rich Griffin

Cross Modal Performance Measures

comparisons between different modes of transportation. This framework and tools would be developed primarily for application at the rural and smaller-urban transportation planning region levels for utilization in longrange planning processes. This research is expected to establish a framework and the tools to provide a consistent means of making

projects, such as a transit project to a highway one, remain. Questions about how to make modal trade-offs and which measures to consider when comparing disparate had little experience in the performance trade-off and comparable costs of alternative modes of transportation CDOT's first effort at developing a multi-modal statewide plan was completed in 1996. However, CDOT has

contribute significantly to the comparison will be included. The research has currently identified five core accepted and understood by Colorado transportation planners and decision-makers, only components that sistent, yet practical in application. Since the focus of the research will be to develop a practical method tions for comparing different transportation modes that are sufficiently comprehensive and conceptually contation modes with an initial focus on the passenger component. The research intends to offer recommendacategories of performance measures; agency cost, safety, user cost, mobility and environment. This research will define a performance measures framework which allows comparisons across varied transpor-

in which the best practice approach and methodology are applied to Colorado situations. Computer spreadsheets and a manual have already been developed. The next step will be to do a case study

Principal Investigators: Sarosh Khan, University of Colorado at Denver and Larry Eubanks, the University of Colorado at Colorado

Study Manager: Rich Griffin



Effects of Geometric Characteristics of Interchanges on Truck Safety

perspective of large truck operations. In addition, there may be insufficient safety information alerting commany cases, these accidents may relate to the inadequate geometric design elements of interchanges from the mercial drivers of potential interchange problems. interchange areas comprise a much smaller percentage of total highway lane area (Firestine, et al. 1993). In National accident statistics show that up to 20 percent of truck accidents occur at interchanges, even though

motorists, a greater level of service will reduce congestion and a reduction in accident related vehicle impacts. reduce the frequency and severity of truck accidents. Overall benefits could include lessening the risk to all This project will determine potential improvement to interchange design specifications that could possibly

ards. The "before" period included the three years prior to installation of this signing in September of 1995 significantly more truck rollovers, on average, per unit of exposure at an interchange. Following the identificathis observational study are included in a 1999 report, now available. tion of this interchange, additional signing was installed to warn truck drivers of potential interchange hazbefore-and-after study was set up at the US 34 and I-25 interchange. This sight was selected because it had The "after" period included the three years from September of 1995 to September of 1998. The findings of To evaluate the effectiveness of the countermeasures applied at a problem sight in Colorado, an observational

Study Manager: Skip Outcalt Principal Investigator: Jake Kononov, Staff Traffic and Bruce Jansen, University of Colorado at Denver

Geofabric Interceptor Drains

groundwater intrusion below the pavement. In recent years, these interceptor drains have been wrapped with come clogged with sediment and how rapidly this occurs. Six groundwater-monitoring wells and a flow meter geofabric to prevent sediment intrusion. There is some question about whether or not these geofabrics bewere installed at the effluence of the interceptor drain, along the SH 34 bypass, immediately following con-Interceptor drains, also called underdrains or French drains, have been used for many years to prevent struction.

month. A small amount of water continued to flow from the underdrain after the taper-off period. Whenever Two periods of flow in the canal were recorded the summer of 1992. Each time the canal was shut off, flows the canal is full, flows have been running around thirty gallons per minute, which is twice what was expected. in the underdrain immediately began to taper off. After the second time, flows gradually tapered off for a This study is expected to be completed in the summer of 1999.

Principal Investigator: Tom Hunt, Region 6

Study Manager: Rich Griffin

Centerline Rumble Strips


equipment for grinding rumble strips into the center of the roadway hoping to reduce traffic accidents caused by SH-119 west of Boulder (Boulder Canyon) is a narrow winding road running approximately 20 miles from Boulder vehicles crossing over the centerline. This equipment grinds a 12-inch wide strip, 7 inches long, with 5 inches causing head-on accidents. During the spring of 1996, Region 4 hired a company that uses a new type of to the town of Netherland. This stretch of state highway has a history of vehicles crossing the centerline and between grindings by utilizing a compact diamond grinding tool attached to the front of the vehicle.


determine the effectiveness of the newly-placed rumble strip by comparing the accident data before and after placement. The Research Branch was asked to monitor construction of the rumble strip being placed with this new device and

in Colorado. This study will evaluate the safety effectiveness of such a treatment and potential roadway mainte-Rumble strips are known for their effectiveness on shoulders, but have never been used to delineate traffic lanes nance problems.

Principal Investigator: Dave Price Study Manager: Skip Outcalt

1996 - 1998 Completed Research Studies with Implementation Statements





CDOT/CTI-96-1

Colorado at Denver. This research was performed for and paid for by the Colorado Transportation Institute. The Colorado Long-Term Performance Tests of Soil-Geosynthetic Composites. Kanop Ketchart and Jonathon Wu, University of Transportation Institute closed in 1996.

of long-term behavior of soil-geosynthetic composites were developed. geosynthetic-reinforced (GRS) retaining wall. Both a modified performance test and a test procedure for the investigation This report describes the development of a testing device and test protocol to measure the performance of a

study. (For related implementation information see CDOT-DTD-97-2, "Long-Term Field Performance of Geosyntheticanalysis is the subject of current on-going research studies conducted by CDOT, and has been proposed for a new NCHRP sumed in conventional analysis. The development of a rational, verified, and simple analysis to replace the conventional Reinforced Soil Retaining Walls.") Implementation statement: This study showed that soil-geosynthetic composite behavior is different than what is as-

CDOT-DTD-SDHYD-R-96-2

experimental feature. The research was performed by Staff Bridge. Erosion Control Project. Rick Moser, Staff Bridge. This report is a courtesy printing of a project evaluation of an Efficiency of Sediment Basins: Analysis of the Sediment Basins Constructed as Part of the Straight Creek

constructed and monitored on an area between I-70 and Straight Creek. The sediment basins were successful in removerosion, sedimentation, and water pollution caused by runoff from highway systems. Eleven sediment basins were This study reviews sediment basin construction and their efficiency at controlling the adverse environmental impacts of ing the majority of sediment from the runoff, capturing 985 tons of sand and sediment.

the sediment basins in other locations. <u>Implementation statement:</u> This report is being used as a resource document for the possible use and/or placement of

CDOT/CTI-96-3

J.T.H. Wu, University of Colorado at Denver. This research was performed for and paid for by the Colorado Transporta-Backfill Walls. William Schiebel, CDOT; Albert Ruckman, MSB Design and Construction; Robert Barrett, CDOT; and The Roles of Facing Connection Strength, Truncated Base, and Embedment in Mechanically Stabilized tion Institute. The Colorado Transportation Institute closed in 1996.

mechanically stabilized backfill (MSB) walls. One of the walls featured concrete blocks, the other featured blocks made of compressed rubber tire chips. These walls experienced minor deflection and the embedment, or non-embedment of This report documents the performance of two 15-foot high geosynthetically-reinforced, block-faced earth features or the walls, has had no effect on the stability of the constructed walls.

(MSE) * walls has resulted in waiving the AASHTO connection requirement in the CDOT revision of section 504 as follows: Implementation statement: CDOT research on the role of facing connection strength for mechanically stabilized earth "for low strength geotextile or woven geofabric reinforced walls, except for the top one block, every block shall be connected by friction with either a main or a tail reinforcement...."

program can be used to check the truncated base design. Staff Bridge is considering a truncated base wall design for a analysis method is needed to check the design of the truncated base. A finite element program and/or a slope stability secondary road. This project can be set up as an experimental project to have the Research Branch monitor its perfor-In a current study with Dr. Wu, guidelines for allowing the use of truncated MSE bases will be developed. A numerical

CDOT design engineers comprehended our research findings that the embedment is not relevant for the internal stability analysis of MSE walls but could be critical for global stability analysis. Therefore, for MSE walls with no global stability problem, CDOT specifications limit the embedments to just 18" for the scour protection of the leveling pad

*While the report refers to MSB (backfill) walls, the preferred terminology now refers to them as MSE (earth) walls.

CDOT/CTI-96-4

Erosion Control and Revegetation Techniques Using Mechanically Stabilized Earth Slopes. William Schiebel, CDOT; Albert Ruckman, MSB Design and Construction; Robert Barrett, CDOT; and Jeff Rodencal, Tensar Earth Technolo-Institute closed in 1996 This research was performed for and paid for by the Colorado Transportation Institute. The Colorado Transportation

study were effective in reducing soil loss on 1:1 slopes to a negligible amount. slopes. Two geogrid reinforced embankments were constructed to provide test slopes with a 1:1 grade, each with a controlled in all test sections regardless of the success of the vegetation. The erosion control systems described in this provided to supplement precipitation as necessary to establish plant growth. Sediment loss from the test slopes was aesthetic options are needed, the vegetation MSE slope should be considered due to its lower cost if irrigation can be north, south, east, and west exposure. The report recommends that when spatial restrictions will allow and where This CTI research reviews commonly used erosion control and vegetation techniques on mechanically stabilized earth

possible alternative. <u>Implementation statement:</u> This technique has not been used on a CDOT project due to lack of information on this

CDOT-R-CSU-96-5

State University. Roadside Vegetation Management. Paul Kohlhepp, Thomas Sanders, Cara Tackett, and Richard Walters; Colorado

a review of the 1990 "Roadside Appearance" chapter of the CDOT Maintenance Manual and additional information obtained from seven states, two Colorado counties and a report by Auburn University. This technical report documents roadside vegetation management practices recommended for CDOT. The report includes

everyday use by CDOT Maintenance. It is available for reference in the CDOT Transportation Library. Copies were sent to Maintenance Sections statewide. <u>Implementation statement:</u> Although accurate and comprehensive, the manual was too academic and unrealistic for

CDOT-DTD-R-96-6

Evaluation of Slope Stabilization Methods (US-40 Berthoud Pass). Construction Report. David Price.

This study is evaluating sixteen erosion control materials and installation techniques on Berthoud Pass. The materials being studied included erosion mats, mulches, and tackifers on three work zones. Each is being reviewed on their constructability and performance on the 1:1 slopes particular to this area. Implementation statement; This is a construction report only, however, the research completed to date has been used for further stabilization projects on SH-40 Berthoud Pass.

CDOT-DTD-R-96-7

SMA (Stone Matrix Asphalt): Colfax Avenue Viaduct. Construction Report. Tim Aschenbrener, Staff Materials and Donna Harmelink.

the second project in Colorado to use the European SMA. Evaluations are continuing and a final report on all SMA projects This construction report documents and evaluates the placement of SMA on the Colfax Avenue viaduct. This project was is expected in 2000.

<u>Implementation statement: Since CDOT's first SMA project in 1994, SMA has been used in limited projects very success-</u> fully. Currently a Task Force is developing a position statement for the appropriate use of SMA to incorporate into the CDOT Design Manual.

CDOT-DTD-R-96-8

Randolph Reyes, Charlie MacKean, and Tim Aschenbrener, Staff Materials. This report is a courtesy printing of a report Determining the Asphalt Cement Content of Bituminous Mixtures Using the NCAT Asphalt Content Oven. completed by and for Staff Materials.

was selected. The research resulted in several recommendations being made. These recommendations were incorpowere evaluated and the procedure that resulted in the most accurate and precise method of AC content determination content oven, or ignition oven, was the objective of this research. Numerous bituminous mixtures from paving projects rated into CDOT CPL-5120 "Determination of the Asphalt Binder Content of Bituminous Mixtures by the Ignition Method." Developing a test procedure for accurately measuring the AC content of bituminous mixtures using the NCAT asphalt

CDOT-R-96-9

This report is a courtesy printing of a report completed by and for Staff Materials. HBP QC & QA Projects Constructed in 1995 under QPM1 and QPM2 Specifications. Bud Brakey, Staff Materials.

and quality assurance (QA & QC) specifications. Meeting and/or exceeding these specifications is tied to incentive payule and more stringent requirements. update reviews the addition of a QC & QA Standard Special Provision that created a greater disincentive payment schedments to the contractor. Failure to meet these specifications can result in a reduction of payment to the contractor. This report is the forth annual update of a pilot project to construct hot bituminous pavements (HBP) under quality control

CDOT-DTD-R-96-10

Long-Term Performance of Accelerated Rigid Pavements, Project CXMP 13-0006-07. Ahmad Ardani.

of faults, a profile measurement, a distress survey, and a set of falling weight deflectometer measurements. Continued was completed in 1989. The evaluation of this project lasted seven years and included visual inspections, measurements use of the fast track concrete paving technique is recommended. Described within this report is the post-construction evaluation of a fast track pavement project in Sterling, Colorado that

conventional concrete pavement. CDOT has been using fast track concrete pavement construction primarily in urban settings to reduce construction time and minimize traffic delays for the travelling public. <u>Implementation statement:</u> The results of this study demonstrate that fast track concrete pavement can be as durable as

CDOT-DTD-96-11

Determining the Degree of Aggregate Degradation After Using the NCAT Asphalt Content Tester. Randolph Reyes, Staff Materials. This report is a courtesy printing of a report completed by and for Staff Materials.

Content Tester, or ignition oven. The evaluation found that the NCAT Asphalt Content Tester may be used for determining With the EPA phasing-out the use of solvents to remove asphalt cement from bituminous mixtures to perform aggregate place and measured the possible degree of degradation after bituminous mixtures were heated inside the NCAT Asphalt gradations of bituminous mixtures and that it can replace the use of chlorinated solvents in determining AC content and aggregate gradation. However, correction factors will be required for aggregate that degrades inside the NCAT Asphalt gradations, an alternative method for this process was needed. This study determined if aggregate degradation took Content Tester.

CDOT-DTD-96-12

Evaluation of Rumble Treatments on Asphalt Shoulders. David Price.

This study evaluated the effectiveness of two types of rumble strips constructed on roadway shoulders. Rumble strips are leaving the roadway. The report concludes that both the rolled rumble strips and chip seal type rumble strips should be a textured treatment constructed on the shoulder of the road to provide an auditory and vibratory warning to drivers considered for installation when a payment is being overlaid.

Implementation statement: The results of this study were incorporated into Colorado M-standard M-614-1 - Rumble

CDOT-DTD-97-1

Avalanche Forecasting Methods: Highway 550. Arthur Mears, Arthur Mears, Inc.

sought to investigate parameters that may be important in forecasting avalanches on Highway 550 and to suggest how This research project developed a methodology for calculating the severity of a particular avalanche activity. The study

directly relates the probability of a vehicle being hit by an avalanche. The study also recommends a continued quantificaan automated weather station. tion of avalanche activity data collection after storm events, shear strength tests of snowpack, and the establishment of maintenance requirement to keep the road open, the length parameter is a better measure of hazard because it more centerline covered, volume of avalanche debris and the avalanche activity index. While volume is a better measure of they may be used to forecast avalanches in the future. Results of the study show a positive correlation between length of

mitigation program at CDOT. <u>Implementation statement:</u> Findings from this study were used to establish the current avalanche forecasting and hazard

CDOT-DTD-R-97-2

Hirsh, and Holly Hodges; University of Colorado at Denver. Ground Access Assessment of North American Airport Locations. Lawrence Cunningham, James Gerlach, Mary

customer needs. Where market share for public transportation is strong, two key factors have been assessed: origin/destination and concludes that access plans are often implemented without the benefit of sufficient knowledge of the markets they serve. study showed that public transportation alternatives to airport ground access do not capture large market shares. It also counties which are planning and operating multi-modal ground access systems would have application for Colorado. This tation planning is applied to varied transportation systems. It was expected that the experiences of other states and This research investigated ground access projects at other airports in North America to identify how multi-modal transpor-

ments in developing and updating transportation plans in the Denver Metropolitan Area. <u>Implementation statement:</u> This report was used for background information by the Denver Regional Council of Govern-

CDOT-DTD-R-97-3

Special Polymer-Modified Asphalt Cement. Donna Harmelink.

clude when a polymer is needed or whether it is cost effective. The introduction of the SHRP performance graded asphalt binder will make it easier for CDOT to better evaluate the effects of both temperature and traffic and their relationship to The study indicated that cracking is reduced when polymer-modified asphalts are used, however, the study did not conperformance of the roadway in relation to rutting and cracking as compared to CDOT standard mixes without modifiers. This research project evaluated and compared the effectiveness of polymer-modified asphalt mixes in improving the performance grading.

CDOT-DTD-R-97-4

Avalanche Detection Using Atmospheric Infrasound. A.J. Bedard, Jr., National Oceanic and Atmospheric Adminis-

results were encouraging, but further testing is necessary to better define the sound patterns produced by avalanches. At This report documents the testing of an infrasound detection system to detect snow avalanches in the southwest mountains of Colorado, due to the belief that snow avalanches produce sounds in the .5 to 5.0 Hertz range. hat time this type of system could be used in conjunction with a motorist warning system.

research funding priorities have not placed this avalanche detection system high enough to complete its development. <u>Implementation statement:</u> Follow-up research is still needed to develop this system into a viable product. To date,

CDOT-DTD-R-97-5

Experimental Evaluation of a Keyed Concrete Curb. William (Skip) Outcalt.

Keyed curbs are tied to the pavement by a key formed when the concrete curb is slip formed over a groove or "keyway" This report is a product evaluation of an experimental feature, keyed curbs, installed on US 24 in Colorado Springs.

that has been milled into the surface of the pavement. There is no sidewalk or fill behind the curb to add support; the will also prove useful when installed on a shoulder of a road where water needs to be diverted to be effectively drained. CDOT has had a design detail for using the keyed curb as an alternative to standard methods. The most effective use of a keyed curb relies completely on the concrete and the keyed joint with pavement for its strength. As of January, 1997, keyed curb is on an existing pavement, where curbs are desired after construction has been completed. The keyed curb

CDOT-DTD-R-97-6

Evaluation of the Iowa Vacuum Tester. Interim Report. William (Skip) Outcalt.

date the vacuum tester has only been tested in warm weather. The final evaluation will focus on the performance of the soapy solution and cause it to bubble. This study compares the results of evaluating the seal with the Iowa Vacuum with a soapy solution and applying a vacuum to the wetted area. If there is a failure in the seal, air will mix with the Iowa Vacuum Tester during cold weather. *(For the final report on the evaluation of the Iowa Vacuum Tester, see CDOT*promise in evaluating joint seals on new construction sites, especially when combined with pull tests of the sealant. Too The Iowa Vacuum Tester is an apparatus that is used to detect defects in joint seals. The test involves wetting a joint DTD-R-98-5.) Tester with the results obtained by an experience visual evaluator. The Iowa Vacuum Tester appears to have the most

CDOT-DTD-97-10

of Colorado at Denver. Loading Test of GRS Bridge Pier and Abutment in Denver, Colorado. Kanop Ketchart and Jonathan Wu, University

presents numerous measured results and discussions of those measured results. examine the performance of GRS bridge abutment and piers when constructed in a less stringent condition. The report long-term performance of such a bridge support system under a sustained design load. The third objective was to support system, including an abutment and a pier, subject to design loads. The second objective was to investigate the The objective of this research was threefold. The first objective was to investigate the performance of a GRS bridge <u>Implementation statement:</u> The outstanding performance of the reinforced bridge abutment in this study cleared the way for the design of geogrid-reinforced abutments in the new Founders/Meadows bridge over I-25. This bridge was the first stration project also gave CDOT design engineers a tool to predict the movement of the Founder/Meadows bridge. of its kind built in the US. One of the features of this design is that it allows for more traffic space under it.

rated in CDOT specifications. CDOT and Colorado county design engineers are encouraged to consider MSE pier construcnear the edge of the MSE walls. The study also supported the need for grouting the top four blocks, a practice incorpo-The observed behavior of the fortress pier alerted our engineers to the importance of the concentrated surface loading tion in remote areas with difficult access by heavy equipment and for temporary needs.

CDOT-DTD-97-11

Synthesis on Faulted Pavements at Bridge Abutments. George Hearn, University of Colorado at Denver.

abutments. This synthesis collected and evaluated existing information and identified the need for new and/or expanded Phase I of a three-phase research project. (Editor's note: No additional phases were completed or are expected to be information on the cause of faults and existing technologies for the mitigation of faults. This synthesis was considered differences in elevation of approach pavements and bridge decks caused by unequal settlement of embankments and This synthesis showcases literature on the problem of faults in roadway pavements at bridge abutments. Faults are completed at time of publication.) Implementation statement: While this study was underway, CDOT began a standard practice of using "flow-fill" for bridge approaches to control faulting. Since this process generally controls the faulting problem, interest in completing the next phases of this study was not supported.

CDOT-DTD-97-12

Wu, University of Colorado at Denver Long-term Field Performance of Geosynthetic-Reinforced Soil Retaining Walls. Phillip E. Crouse, Jonathan T.H.

creep deformation of a GRS wall beyond the measurement period. It was concluded by the study that all GRS retaining walls with granular backfill deform very little due to creep and were stabilizing with time. It also found that the current field. After an extensive literature review and survey, seven GRS retaining walls were selected for this study. Wall perfordesign methodology to account for creep is overly conservative when well-compacted granular backfill is employed. mance was assessed using a conservatism index (CI). In addition, an analytical equation was developed for predicting This study synthesized long-term performance data of full-scale geosynthetic-reinforced soil (GRS) retaining walls in the

on the durability of geosynthetic materials, will eventually be incorporated into AASHTO specifications. developed new protocols for confined creep testing of geosynthetics for highway applications. The FHWA report indicates sion/Creep Testing of Geosynthetics for Highway Application" FHWA-RD-97-143 recognized CDOT research findings and a strong impact of the use of reinforced soil technology. The FHWA report "Development of Protocals for Confined Extengranular and fine soils. Although CDOT research findings contradict current AASHTO specifications, this research has had in CDOT research reports nearly ten years ago. The results of the FHWA report, which is part of a comprehensive study that the confinement of geosynthetic reinforcement significantly limits the creep response. This phenomena was reported <u>Implementation statement:</u> CDOT has conducted extensive research on the creep of geosynthetic material confined in

ments. This new percentage is reflected in the new CDOT specification on creep, still in the review process, and has been used on at least one project. With this new specification, CDOT has adopted one of the highest creep factors in the US. The CDOT structure committee voted to relax the creep factor and raise it by 30% for geogrid and geotextile reinforce-

CDOT-DTD-R-98-1

I-76 Truck Study. David Price.

This evaluation reviews the performance of a 140-mile section of I-76 in northeastern Colorado. This section of road was pavement distress between the two lanes and may be a temporary measure to prolong pavement life until reconstruction under evaluation because the region office had placed signs along the highway asking truck traffic to use the passing, or left lane, while travelling on this section in order to prolong the pavement's life. Moving the truck traffic did not show a definite advantage or disadvantage in increasing the life of the outside passing lane. It did, however, balance out the can begin. <u>Implementation statement:</u> The procedures followed in this study have also been used for prolonging the pavement life in areas along eastern I-70.

CDOT-DTD-R-98-2

HBP Pilot Void Acceptance Projects in Region 2 in 1997. Interim Report. Bud Brakey, Staff Materials. report is a courtesy printing of a report completed by and for Staff Materials.

completed. The report has numerous conclusions and recommendations including the continued use of and increasing the This report covers three current void acceptance (VA) projects and compares them with previous VA and quality assurance and quality control (QA & QC) projects. It also summarizes all of the twelve VA projects, including nine that have been number of VA pilot projects.

CDOT-DTD-R-98-3

1997 HBP QC for Pay Pilot Projects with Void Acceptance. Interim Report. Bud Brakey, Staff Materials. This report is a courtesy printing of a report completed by and for Staff Materials.

addition, a special incentive pay formula, based on quality level analysis (QLA) of VMA and VA, was included. some contractors. CDOT did not assess disincentive payments for pay factors of less than 1.0 for void properties. In includes tests for determining the percent of air voids (AV) and voids in the mineral aggregate (VMA) which did worry basis for payment for the usual three elements - asphalt content, in-place density, and gradation. This new specification tion season. Standard QC & QA HBP specifications were modified to make QC test (instead of CDOT acceptance) the CDOT, with assistance from industry, wrote a pilot for quality control for pay (QCFP) specification for the 1997 construc-

CDOT-DTD-R-98-4

& Final Report. Bud Brakey, Staff Materials. This report is a courtesy printing of a report completed by and for Staff Hot Bituminous Pavement QC & QA Projects Constructed in 1997 Under QPM 2 Specifications. Sixth Annual

recommended for HBP QC & QA program. rank the contractor's performance. The QL specifications are performing satisfactorily and no significant changes are pavement density) and the item composites are summarized. The QL determines the pay factor (PF) and is also used to pleted in 1997 – the third season using the specifications. The QL for the elements (sieve analysis, asphalt content, and This report presents tables and figures which summarize the HBP quality level analysis (QL) for QA & QC projects com-

CDOT-DTD-R-98-5

Evaluation of the Iowa Vacuum Tester. William (Skip) Outcalt

the construction report on the Iowa Vacuum Tester, see CDOT-DTD-R-97-6., recommended. The tester is probably most useful in determining if seals on new projects will perform adequately. (For in the seal, air will pass through and bubbles will form on the top of the surface. The use of the Iowa Vacuum Tester is To use the Iowa Vacuum Tester you must first apply a soapy solution to an area and then the vacuum. If there is a failure evaluation of the Iowa Vacuum Tester here in Colorado and its comparison to results obtained by visual inspection only. The Iowa DOT developed the Iowa Vacuum Tester to determine if and where joint seals are leaking. This report is an Implementation statement: The Iowa Vacuum Tester is available for use by CDOT personnel. Contact Skip Outcalt at (303) 757-9984 if you would like a demonstration or would like to borrow the equipment.

CDOT-DTD-98-6

Simulation of 12 High Geosynthetic Reinforced Retaining Walls Under Surcharge Loading by Centrifuge Testing. James Klamerus and Hon-Yim Ko, University of Colorado at Denver.

under surcharge loading. Only one centrifuge showed signs of catastrophic failure so it is difficult to draw general conclusions on the failure performance of other tests. However, centrifuge modeling of geosynthetic reinforced retaining walls is This report examines thirteen centrifuge model tests on geosynthetic reinforced retaining walls. These tests determine the effects of backfill type, reinforcement shape (length), and degree of saturation on displacement and mode of failure considered to be a cost-effective method of producing meaningful results for developing a rational theory of safe and economical design guidelines.

stabilized earth walls that do not fail even under a high gravity level. The only centrifuge test that failed was when fat clay <u>Implementation statement:</u> While this research was not conclusive in its results it did show how to design mechanically was used as the reinforced backfill. This alerted CDOT to limit the amount of clay particles in backfill materials. CDOT specifications have strict limits on the percentage of -#200 sieve and the plasticity index of backfill materials.

CDOT-DTD-R-98-7

Colorado Study on Transfer and Development Length of Prestressing Strand in High Performance Concrete Box Girders. Daniel Cooke, P. Benson Shing, Dan Frangopol, University of Colorado.

prestressing strands spaced at 51 mm (2 in) on center in high performance concrete. The transfer length was determined This study reports on an investigation on the transfer and development lengths of Grade 270 (15.2 mm/.6 in) diameter by measuring concrete surface strain with mechanical strain gages. The development length was measured using an terative testing process involving six flexural tests. The development length for these girders was determined to be

girders by 18%, and the development length by 53%. approximately 1524 mm (50 in). It was concluded that the ACI/AASHTO formulas over-estimate the transfer length of the

CDOT-DTD-98-8

Particulate Matter from Roadways. Chatten Cowherd, Midwest Research Institute

characteristics and fine particle emissions and evaluates the emission control measures that reduce road surface silt sible for a large share of reetrained dust emissions. It is now believed that sanding may cause up to 60-80% of winter loading. Several types of field studies were used in performing this research. The study found that sanding was responreentrained dust emissions, approximately double what had been previously thought. This report presents the results of research to determine the relationships between the paved roadway surface dust

along with a decrease in the application of sand and salt. A follow-up study funded jointly by local governments, the ing the effectiveness of alternative deicing materials and sweepers. Denver Regional Council of Governments (DRCOG), CDOT, private sources and the Regional Air Quality Council is evaluat-<u>Implementation statement:</u> The results from this intensive study support the continued increase in chemical deicing,

CDOT-DTD-R-98-9

Evaluation of Design-Build Practices in Colorado, IR (CX)70-4(143). Interim Report. Ahmad Ardani and Paul Jesaitis, Region 1.

and examine its overall applicability to CDOT. A final report will be issued 90 days after the completion of the project. Airpark Road East. The goal of this research is to identify and document the pros and cons of the design-build practice mental Project No. 14, the FHWA approved the design-build concept to be used for the 12-mile reconstruction of I-70 from This report summarizes the construction activities of a design-build project in CDOT's Region I. Under the Special Experi-

Implementation statement: The use of design-build methodology for awarding construction projects looks promising

However, there is room for improvement in a fully implemented design-build concept. When early completion of a project is of significant value, design-build for project delivery becomes very attractive. For simple design-build projects with welldefined end results, the low-bid process is still the ideal since it minimizes the review of voluminous technical proposals. For larger and more complex design-build projects the "best value" concept (not necessarily the lowest bid) is more appropriate. The best value concept encourages innovation and allows the contractors to optimize their work force, equipment and schedules.

CDOT-DTD-R-98-10

Guidelines for the Thickness Design of Bonded Whitetopping Pavement in the State of Colorado. Scott Tarr, Matthew Sheehan, Paul Okamoto, Construction Technology Laboratories, Inc.

including an overview of the selected sites, design parameters, instrumentation, data acquisition, and analysis. Equations allows the evaluation of whitetopping thickness and joint spacing. A modified procedure was developed incorporating an subgrade modulus of 150 pci is required along with a asphalt thickness of 5 inches. However, these conclusions need to were developed to predict the critical stresses and asphalt strains. A mechanistic design procedure is described which This report summarizes the development of procedures for the thickness design of bonded whitetopping pavements empirical approach based on the number of equivalent single-axle loads. The research concludes that a minimum be verified by future work and the long-term performance of test sections. Implementation statement: The newly-developed procedures for the thickness design of whitetopping have been used on a few whitetopping projects in Colorado. Prediction models developed during this research are part of a first-generation procedure which needs to be fine-tuned and validated after the collection of additional data from future projects.


Edited by:


Beth Moore


Contributors:

Naser Abu-Hejleh Ahmad Ardani Richard Griffin Donna Harmelink Werner Hutter Beth Moore Skip Outcalt Joan Pinamont Dave Price

Photo credits pages 2, 13, 54 Gregg Gargan







Colorado Springs. For the related write-up and a photograph of the completed project see page 38. Reinforced soil abutments are under construction at the Meadows/Founders bridge over I-25 in